



PRODUCT PORTFOLIO

FLOOR COVERINGS 2023

creating better environments



FLOORING SYSTEMS

NUWAY
ENTRANCE
FLOORING

CORAL
ENTRANCE
FLOORING

MARMOLEUM
NATURAL
LINOLEUM

MARMOLEUM
MODULAR
NATURAL
LINOLEUM TILES

OFF THE
FLOOR
LINOLEUM

ALLURA
LUXURY
VINYL TILES

MODUL'UP
ADHESIVE
FREE VINYL

ETERNAL
HETEROGENEOUS
VINYL

SPHERA
HOMOGENEOUS
VINYL

STEP
SAFETY
VINYL

WETROOM
SOLUTIONS

SARLON
ACOUSTIC
VINYL

COLOREX
STATIC
CONTROL
FLOORING

TESSERA
CARPET TILES

FLOTEX
FLOCKED
FLOORING

BESPOKE AND
DESIGNER
COLLECTIONS

FURTHER
INFORMATION

A photograph of a modern outdoor lounge area set in a lush forest. The scene features contemporary furniture including a dark grey sofa with orange cushions, a matching armchair, and a side table. A green carpet is laid out on the ground. The background is filled with tall, slender trees and sunlight filtering through the canopy.

MAKING SPACES INTO PLACES...

We like to think that the floor coverings that we design and manufacture provide an inspirational basis for interior designs. We aim at helping you create inspiring and high performing interiors which leave lasting impressions. With Forbo you get more than a floor.

CONTENTS



INTRODUCTION 4

This is our world	4
Our design	6
Our environment	8
Our logistics	12
Our products	14
Entrance Flooring Systems	14



ENTRANCE FLOORING 18

NUWAY	18
Nuway at a glance	18
Nuway Tuftiguard	20
Nuway Tuftiguard HD	24
Nuway Connect	28
Nuway Grid	34
CORAL	
Coral at a glance	38
Coral Brush	40
Coral Classic	41
Coral Welcome	42
Coral Duo	43
Coral Luxe	44
Coral Grip	45
Coral Click	46
Coral Bright	47
Coral Interior	48



MARMOLEUM 50

Marmoleum at a glance	50
MARBLED	
Marmoleum Fresco / Real / Terra / Vivace / Splash	54
Marmoleum Ohmex	58
Marmoleum Acoustic	59
Marmoleum Decibel	60
Marmoleum marbled sheet options by colour	61
Marmoleum Sport	62
SOLID	
Marmoleum Cocoa / Marmoleum Walton	64
Marmoleum Piano	65
Marmoleum Concrete	66
Marmoleum Slate	67
LINEAR	
Marmoleum Striato	68
MODULAR	
Marmoleum Modular at a glance	72
Marmoleum Modular Lines	74
Marmoleum Modular Textura	75
Marmoleum Modular Shade / Slate	76
Marmoleum Modular Colour / Marble	77
Marmoleum Click	78
OFF THE FLOOR	
Off the Floor Marmoleum at a glance	81
Bulletin Board	82
Furniture Linoleum Desktop	83



SHEET VINYL & LVT 84

PROJECT VINYL	
Project vinyl at a glance	84
ALLURA	
Allura at a glance	86
Allura Dryback	92
Allura Flex	99
Allura Click Pro	105
Allura Puzzle	107
Allura at a glance	108
Allura Decibel	113
Allura Colour Plus	118
SPHERA	
Sphera at a glance	120
Sphera SMART technology	122
Sphera Element	124
Sphera Energetic	126
Sphera Elite	128
Sphera SD EC	130
ETERNAL	
Eternal at a glance	134
Eternal Wood	136
Eternal Material	140
Eternal Colour	142
Eternal Original	144
Eternal de Luxe	146
SARLON	
Sarlon at a glance	148
Sarlon Wood	152
Sarlon Material	153
Sarlon Graphic	156
Sarlon Colour	159
MODUL'UP	
Modul'up at a glance	164
Modul'up Wood	168
Modul'up Material	170
Modul'up Graphic	172
Modul'up Colour	175
STEP	
Step at a glance	180
Step applications	182
Surestep Original	184
Surestep Star	186
Surestep Steel	186
Surestep Material	187
Surestep Wood	188
Surestep Laguna	189
Safestep R11	190
Safestep R12	190
Surestep Decibel	191
Surestep Digital Print	192
WETROOM	
Surestep at a glance	194
Surestep Laguna	196
Safestep Star Barefoot	196
Surestep Aqua	197
Onyx+	198
COLOREX	
Colorex at a glance	200
Colorex SD, EC, plus	204
SPORTLINE	
Sportline	207



TESSERA CARPET TILES 210

CARPET TILE	
Tessera at a glance	210
Tessera Inline	212
Tessera Cloudscape	213
Tessera Basis Pro	214
Tessera Create Space 1	216
Tessera Barcode	217
Tessera Diffusion	218
Tessera Struktur 1	219
Tessera Struktur 2	221
Tessera Perspective	223
Tessera Infused	224
Tessera Layout & Outline Planks	226
Tessera Contour	228
NEEDLEFELT	
Needlefelt Akzent	232
Needlefelt Markant	233
Needlefelt Markant Graphic City	234
Needlefelt Forte Tile	235
Needlefelt Forte	236
Showtime Colour	239
Showtime Graphic	240



FLOTEX FLOCKED FLOORING 242

Flotex at a glance	242
COLOUR	
Flotex Colour at a glance	246
Flotex Colour Metro, Penang, Calgary, Canyon	248
Flotex Colour Embossing Highlight	254
NATURALS	
Flotex Naturals	256
OTHER FLOTEX COLLECTIONS	
Flotex Stratus	260
Flotex Cirrus	260
Flotex Cityscape	262
PLANKS	
Flotex Ombré	266
Flotex Montage	267
Flotex Frameweave	268
Flotex Converge	269
Flotex Refract	270
Flotex Triad	271
Flotex Box-Cross	272
Flotex Seagrass	273
Flotex Concrete	274
Flotex Marble	275
Flotex Wood	276



BESPOKE AND DESIGNER COLLECTIONS 278

FLOORCOVERINGS CREATED BY	
Index Floorcoverings created by	278
Flotex by Starck - Vortex	280
Flotex by Starck - Artist	281
Flotex by Starck - Twilight	282
Flotex Tibor	283
Flotex Sottsass	293
Created by José Medina Galeote	298
Mac Stopa	304
CUSTOM FLOORING	
Index custom flooring	311
Flotex vision	312
Eternal bespoke	312
Designing with Marmoleum	314
Coral Logo	316



FURTHER INFORMATION 318

Further information	318
Online services	320
Archldea magazine	322
Sample service	323



THIS IS OUR WORLD

An impressive and functioning interior starts from the floor up

At Forbo, we're passionate about Flooring. We produce the largest range of sustainable floor coverings in the world and supply total solutions for every area in every type of building.

This single source solution overcomes the need for multiple supplier visits and ensures total accountability across the project, giving you peace of mind. Also, as Forbo Flooring Systems has been awarded a place on a Crown Commercial Services framework agreement for floor coverings, you can be confident that we can also save you valuable time and money.

We like to think that the floor coverings we create provide an inspirational basis for interior design. We aim at helping to build brands and create lasting impressions. With Forbo you get more than a floor.

A SHOWCASE OF COLOUR AND FUNCTION

Our design

Our collections are designed in-house and realised with the most modern printing and manufacturing techniques, resulting in inspiring designs no matter what floor covering or combination of floor coverings you select. Digital print and custom colourations are possible throughout our portfolio. For more information on our bespoke collection please visit page 278.

We also ensure our products are produced to the latest technical standards to ensure your floor covering will offer outstanding performance throughout its long lifetime.

www.forbo-flooring.com





In the development of our Allura collections we continuously work to increase the sustainability of our portfolio. And through it all, we use life cycle assessments (LCAs) to guide our journey, ensuring we make the right decisions continuously on our products and contribute to a circular economy. And we always make sure that our Environmental Product Declarations (EPDs) are third-party certified – that way we can ensure full transparency.

THE PILLARS OF OUR AMBITION

TRANSPARENCY

Transparency is the foundation for making the right circular choices. With life cycle assessments as our constant guide in doing right, we continue to lead the industry towards new environmental standards.

CIRCULARITY

True circularity is to go all the way around. We think circular in everything we do. We work on creating products that keep the end in mind – and do this throughout our design process and choice of materials.

RENEWABILITY

Renewable materials are an important part of a fully circular future. We want to be the trusted partner for fully circular flooring solutions made with renewable raw materials. We know that the recycling of flooring is important. And we know that it is crucial to achieve carbon neutrality.



GOING ROUND, MOVING FORWARD

Sustainable solutions

Many of the flooring systems and building materials used today have an impact on the planet. The right flooring can help lower emissions and reduce waste – that's why we want to contribute with more sustainable solutions.



1. PRODUCT DEVELOPMENT AND DESIGN

Product design with circularity and users in mind

We develop and design flooring solutions to create value during use and after, keeping both the environment and users in mind. Our focus is on designing flooring with renewable and recycled materials. This enables us to deliver products that help take care of both the environment and you. We aim to create easy-removal solutions that are eco- and human-safe in all product categories while contributing to recycling schemes worldwide. That means you get products that are easy to install and remove - enabling a smooth recycling process.

MOST FLOORING ONLY HAS ONE LIFETIME - OURS HAS A FEW MORE

2. SOURCING AND RAW MATERIALS

Maximizing the use of sustainable & renewable flooring materials

To make sure our products are completely sustainable, we set ourselves the highest standards when it comes to sourcing and materials. Our products are third-party verified with environmental declarations such as LCAs, EPDs and HPDs. We aim to only use 100% harmless and traceable raw materials and increase the amount of fully bio-based products sold. That means you get products that are completely toxin- and phthalate-free and sourced from natural raw materials to work with, not against, the environment.

GOING ROUND WITH TRANSPARENCY FROM CRADLE TO CRADLE STARTS WITH DECLARING OUR ENVIRONMENTAL AND HEALTH IMPACT



3. PRODUCTION & DISTRIBUTION

Carbon-neutral and zero-waste production

We don't just aim to only use sustainable materials for our products. We also aim to make our products as sustainable as possible. That's why we are working towards a zero-waste production cycle and products made using as much recycled material as possible. We make flooring solutions that are as green as possible from design to end-of-life and are produced using 100% green energy, where available. This is how we produce products that are truly CO2 neutral without the need for offsetting.

TOO MANY FLOORS COME WITH A CARBON FOOTPRINT - WE AIM TO MAKE FLOORS WITHOUT LEAVING A TRACE

4. LONG LASTING & EASY TO MAINTAIN

Highly durable and fit-for-purpose solutions

Sustainability and longevity go hand in hand - the less energy we spend creating, installing, removing, repairing and recycling products, the less energy we use overall. That is why our flooring solutions are made to withstand stressful environments in addition to being easy to clean, thereby significantly reducing your cleaning costs. We also offer short-term solutions that can be used over and over again.

TO TRULY GO ROUND, WE OFFER A WIDE CHOICE OF FLOORS THAT ARE DESIGNED WITH A PURPOSE

5. RECYCLING & END OF LIFE

Recreating value at the end

To become truly sustainable, we need to close the loop. We do that by continuously improving our modular offerings and finding ways to recycle them at their end of life and working with local recycling schemes. We also design floors that are made of recycled materials, so your old floors can be repurposed today - and tomorrow. We aim to ensure flooring materials are fully recyclable and help drive the implementation of economically viable take-back schemes since not all materials can be infinitely recycled. That means you get products with up to 25% recycled from sources such as fishnets and post-consumer waste.

TO LAY THE FOUNDATION FOR A BETTER FUTURE - WE NEED TO DESIGN RECYCLED MATERIALS INTO OUR FLOORS

For more information please visit www.forbo-flooring.com/sustainability





RELIABLE LOGISTICS ACROSS THE WORLD

Our logistics

In our world we are recognised as a trusted partner. Our global logistics network and co-operation with flooring installers all over the world ensures your job gets done when you ask for it, on time, quickly and to your satisfaction.

ENTRANCE FLOORING SYSTEMS



nuway®

A collection of rigid entrance systems for entrances with very heavy or intense traffic.



coral®

A collection of textile clean-off products for entrances with heavy traffic.

CARPET TILES



tessera®

Tessera offers stylish, sustainable and hardwearing carpet tiles in various pile constructions, shapes and textures, delivering specific performance and aesthetic benefits.

PORTFOLIO



Designer collections and bespoke design

We offer bespoke design across our portfolio to create a truly unique focal point in addition to unique designer collections.

RESILIENT FLOORING



marmoleum®

Forbo's linoleum brand – natural, sustainable, durable, high quality and innovative in colour and design. Available in sheet, tile and plank format.



Project vinyl

A vinyl portfolio offering flooring solutions that encompass general purpose, safety, acoustic, static control, LVT design tiles and wetroom solutions.

FLOCKED FLOORING



flotex®

A flocked floor covering that looks and feels like a carpet without any of the drawbacks of a textile floor covering.

ANYWHERE, ANY PLACE

Our products

We pride ourselves on offering a truly comprehensive product portfolio with leading edge products specifically designed to cater for each area of a project, from the entrance through circulation and communal zones, to each individual space in a building. The following pages showcase our offer.

To see our latest new products visit www.forbo-flooring.com




We've been the world leader in textile entrance flooring for over 50 years, so there's nothing Forbo Flooring doesn't know about stopping dirt coming into your building with attractive floors. And now we can offer you more choice of colours, designs and technical specifications than ever before.

First impressions count. When people enter your building, they should like what they see – including the floor. But you also have the practical pressures of keeping your building floors clean and keeping your visitors safe. Our entrance flooring does all of this, and more.

Each range in the Entrance flooring collection has been designed to deal with all kinds of entrance environments, from street grime to sand, and from monsoon to snow.

Whatever it is that tries to hitchhike into your building on people's shoes, we'll show you how to stop it in its tracks with a great-looking floor.

An entrance flooring system consist of zones



zone 1

Primary matting

- (Coral grip, Nuway ridged matting or Coral click)
- Outside the building or first area inside the building
 - Use scraping of dirt

zone 2

Secondary matting

- (Coral classic, Coral brush, Coral welcome, Coral duo, Coral bright, Coral interior)
- Ideally 6 meters of mat or in combination with primary or circulation zone matting.
 - Inside the building after primary matting
 - Use for picking up fine dirt and moisture

zone 3


Circulation zone matting

- (Coral interior, Coral luxe, Coral bright, Coral classic)
- Inside the building at reception area or in corridors
 - Also has scraper yarns and takes up moisture
 - Very much required when entrance flooring in zone 1 or 2 is too short or not present

REDUCE YOUR FLOOR CLEANING TIME BY 65%

A coral entrance with a 3-step clean-off zone will cut your future maintenance costs by stopping up to 95% of walked in dirt and moisture from reaching your building floors. This reduces your building's floor cleaning time by up to 65% and prolongs the life of your floors. (The maintenance cost of commercial floors is 86% of the total life cycle cost).

WHICH ENTRANCE FLOORING SYSTEM SHOULD I CHOOSE?



If you really want to keep your building clean and safe, it's not enough to throw down a mat at the door. In fact the Health and Safety Executive advises against the use of loose lay mats which they state *'can introduce a range of hazards and are not always very effective'*.

Source: HSE elearning module, 'Watch your step'

APPLICATION 1

OUTSIDE USE

Any matting placed outside the building entrance is the first line of defence against foot-borne soil, scraping the coarsest dirt from the soles of shoes before they cross the threshold.

APPLICATION 2

INSIDE USE

Moving inside, the next line of defence, is used to remove foot-borne moisture and finer dirt particles.

APPLICATION 3

OTHER CIRCULATION AREAS

Other areas in the building also suffer from soil and moisture; reception areas, corridors, walkways to other parts of the building, elevator, staircase exits, etc. All these areas will be prone to residual soiling and will benefit highly from a purposely designed Coral textile entrance mat to absorb this soiling.

WHAT DO I NEED TO CONSIDER?

Where to use?	Internal or External?	Reversible	Finishes – Reversible	Removes Moisture	Which should I choose?	Guarantee								
			Scraper bars Wiper strips Finishes – Single sided Carriers Inserts											
The location, type and level of traffic affects the choice of product.	Matting placed outside will defend against soil and the coarsest of foot-borne dirt. Inside it will defend against foot-borne moisture and finer dirt particles.	Double sided rigid mats can be reversible, effectively doubling their lifespan. Please see the table below to see which products are reversible.	There is a wide choice of wiper strips and scraper bars/carriers and inserts to allow our Nuway mats to co-ordinate with all interior finishes. <table border="1"> <thead> <tr> <th>Scraper Bars</th> <th>Wiper Strips</th> </tr> </thead> <tbody> <tr> <td>As the name suggests, they scrape soil from the traffic walking across the mat.</td> <td>Prime rubber and polyamide fibre strips remove moisture and fine dirt</td> </tr> <tr> <th>Single sided carriers</th> <th>Single sided inserts</th> </tr> <tr> <td>With crimping action to secure insert.</td> <td>Mix and match with Ultragrip rubber, bristle and a wide range of Coral inserts which allow colour coordination with interior finishes.</td> </tr> </tbody> </table>	Scraper Bars	Wiper Strips	As the name suggests, they scrape soil from the traffic walking across the mat.	Prime rubber and polyamide fibre strips remove moisture and fine dirt	Single sided carriers	Single sided inserts	With crimping action to secure insert.	Mix and match with Ultragrip rubber, bristle and a wide range of Coral inserts which allow colour coordination with interior finishes.	Removing moisture from the soles of shoes is vital to prevent slipping.	Each product in our Nuway and Coral collections offers differing benefits and features.	Standard Guarantee is up to 10 years, depending on the product. Installations by FESSIs (Forbo Entrance System Specialist Installer) have an extended guarantee*.
Scraper Bars	Wiper Strips													
As the name suggests, they scrape soil from the traffic walking across the mat.	Prime rubber and polyamide fibre strips remove moisture and fine dirt													
Single sided carriers	Single sided inserts													
With crimping action to secure insert.	Mix and match with Ultragrip rubber, bristle and a wide range of Coral inserts which allow colour coordination with interior finishes.													

	Application			Intense traffic	Extreme point loading	Reversible	Guarantee
nuway® tuftiguard	1 + 2						15 years*
nuway® tuftiguard HD	1 + 2						15 years*
nuway® connect	1 + 2						7 years*
nuway® grid	1 + 2						7 years*
coral® click	2						5 years
coral® duo	2						5 years
coral® brush	2 + 3						5 years
coral® welcome	2 + 3						5 years
coral® classic	2 + 3						5 years
coral® logo	2 + 3						3 years
coral® luxe	2 + 3						5 years
coral® bright	2 + 3						5 years
coral® interior	2 + 3						5 years

RIGID ENTRANCE FLOORING SYSTEMS

The recognised market leader in engineered entrance flooring systems, Nuway offers a wide range of rigid single and double sided made-to-order mats which provide an outstanding first line of defence against soil and moisture entering a building on the soles of shoes and the treads of wheeled traffic.

<p>OPEN</p>  <p>CLOSED</p>  <p>Most Nuway ranges offer a choice of open or closed construction to meet individual requirements.</p>	<p>DOUBLE</p>  <p>Nuway Tuftiguard can be reversible, effectively doubling its life.</p>	 <p>Nuway Tuftiguard HD is strong enough to cope with high point loads of up to 900kg/cm².</p>
<p><i>customise</i> nuway®</p> <p>All Nuway mats can be customised with names, logos and corporate messages.</p>	 <p>Nuway Tuftiguard is available in Bamboo, a sustainable species of grass.</p>	<p>SINGLE</p> <p>+ coral®</p> <p>Nuway single sided ranges are available with Coral inserts for colour co-ordination.</p>
 <p>Nuway Tuftiguard Bamboo prevents strobing in bright entrances.</p>	 <p>Nuway Grid is easy to shape on site.</p>	 <p>100% of aluminium and steel waste from our Nuway production is recycled.</p>

With our products we aim to create better quality interior environments in which people can live, work and learn. Our Nuway entrance products help to ensure that buildings are safe and hygienic in all weather conditions.

The WELL Building Standard® also recommends the use of entrance matting as an important tool to reduce pollutants entering the building.

NUWAY COLLECTION AT A GLANCE

nuway® tuftiguard

The original and most widely used rigid entrance mat. Reversible, effectively doubling its lifespan and guaranteed for up to 15 years. Available in open or closed format with single or double wiper strips for increased moisture removal.



nuway® tuftiguard HD

For entrances with intense traffic and high point loads.



nuway® connect


Single sided product offering 'mix and match' opportunities including bristle, Ultragrip rubber and Coral inserts.



nuway® grid

Single sided product available with 12 inserts, including new Ultragrip Rubber for sure footing in multi-directional entrances.





At the heart of the Nuway range, **Tuftiguard Classic** is the most widely used rigid engineered entrance mat in the UK. Tuftiguard has the **durability, strength** and **structural integrity** to deliver **excellent performance and appearance retention** in intense traffic locations.

- High tensile steel linkages give Nuway Tuftiguard **construction integrity**.
- Tuftiguard mats can sit in a matwell or can be used with ramp systems.
- For multi-directional entrances, Nuway Tuftiguard is **available in 50cm tile format**.
- Tuftiguard is available in **open or closed construction** to suit the location of the mat and preferred cleaning regime.
- Tuftiguard is **available with single wiper strips or double wiper strips** where extra moisture absorption is required or where the entrance is less than 3 metres deep.
- Tuftiguard is available in a **choice of depths** to match most matwells. Ramp frames are also available.
- **Scraper bars**, as the name suggests, scrape soil from the traffic crossing the entrance system.
- **Wiper strips** remove moisture and finer dirt.
- In our **Black anodised** aluminium mats, the black anodised finish is **removed from the tip of the scraper bars** to ensure a **consistent appearance** across the mat.

CONSIDERATIONS

As with all aluminium matting systems of this type, in very brightly lit areas, the strong contrast between a light aluminium scraper bar and a dark wiper strip can sometimes create a strobe effect which should be prevented.


To avoid disorientating pedestrians affected by this type of visual disturbance, consider using Bamboo or Black anodised scraper bars or a less contrasting wiper strip.

CHOOSE FROM THREE STYLES OF TUFTIGUARD

There are three different styles of Tuftiguard, each offering a different level of design and performance flexibility.

	Best Seller Tuftiguard Classic	Tuftiguard Plain	Tuftiguard Design
Suitable for external / interior entrances	INT	EXT	INT
Reversible?	DOUBLE DOUBLE		
Colours of wiper strips available	Buffed rubber for maximum dirt hiding	Unbuffed rubber for use in external entrances	Additional choice of 4 colours to reflect interior colour schemes
Wiper strip format	Single wiper strip	Double wiper strip for increased moisture removal and where the entrance is less than 3m deep	
Colours of scraper bars available			
Depth options	12mm or 17mm		
Construction of mat	CLOSED or OPEN		Open construction, ideal for external entrances as it can store more wet and dry soil. The new open construction design is heel proof.
Guarantee	GUARANTEE 10 YEARS		
Where to use?	Very heavy and intense traffic areas.		

New Tuftiguard Bamboo – the sustainable choice



- Bamboo is a **sustainable** species of grass.
- Tuftiguard Bamboo uses **moso high density** which outperforms the very best hardwood species, making it the best natural solution in heavy traffic situations.
- Moso bamboo is the **fastest growing** plant in the world.
- Moso bamboo is **sourced from sustainably managed forests** and plantations and is **FSC® certified**.
- As Bamboo is a **natural product**, there will be some **slight colour variances** between the scraper bars.
- Again, as it's a **natural product**, the mat may **fade** slightly over time and could lose some **small splinters** during its life cycle, however, this **will not affect the structural integrity** of the mat.

Bamboo scraper bars



Tuftguard plain



Tuftguard classic




Tuftguard design




Maximum length per module	2500mm (Bamboo 2400mm)															
Maximum width per module	750mm															
Maximum weight per module	23kg/m ²															
Depth	12mm								17mm							
Scraper bar material	Aluminium / Black Anodised Aluminium				Bamboo				Aluminium / Black Anodised Aluminium				Bamboo			
Construction	Open		Closed		Open		Closed		Open		Closed		Open		Closed	
Number of wiper strips	1	2	1	2	1	2	1	2	1	2	1	2	1	2	1	2
Total weight (kg/m ²)	11	12	14	15	10	11	13	14	14	15	16	17	13	14	15	16
Max static load (kg/cm ²)	200				100				200							
Dynamic load (kg) 2 wheels 80mm, 20,000 passes	200				100				200							
Frames	A selection of recessed matwell frames are available															
Ramp frame model	ARF 50								ARF 70							
Manufacturing method	Entrance flooring system with scraper bars and rubber wiper strips															
Wiper designs	Plain, natural fibres, coloured fibres															
Wiper material	Rubber															
Pile material	100% Polyamide BCF															

TECHNICAL SPECIFICATIONS



Tuftguard Classic and Design – dimensions



12mm single closed

17mm single closed

12mm single open

17mm single open

All dimensions are approximate.



CONSIDERATIONS

Bamboo is a natural product so there will be a variance of colour within the scraper bars and although the Bamboo may fade and lose small 'splinters', the structural integrity of the mat will not be affected.

In very brightly lit areas, the strong contrast between a light aluminium scraper bar and a dark wiper strip can sometimes create a strobe effect, which should be avoided.

To prevent this type of occurrence, consider using scraper bars in **Bamboo** or **Black Anodised Aluminium**.



Scraper bars




Wiper bar options

Plain and Classic



Wiper bar options

Design





• The ideal matting solution for entrances with **heavy duty loads** and **intense pedestrian and/or wheeled traffic**.

• Patented aluminium scraper bar ensures it's the **strongest type of matting in the Nuway range**, and possibly in the UK.

• Tests have confirmed that Tuftguard HD **can withstand static loads of up to 900kg/cm²** compared with the maximum load of 200kg/cm² for standard Tuftguard mats.

• Aluminium scraper bars have special ridges which **effectively remove dirt** while also being **smooth enough for wheeled traffic** to move easily.

CONSIDERATIONS

As with all aluminium matting systems of this type, in very brightly lit areas, the strong contrast between a light aluminium scraper bar and a dark wiper strip can sometimes create a strobe effect which should be prevented.

To avoid disorientating pedestrians affected by this type of visual disturbance, consider using a less contrasting wiper strip.

CHOOSE FROM **THREE STYLES** OF TUFTGUARD HD

There are three different styles of Tuftguard HD, each offering a different level of design and performance flexibility.

Tuftguard HD classic

This is the best selling option in our HD collection.

- The wiper strip is buffed rubber for maximum dirt hiding as most dirt is light grey.
- The ridged scraper bars help to prevent glare.

Tuftguard HD plain

As the Classic offer but with an unbuffed wiper strip making it suitable for external entrances.

Tuftguard HD design

As the Classic offer but with an additional choice of nine wiper strips to reflect interior colour schemes.



	Tuftguard HD Classic	Tuftguard HD Plain	Tuftguard HD Design
Suitable for external / interior entrances			
Reversible?	DOUBLE REVERSIBLE		
Colours of wiper strips available	Buffed rubber for maximum dirt hiding	Unbuffed rubber for use in external entrances	Additional choice of 4 colours to reflect interior colour schemes
Wiper strip format	Only available in closed format with double wiper strips to ensure maximum performance and durability		
Colours of scraper bars available	Aluminium		
Depth options	12mm or 17mm		
Construction of mat	CLOSED		
Guarantee	GUARANTEE 10 YEARS		
Where to use?	Very heavy and intense traffic areas with high point loading.		



Tuftguard HD plain



Tuftguard HD classic



Tuftguard HD design




	Nuway 12mm	Nuway 17mm
Maximum length per module	2500mm	2500mm
Maximum width per module	750mm	750mm
Maximum weight per module	23kg/m ²	23kg/m ²
Depth	12mm	17mm
Scraper bar material	Aluminium	Aluminium
Construction	Closed	Closed
Number of wiper strips	2	2
Total weight (kg/m ²)	17	24
Max static load (kg/cm ²)	900	900
Dynamic load (kg) 2 wheels, 80mm 20,000 passes	350	350
Fire behaviour EN13501-1	C _{fl} -s1	C _{fl} -s1
Frames	A selection of recessed matwell frames are available	
Ramp frame model	ARF 50	ARF 70
Manufacturing method	Entrance flooring system with scraper bars and rubber wiper strips	
Wiper design	Plain, natural fibres, coloured fibres	
Pile / wiper material	100% polyamide BCF	


TECHNICAL SPECIFICATIONS



Tuftguard HD plain – dimensions




12mm double closed




17mm double closed

Tuftguard HD classic/design – dimensions



12mm double closed



17mm double closed

All dimensions are approximate.



Scraper bars

Universal



Aluminium

Wiper bar options

Plain and Classic



Unbuffered (Plain)



Buffered (Classic)

Wiper bar options

Design



Charcoal



Ocean



Willow



Scarlet



Nuway Connect is a very versatile roll-up single sided entrance system that's easy to shape on site, making it ideal for awkwardly shaped entrances. It's also available with a wide choice of inserts allowing the mat to be adapted to suit individual requirements.



- **Ultragrip rubber inserts** have been tested using the Pendulum (the HSE recommended test method) in accordance with BS7976-2 and the UK Slip Resistance Group Guidelines and **offer a low slip risk** in wet and dry conditions.
- **Ultragrip rubber** offers excellent sure-footing and is **ideal for multi-directional entrances**. Its high rubber content prevents it getting slippery when wet.
- **Ultragrip rubber** offers improved **underfoot comfort** and **moisture removal** due to its 'pocket' design. It also offers **excellent fire rating properties**.

- A choice of **5 Coral Classic inserts** allows colour co-ordination with matching Coral Classic sheet product used in the secondary matting zone.
- All three elements, Coral, bristles and Ultragrip rubber, **can be mixed and matched** to create the precise entrance system to meet your needs.
- Open construction **Connect** mats **can be rolled up** for ease of cleaning.
- The patented product design ensures that the **mat can only be rolled inwardly**, helping to prevent the **bow wave** that can occur on other rollable products.



THE FLEXIBLE, RIGID ENTRANCE SYSTEM

Connect carrier component structure



Inserts

Available with a choice of 5 Coral Classic, 4 row bristle and Ultragrip rubber inserts for internal and external use.

Carrier Section

Low lustre aluminium anodised finish helps to prevent a strobing effect in bright conditions. **Note:** There is a slight difference in the profile between 10mm and 17/22mm Connect. (see image on the left).

Choose your combination


Nuway Connect is one of the most flexible single sided entrance mats available in the UK. With a choice of 7 inserts, 3 heights and 2 constructions, a Nuway Connect mat can be precisely tailored to your individual requirements.

1 PICK YOUR INSERT



Coral Classic

- For picking up moisture and fine dirt
- For interior use only (colours are shown overleaf)



4-row bristle


- For removal of coarse dirt
- For exterior and interior use



Ultragrip rubber

- Ideal for multi directional entrances
- Proven low slip risk
- Fire rating of Bfls1

2 MIX & MATCH YOUR OPTIONS



The following options are available if required

- Ultragrip rubber with bristles (alternating)
- Textile with Ultragrip rubber or bristles (alternating)

3 CHOOSE YOUR CONSTRUCTION



Open

- Collects dirt in the matwell rather than on the surface
- Easily rollable for cleaning



Closed

- Improved functionality of the mat as there is a greater surface of inserts


4 SELECT YOUR HEIGHT



10mm



17mm



22mm

Please note: Due to the different construction of the 10mm depth product, there is a greater visibility of aluminium scraper bar than on the other 2 heights.




Nuway Connect is flexible single sided solutions with three different inserts which can be mixed and matched for the ideal entrance.

Different heights – different profiles


The appearance of the 10mm depth Connect differs from the 17 and 22mm versions as the width of the profile of 10mm Nuway Connect is larger and therefore shows more aluminium.

Open or closed construction


Mix and match – bristle and Ultragrip rubber




10mm




Open (10mm height)




Textile with bristles (10mm height)



17/22mm



Closed (10mm height)



Bristles with Ultragrip rubber (10mm height)



Coral Classic colours available in Nuway connect



4701 | anthracite



4730 | raven black




4753 | bright red




4764 | taupe



4750 | warm black



Ultragrip rubber



Bristles



Specials

Different colours of Coral Classic and Coral Brush inserts are available at a small price premium and there is also the possibility of adding anodised aluminium branding strips. To find out more, please contact your local customer service team.

	Connect with Coral textile inserts	Connect with bristle inserts	Connect with Ultragrip rubber inserts
Suitable for external / interior entrances			
Inserts available	coral® classic 5 colours (see above for details)	 4-row bristle	 Slip resistant Ultragrip rubber
Carrier	 Low lustre aluminium		
Construction of mat	OPEN or CLOSED		
Height options	10mm 17mm 22mm		
Mix and match inserts	 Offers a mix and match option including textile, bristle and Ultragrip rubber.		
Rollable	 Rollable for ease of cleaning in open construction only		
Guarantee	GUARANTEE 5 YEARS		
Where to use?	 Very heavy traffic.		

CONSIDERATIONS

As with all aluminium matting systems of this type, in very brightly lit areas, the strong contrast between a light aluminium carrier and a dark insert can sometimes create a strobe effect which should be prevented. To avoid disorientating pedestrians affected by this type of visual disturbance, consider using a less contrasting insert.

If you are considering Connect for an exterior mat in an exposed entrance we recommend using Ultragrip rubber or a combination of Ultragrip rubber and bristle for maximum slip resistance, please contact our Entrance Flooring Systems customer service team to ensure compatibility.



NUWAY CONNECT WITH CORAL CLASSIC TEXTILE INSERT

Combination	Textile only						Textile and 4 row bristle					
	Open			Closed			Open			Closed		
	10mm	17mm	22mm	10mm	17mm	22mm	10mm	17mm	22mm	10mm	17mm	22mm
Depth to height of aluminium (mm)	8	14	19	8	14	19	8	14	19	8	14	19
Depth to height of insert (mm)	11	17	22	11	17	22	15	21	26	15	21	26
Distance between the profiles (mm)	5			0			5			0		
Weight (kg/m ²)	9.5	13.2	14.9	10.5	15.1	17.1	11.1	15.1	16.9	12.4	17.4	19.4
Max width per module (mm)	3000											
Max depth per module (mm)	Relates to the weight											
Max weight per module (kg)	23											
Max static load (kg/cm ²)	200	200	200	200	200	200	100	100	100	100	100	100
Dynamic load (kg) 2 wheels, 80mm 20,000 passes	200	200	200	200	200	200	50	50	50	50	50	50
Fire behaviour EN ISO 9239-1	B _{fl} s1						C _{fl} s1					
Frame	A selection of recessed matwell frames are available											
Ramp frame	ARF 50	ARF 70		ARF 50	ARF 70		ARF 50	ARF 70		ARF 50	ARF 70	
Material and manufacturing method	Anodised aluminium profiles with PVC connector profiles, stainless steel clips											
Wiper design	Coral clean-off system						Coral clean-off system and 4 row bristles					
Wiper material	100% polyamide BCF						100% polyamide BCF for both textile and bristles					

NUWAY CONNECT WITH BRISTLE

Combination	Bristle only						Bristle and Rubber					
	Open			Closed			Open			Closed		
	10mm	17mm	22mm	10mm	17mm	22mm	10mm	17mm	22mm	10mm	17mm	22mm
Depth to height of aluminium (mm)	8	14	19	8	14	19	8	14	19	8	14	19
Depth to height of insert (mm)	15	21	26	15	21	26	15	21	26	15	21	26
Distance between the profiles (mm)	5			0			5			0		
Weight (kg/m ²)	12.7	17.1	18.8	14.2	19.6	21.6	12.3	16.6	18.3	13.8	19.1	21.1
Max width per module (mm)	3000											
Max depth per module (mm)	Relates to the weight											
Max weight per module (kg)	23											
Max static load (kg/cm ²)	100	100	100	100	100	100	100	100	100	100	100	100
Dynamic load (kg) 2 wheels, 80mm 20,000 passes	50	50	50	50	50	50	50	50	50	50	50	50
Fire behaviour EN ISO 9239-1	C _{fl} s1						C _{fl} s1					
Frame	A selection of recessed matwell frames are available											
Ramp frame	ARF 50	ARF 70		ARF 50	ARF 70		ARF 50	ARF 70		ARF 50	ARF 70	
Material and manufacturing method	Anodised aluminium profiles with PVC connector profiles, stainless steel clips											
Wiper design	4 row bristles						4 row bristles and ribbed rubber					
Wiper material	100% polyamide BCF						100% polyamide BCF for bristles and 100% EPDM for rubber					

To find out more about how our Nuway ranges help to create better environments, please visit our web site and download the environmental data sheets www.forbo-flooring.com

Please note EPDM rubber is Ethylene Propylene Diene Monomer.




NUWAY CONNECT WITH RUBBER OR ULTRAGRIP RUBBER

Combination	Rubber only						Ultragrip safety rubber only					
	Open			Closed			Open			Closed		
	10mm	17mm	22mm	10mm	17mm	22mm	10mm	17mm	22mm	10mm	17mm	22mm
Depth to height of aluminium (mm)	8	14	19	8	14	19	8	14	19	8	14	19
Depth to height of insert (mm)	12	18	23	12	18	23	10	16	21	10	16	21
Distance between the profiles (mm)	5			0			5			0		
Weight (kg/m ²)	12	16.2	17.9	12	16.2	17.9	12	16.2	17.9	12	16.2	17.9
Max width per module (mm)	3000											
Max depth per module (mm)	Relates to the weight											
Max weight per module (kg)	23											
Max static load (kg/cm ²)	100	100	100	100	100	100	100	100	100	100	100	100
Dynamic load (kg) 2 wheels, 80mm 20,000 passes	100	100	100	100	100	100	100	100	100	100	100	100
Fire behaviour EN ISO 9239-1	C _{fl} s1						B _{fl} s1					
Frame	A selection of recessed matwell frames are available,											
Ramp frame	ARF 50	ARF 70		ARF 50	ARF 70		ARF 50	ARF 70		ARF 50	ARF 70	
Material and manufacturing method	Anodised aluminium profiles with PVC connector profiles, stainless steel clips											
Wiper design	Ribbed rubber						Coarse rubber					
Wiper material	100% EPDM						Rubber					


To find out more about how our Nuway ranges help to create better environments, please visit our web site and download the environmental data sheets www.forbo-flooring.com

MAIN DIMENSIONS SHOWN IN MM


Nuway connect 10mm




Nuway connect 17mm



Nuway connect 22mm





Nuway Grid offers a contemporary and cost effective alternative to Nuway Tuftguard entrance matting and is an ideal solution in very heavy traffic entrance areas where aesthetic considerations are paramount.

- Coral carrier sections can allow colour co-ordinated entrance areas to be created with primary and secondary entrance matting products.
- Inserts include strips of textile inserts (for internal use only) in 11 different colourways drawn from the Coral Classic, Coral Brush and Burford ranges.

- Other textile inserts from the Coral range are available to special order.
- Grid Ultragrip provides a slip resistant surface, ideal for external entrances with multi directional traffic.
- Ultragrip rubber inserts have been tested using the Pendulum (the HSE recommended test method) in accordance with BS7976-2 and the UK Slip Resistance Group Guidelines and offer a low slip risk in wet and dry conditions.
- Grid Ultragrip offers improved underfoot comfort and moisture removal due to its 'pocket' design. It also offers excellent fire rating properties.
- Available in a choice of 12 and 17mm depths to suit the majority of matwells.
- Unique dovetail construction allows for easy shaping on site.



CONSIDERATIONS

As with all aluminium matting systems of this type, in very brightly lit areas, the strong contrast between a light aluminium carrier and a dark insert can sometimes create a strobe effect which should be prevented. To avoid disorientating pedestrians affected by this type of visual disturbance, consider using a less contrasting insert.


Contact our Entrance Flooring Systems Customer Service team to ensure compatibility.




Coral Classic colours available in Nuway Grid



Coral Brush colours available in Nuway Grid



Ultragrip rubber insert



Burford insert



Nuway Grid carrier component structure



Inserts – Nuway Grid is available in a selection of 12 different inserts from the Coral Classic, Coral Brush and Burford ranges and Ultragrip rubber inserts (for exterior entrances).

Carrier Section – Low lustre anodised finish complies with Equality Act requirements. Patented crimping action firmly secures the insert within the carrier section.

For technical information please visit www.forbo-flooring.com/Nuway

	Grid with textile inserts	Grid with Ultragrip rubber inserts
Suitable for external / interior entrances		
Inserts available	coral® classic 5 colours coral® brush 5 colours Burford	Slip resistant Ultragrip rubber
Carrier	Low lustre aluminium	
Height options	12mm or 17mm	
Construction of mat	CLOSED	
Guarantee	GUARANTEE 5 YEARS	
Where to use?	Very heavy traffic.	


	12mm Grid		17mm Grid	
Maximum length per module	3000mm		3000mm	
Maximum width per module	750mm		750mm	
Maximum weight per module	23kg		23kg	
	Rubber	Textile	Rubber	Textile
Depth to height of aluminium	12mm	12mm	17mm	17mm
Depth to height of infill	14mm	18mm	19mm	23mm
Infill material	Ultragrip Safety Rubber	Burford/Coral Classic/ Coral Brush	Ultragrip Safety Rubber	Burford/Coral Classic/ Coral Brush
Construction	Closed		Closed	
Total weight (kg/m ²)	10.5	Approx 9	17.2	Approx 15
Max static load (kg/cm ²)	100		100	
Dynamic load (kg) 2 wheels 80mm, 20,000 passes	200		200	
Fire behaviour EN ISO 9239-1	Ultragrip B _{fl} s1		Textile B _{fl} s1	
Ramp frame model	ARF 50		ARF 70	
Manufacturing method	Entrance flooring system with carriers and rubber infills	Entrance flooring system with carriers and textile infills	Entrance flooring system with carriers and rubber infills	Entrance flooring system with carriers and textile infills
Wiper material	Rubber	Needlefelt/PVC backed textile	Rubber	Needlefelt/PVC backed textile
Pile material	N/A	100% polypropylene (Burford) /100% polyamide (Coral)	N/A	100% polypropylene (Burford) /100% polyamide (Coral)



To see full range of inserts, please visit www.forbo-flooring.com




Nuway Grid 12mm




Nuway Grid 12mm with Ultragrip insert

Nuway Grid 17mm




Nuway Grid 17mm with Ultragrip insert



Nuway Grid 12mm with textile insert



Nuway Grid 17mm with textile insert



CONSIDERATIONS

In very brightly lit areas the strong contrast between a light aluminium scraper bar and a dark wiper strip can sometimes create a strobe effect, which should be avoided.

To avoid disorientating pedestrians affected by this type of visual disturbance consider using a less contrasting insert. Contact our Entrance Flooring Systems Customer Service team to ensure compatibility.




Stop **dirt** in its tracks with Coral

When people enter your building, they carry unwanted guests on their shoes – muck and damp. But Coral entrance flooring stops them in their tracks. For example, over a 6 metre stretch of Coral flooring, up to 95% of walked in dirt and moisture is removed. Reduce your cleaning costs and keep your building looking good, let Coral stop those filthy gate crashers.

Only a well designed entrance flooring system can keep dirt in its tracks

That's why Coral:



Good for the environment.
Good for your daily environment.

From how they're made to how they perform, forbo flooring is truly sustainable. With its eco, safety, design and cleaning credentials, forbo is good for buildings, good for people and good for the planet. We help people work, live and relax in a better environment.

MANY CORAL PRODUCTS USE ECONYL YARN - MADE FROM USED AND ABANDONED FISHING NETS

Using Econyl helps reduce the planet's existing waste, avoids additional manufacturing-related pollution, and keeps the consumption of natural resources and energy to a minimum.

ALL WASTE YARN FROM CORAL PRODUCTION IS RE-USED BY THE YARN SUPPLIER.

Our constant search for new ways to reduce our environmental impact has led us to work very closely with forward-thinking suppliers. They incorporate ever higher levels of recycled content in their materials.

PRODUCED WITH 100% GREEN ELECTRICITY FROM RENEWABLE RESOURCES


We only use electricity from renewable sources - part of our rigorous environmental management system that has earned us a ISO 14001 certification.

The coral manufacturing plant creates virtually zero landfill.

CORAL COLLECTION AT A GLANCE


coral® brush

The great all-rounder.




coral® grip

The robust and ultimate dirt and grit remover.



coral® classic

The ultimate moisture absorber.




coral® click

The first steps in protecting your building.



coral® welcome

Where design meets environment.




coral® bright

When price is key.




coral® duo

The ultimate dirt and moisture remover.




coral® interior

Modularity in optima forma.



coral® luxe

Where aesthetic appeal is a top priority!



coral® logo

Make a lasting impression by creating your logo or bespoke design as an integral part of your entrance zone.

See Coral logo on page 316.



The great all-rounder against dirt and moisture.

Coral Brush is suitable for all types of entrance areas, absorbing moisture and removing dry soiling as the weather demands.

- Functional all-rounder that removes both moisture and dirt
- 100% of the yarn in Coral Brush is Econyl[®] regenerated solution dyed polyamide
- Appealing solid and linear designs
- Complies with the highest fire class standard for a textile product: B_{fl}-s1
- Suitable for heavy contract use
- Ideal for interior entrances and circulation areas
- Available in sheet, mats and 50cm x 50cm tiles



FAST FLOORING * available as Fast Flooring installation

Description	Tufted cut pile	
Dimensions	Roll width 105 / 155 / 205cm Roll length ≤ 27.5m Tiles 50 x 50cm	
Mat dimensions	55 x 90cm / 90 x 155cm / 135 x 205cm / 205 x 300cm	
Total thickness	ISO 1765	Approx 9.0mm
Backing	EVERFORT [®] vinyl	
Yarn	Regenerated Econyl polyamide	
Area of use	Commercial heavy	
Reaction to fire	EN 13501-1	B _{fl} -s1, G, NCS
Slip resistance	EN 13893	μ > 0.30
Personal charging	ISO 6356	≤ 2 kV

*NOTE: Roll sizes include 2.5cm salve edge on each side.

Fire Resistant (FR) version available.

Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect. www.forbo-flooring.com

The ultimate moisture absorber.

Research shows that taking just two steps on Coral Classic's moisture absorbing yarns is enough to absorb half of the foot-borne moisture that would otherwise be carried inside on the soles of people's shoes.

- Maximum moisture absorption and effective dirt removal
- Choice of practical colourways
- Complies with the highest fire class standard for a textile product: B_{fl}-s1
- Suitable for heavy contract use
- Ideal for interior entrances and circulation areas
- Available in sheet, mats and 50cm x 50cm tiles



FAST FLOORING * available as Fast Flooring installation

Description	Tufted cut pile	
Dimensions	Roll width 105 / 155 / 205cm* Roll length ≤ 27.5m Tiles 50 x 50cm	
Mat dimensions	55 x 90cm / 90 x 155cm / 135 x 205cm / 205 x 300cm	
Total thickness	ISO 1765	Approx 9.0mm
Backing	EVERFORT [®] vinyl**	
Yarn	solution dyed polyamide	
Area of use	Commercial heavy	
Reaction to fire	EN 13501-1	B _{fl} -s1, G, NCS
Slip resistance	EN 13893	μ > 0.30
Personal charging	ISO 6356	≤ 2 kV

*NOTE: Roll sizes include 2.5cm salve edge on each side.

**Coral Classic tiles also available with Bitumen backing.

Fire Resistant (FR) version available.


Our recommended adhesive for Coral Sheet products is 540 Eurosafe special. Full technical specifications are available at www.forbo-flooring.com




5714 | shark grey LRV 4



5721 | hurricane grey* LRV 3



5774 | biscotti brown LRV 4



5710 | asphalt grey* LRV 2



5716 | masala brown LRV 5



5708 | avocado green LRV 3



5715 | charcoal grey LRV 2



5736 | cinnamon brown LRV 3




5722 | cornflower blue LRV 3



5730 | vulcan black LRV 1



5724 | chocolate brown LRV 3



5727 | stratos blue LRV 1



Coral brush 5727 | stratos blue




5739 | Byzantine purple LRV 2



5723 | cardinal red LRV 2




4751 | silver grey LRV 9



4701 | anthracite* LRV 6




4764 | taupe LRV 6



4721 | mouse grey LRV 4



4784 | coffee LRV 3



4768 | hunter green LRV 4



4730 | raven black* LRV 2



4726 | auburn LRV 4




4737 | Prussian blue LRV 2




4750 | warm black LRV 4



4756 | bronzetone LRV 2



4763 | ruby red LRV 6



Coral classic 4764 | taupe, 4726 | auburn

IN JUST TWO FOOTSTEPS, CORAL CLASSIC ABSORBS UP TO HALF THE WATER THAT WOULD OTHERWISE BE CARRIED INSIDE.

A few steps more, and your footwear is almost dry. This means the interior floor stays cleaner for longer. And resilient interior floors like vinyl, linoleum, wood and concrete are less likely to become slippery and dangerous.

Where design creates a better environment.

With its contemporary linear design and rich, deep pile, Coral Welcome packs the style and aesthetic appeal of a luxury carpet and makes an unequivocal statement in any entrance area.




- 100% of the yarn in Coral Welcome is Econyl® regenerated solution dyed polyamide
- Primary backing is made from recycled PET bottles
- Prevents moisture and dirt being tracked onto interior surfaces
- Striking linear aesthetic which makes a design statement in any entrance
- Complies with the highest fire class standard for a textile product: B_{fl}-s1
- Suitable for heavy contract use
- Ideal for interior entrances and circulation areas



Description	Tufted cut pile
Dimensions	Roll width 205cm* Roll length ≤ 27.5m
Mat dimensions	105 x 155 cm
Total thickness	ISO 1765 Approx 9.0mm
Backing	EVERFORT® vinyl
Yarn	Regenerated ECONYL® polyamide
Collection size	8
Area of use	Commercial heavy
Reaction to fire	EN 13501-1 B _{fl} -s1, G, NCS
Slip resistance	EN 13893 μ > 0.30
Personal charging	ISO 6356 ≤ 2 kV

*NOTE: Roll sizes include 2.5cm salve edge on each side.
Fire Resistant (FR) version available.



The ultimate dirt and moisture remover.

Coral Duo is the ideal solution when you need maximum dirt removal, unrivalled dirt retention and exceptional moisture absorption, all in just a couple of paces.




- Ideal solution for most entrances and especially smaller entrances
- 75% of the yarn in Coral Duo is Econyl® regenerated solution dyed polyamide
- Unbeatable performance for moisture and dirt removal
- Complies with the highest fire class standard for a textile product: B_{fl}-s1
- Suitable for heavy contract use
- Ideal for interior entrances and circulation areas

Description	Tufted cut pile
Dimensions	Roll width 205cm* Roll length ≤ 27.5m
Total thickness	ISO 1765 Approx 9.0mm
Backing	EVERFORT® vinyl
Yarn	regenerated ECONYL® polyamide solution dyed polyamide
Collection size	6
Area of use	Commercial heavy
Reaction to fire	EN 13501-1 B _{fl} -s1, G, NCS
Slip resistance	EN 13893 μ > 0.30
Personal charging	ISO 6356 ≤ 2 kV

*NOTE: Roll sizes include 2.5cm salve edge on each side.
Fire Resistant (FR) version available.

Our recommended adhesive for Coral Sheet products is 540 Eurosafe special. Full technical specifications are available at www.forbo-flooring.com

Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect. www.forbo-flooring.com



coral® luxe


Where aesthetic appeal is a top priority!

With its luxurious appearance and rich pile height Coral Luxe may not give the impression of a traditional entrance floor, but is in fact a highly efficient clean-off solution for light to medium traffic areas where aesthetic appeal is top priority.

- Rich and elegant appearance
- Comfortable and soft feel
- Effective moisture and soil absorption
- Quick drying for maximum functionality
- Compliance with the highest fire class standard: Bfl-s1
- Suitable for light industrial use and private applications
- Ideal for circulation areas
- Produced with phthalate free technology



Coral Luxe 2910 | onyx



Description	Tufted cut pile
Dimensions	20 m x 205 cm 20 m x 105 cm 135 cm x 205 cm 105 cm x 155 cm
Total thickness	ISO 1765 Approx 8.5mm
Backing	EVERFORT® vinyl
Yarn	regenerated ECONYL® polyamide
Collection size	6
Area of use	Commercial heavy
Reaction to fire	EN 13501-1 B _{fl} -s1, G, NCS
Slip resistance	EN 13893 $\mu > 0.30$
Personal charging	ISO 6356 ≤ 2 kV

coral® grip

Want to know the secret to keeping your interior clean even when it looks like a hopeless cause? Don't start your entrance floor protection inside, start outside – by scraping off the largest soil particles before your visitors even cross the threshold. Coral Grip is a versatile, non-woven clean off barrier mat for outdoor and indoor use that comes in mediumduty (MD) and heavy-duty (HD) formats. Standard Coral Grip has an open, non-backed, pervious structure, though it can also be manufactured with an Everfort vinyl backing to make it impervious. And when the going is really tough, there's Coral Grip HD, whose patented embossed design and durable, pliable vinyl filaments ensure a highly effective dirt-scraping action.



The robust and ultimate dirt and grit remover

- Contains granulates for maximum non-slip performance
- Cleans off the worst dirt before it can get inside
- Helps protect an inviting interior design street-side
- Suitable for the heaviest commercial use
- Ideal for outside and inside entrance



Description	Non Woven scraping mat
Dimensions	Rolls open 122 cm, with backing 127 cm. Matts 60 x 90 cm (open) Length rolls approx 10 meter (HD) 15 meter (MD)
Total thickness	ISO 1765 Open structure approx. 16 mm (HD) 11 mm (MD) With backing approx. 17 mm (HD) 12 mm (MD)
Backing	EVERFORT vinyl
Yarn	solution dyed vinyl with anti-slip granulate particles
Collection size	4
Area of use	Commercial heavy
Reaction to fire	EN 13501-1 B _{fl} -s1, G, NCS
Slip resistance	EN 13893 $\mu > 0.30$
Personal charging	ISO 6356 ≤ 2 kV

open structure closed structure




Coral grip 6148 | grass

The first steps in protecting your building.

Coral Click is an exceptionally versatile 'off the shelf' modular matting system that can be assembled on site. Coral Click can be used on its own or in conjunction with our Coral clean-off textile ranges to provide an integrated entrance system.

This versatile PVC tile with Coral textile inserts can be used in all types of buildings and, because it contains no metal components, Coral Click entrance products are particularly suitable for installation in retail environments as they do not interfere with electronic-tagging systems.




- 'Off the shelf' modular matting system
- Exceptionally easy to fit, handle and store
- Available in 12mm & 17mm depths
- Textile inserts from the award winning Coral Brush collection
- Coral Brush insert is produced using 100% Econyl® regenerated yarn
- Coral Entrance flooring systems removes up to 95% of dirt and moisture from shoes and wheeled traffic
- 5 year guarantee



Description	Modular matting system	
Dimensions	24 x 24cm	
Total thickness	ISO 1765	11/16mm (without textile insert) 14/19mm (with Coral Brush insert)
Pile material	100% regenerated Econyl® Nylon	
Collection size	6	
Application	EN 1307	Class 33
CE	EN 14041	



7830 (12mm) | 7880 (17mm)



7833 (12mm) | 7883 (17mm)



7831 (12mm) | 7881 (17mm)



7834 (12mm) | 7884 (17mm)



7838 (12mm) Plain | 7888 (17mm) Plain



7837 (12mm) | 7887 (17mm)

When price is key

Fancy colours lighten up your entrance and create a welcoming atmosphere. With Coral bright you choose an economically attractive entrance floor that still has Coral functionalities.




Coral Bright 2607 | deep water, 2603 | vivid earth


- Comfortable and soft feel
- Suitable for entrances with low to medium footfall
- Attractive colours
- Also available in tiles




2604 | virgin sand LRV 10



2610 | cold lava LRV 2



2606 | fine peat LRV 2



2608 | fresh grass LRV 11



2607 | deep water LRV 3



2603 | vivid earth LRV 23

Description	Tufted cut pile	
Dimensions	27,5 m x 90 cm 27,5 m x 130 cm 27,5 m x 200 cm 50 x 50 cm mats: 60 x 90 cm 90 x 150 cm	
Total thickness	ISO 1765	Approx 8.5mm
Backing	EVERFORT® vinyl	
Yarn	Solution dyed regenerated ECONYL® polyamide	
Area of use	Commercial medium	
Reaction to fire	EN 13501-1	B _{fl} -s1, G, NCS
Slip resistance	EN 13893	μ > 0.30
Personal charging	ISO 6356	≤ 2 kV

Modularity in optima forma

Designing a nice building and interior comes with taking care of it. When using Coral interior as the circulation product in hallways, lounges and lobbies an integrated entrance system is covered. The colours of Coral interior are coordinated with other entrance products so a natural flow creates a coordinated look. The installation is extremely easy, tiles and planks are being randomly placed and installation waste is reduced to a minimum.

- Mix of planks and tiles for ultimate random effect
- Easy and quick installation (no pattern)
- Unique product for both entrance and circulation zone
- Colour matching with other entrance products
- Suitable for the toughest commercial use



Description	Tufted cut pile	
Available in tiles	50x50 cm & 100x25 cm / 6+6 per box / 3 m ²	
Total thickness	ISO 1765	Approx 10 mm
Backing	EVERFORT [®] vinyl	
Yarn	regenerated ECONYL [®] polyamide solution dyed polyamide	
Area of use	Commercial heavy	
Reaction to fire	EN 13501-1	B ₁ -s1, G, NCS
Slip resistance	EN 13893	μ > 0.30
Personal charging	ISO 6356	≤ 2 kV



Coral interior 1525 | prairie dusk



1521 | Alpine peak

LRV 10



1520 | desert sand

LRV 7



1525 | prairie dusk

LRV 5



1518 | rain forest

LRV 3



1515 | storm cloud

LRV 4



1517 | ocean spray

LRV 2



1530 | midnight shadow

LRV 1



1513 | savanna sunset

LRV 1

marmoleum®

FORBO'S LINOLEUM BRAND

The Marmoleum collections provide the largest color bank in resilient flooring, a beautiful array of structures and designs that connects the colors of the indoor space. Made from natural raw materials Marmoleum is the most sustainable resilient floor around.

Sheet Marmoleum

Forbo's sheet Marmoleum comprises 3 collections – Marbled, Solid and Linear.

marmoleum® marbled

Taking inspiration from the natural world, and offering a spectrum of over 90 colours across the Fresco, Real, Terra, Vivace and Splash ranges, the Marmoleum Marbled collection combines both subtle and striking marbled effects to create a range that provides the perfect backdrop for any commercial interior.



marmoleum® solid

The five individual finishes provide the foundation for creating pure, distinctive and modern spaces. The Solid collection combines contemporary styling with a versatility that enables designers to design an elegant, natural backdrop to any interior.



marmoleum® linear

This Linear collection offers a relevant, functional and desirable range that allows you to create comfortable spaces with a natural touch where you truly feel at home. The directional Linear pattern can be used to create a floor that guides people from one space to another, and to indicate an area within a larger space.




MARMOLEUM COLLECTION AT A GLANCE

marmoleum®

ohmex | decibel | acoustic

(special acoustic and static dissipative varieties)

In addition to our standard ranges, we also offer a number of linoleum floor coverings developed to meet specific technical or comfort requirements, including static control and sound reduction.



marmoleum® sport

Floor coverings in sports and multipurpose halls have extensive requirements to meet. A sports floor with Marmoleum Sport as a top layer diminishes the risk of injuries, reduces the risk on muscle fatigue and overstraining. The top layer guarantees optimal performance in terms of anti-slip and glide.



marmoleum® modular

Comprising 6 distinct design ranges – Lines, Textura, Slate, Shade, Marble and Colour, the Marmoleum Modular collection offers 100 x 25cm planks and 50 x 25cm and 50 x 50cm tiles to allow complete design freedom.



marmoleum® click

Our Marmoleum Click panels are very durable and simple to care for. The smooth surface is easy to clean while its beautiful colours won't fade over time. Marmoleum Click is available in 23 colours and 3 panel sizes, which offers great design opportunities to create your own unique floor.



bulletin board®

Pinboard linoleum, or Bulletin Board, offers a practical, simple solution to collect and exchange thoughts and ideas wherever people plan, create and meet. Simply share your thoughts by pinning your idea onto the wall.



furniture linoleum

Furniture Linoleum is a decorative surfacing material that can be applied to vertical, horizontal and curved surfaces, providing interior furniture with a truly distinctive and individual look.






Marmoleum Fresco | 3259 mustard

Marmoleum is over 150 years old and is a natural floor covering that is associated with sustainability, durability, high quality and innovative design.

Discover the versatile world of Marmoleum with over 300 colours and more than 12 different structures to choose from, available in sheet and modular tile formats.

Marmoleum stands for versatility in application as well as in colour and design.

What makes Marmoleum special is that it is created from 97% natural raw materials that give it its unique performance attributes.



CO₂ neutral

With Marmoleum you are actually choosing a floor that is CO₂ neutral, by nature, from cradle to gate. The raw materials used for creating linoleum have absorbed such an amount of CO₂ during the time the plants, trees and crops matured, that this amount of CO₂ actually exceeds the amount of CO₂ that is emitted during the production process of the product. Each square meter of Marmoleum sheet delivers a bonus to the environment and reduces CO₂ emissions.

Topshield

All Marmoleum floors include Topshield, a double UV-cured finish which is scratch and scuff resistant, easy to maintain and ensures a long lasting appearance retention. Topshield is also naturally bacteriostatic, resistant to chemicals and hand disinfectants making it an ideal solution for all heavy traffic environments such as schools, healthcare, offices and public buildings.

Marmoleum has been awarded with a large array of international environmental certificates such as the Nordic Swan, the Blue Angel, Nature Plus. In addition Marmoleum floor covering improves the environmental and well-being score in building ratings such as LEED, Breeam and the Well building standard.

marmoleum® marbled

fresco | real | terra | vivace | splash



Fresco: a strong palette of tone in tone colors creating a fresh, delicate and balanced aesthetic with a soft contrast and a refined marbled structure.

Real: the 'royal' classic blend of carefully selected colors, developed to create choice and mixes of color ranging from warm neutrals to calm greys as well as exiting brights and fashion shades.

Terra: a new design with a close and highly contrasting structure inspired by ingenious rock types. It creates a sophisticated small scale marble with great soil hiding properties in an authentic color mix.

Vivace: Marmoleums' most liveliest and most outspoken blend made with six to eight colors to create a chameleon floor that adapts well to a multitude of interiors.

Splash: a modern playful design which from a distance appears a contemporary light grey solid floor with a slight nuance in tone, yet from up close surprising colors are peeking through, offering great combinations of interior elements.



3883 | moonstone LRV 45



3257 | edelweiss LRV 58 3860 | silver shadow LRV 48 3136 | concrete LRV 47



3428 | seashell LRV 45 3032 | mist grey LRV 42 3405 | Granada LRV 28




2621 | dove grey LRV 36 3420 | surprising storm LRV 31 3889 | cinder LRV 30



3053 | dove blue LRV 27 3146 | serene grey LRV 27 5802 | alpine mist LRV 31



3866 | eternity LRV 21 3234 | forest ground LRV 33 2499 | sand LRV 56 3038 | Caribbean LRV 55



5801 | river bank LRV 29 3890 | oat LRV 31 3407 | donkey island LRV 36 5803 | weathered sand LRV 31 3254 | clay LRV 17



2629 | eiger LRV 19 3137 | slate grey LRV 16 3872 | volcanic ash LRV 10 3139 | lava LRV 9 2939 | black LRV 5

Description	Linoleum sheet	
Dimensions	EN-ISO 24341	Roll width 2.0m Roll length ≤ 32m
Total thickness	EN-ISO 24346	2/2.5/3.2mm
Collection size	90	
Application	EN-ISO 10874	Class 23/34/43
CE	EN 14041	
Reaction to fire	EN 13501-1	C _{fl} -s1
Slip resistance	EN 13893	DS: ≥0.30

Our recommended adhesive is 414 Euroflex Lino Plus or 614 Eurostar Lino Plus. Full technical specifications are available at www.forbo-flooring.com

3421 | oyster mountain LRV 17 3048 | graphite LRV 14 3872 | volcanic ash LRV 10 3139 | lava LRV 9 2939 | black LRV 5

marmoleum® marbled

fresco | real | terra | vivace | splash



3858 | Barbados LRV 65 2713 | calico LRV 53 3861 | Arabian pearl LRV 50 3120 | rosato LRV 51 3141 | Himalaya LRV 40



3433 | rockpool LRV 46 3232 | horse roan LRV 40 5804 | pink granite LRV 27 3252 | sparrow LRV 29



3246 | shrike LRV 21 3234 | forest ground LRV 33 2499 | sand LRV 56 3038 | Caribbean LRV 55



5803 | weathered sand LRV 31 3254 | clay LRV 17 5801 | river bank LRV 29 3890 | oat LRV 31 3407 | donkey island LRV 36






3233 | shitake LRV 23 3426 | cork tree LRV 16 3874 | walnut LRV 11 3236 | dark bistre LRV 7 3427 | agate LRV 39 3075 | shell LRV 44





3236 | dark bistre LRV 7 3427 | agate LRV 39 3075 | shell LRV 44

BREEAM generic ratings
Marmoleum – Linoleum (plain and decorative EN548)
 Please note: Digital representations may vary from the actual product.
 Please order a sample to see the full effect. www.forbo-flooring.com



Description	Linoleum sheet	
Dimensions	EN-ISO 24341	Roll width 2.0m Roll length ≤ 32m
Total thickness	EN-ISO 24346	2/2.5/3.2mm
Collection size	90	
Application	EN-ISO 10874	Class 23/34/43
CE	EN 14041	
Reaction to fire	EN 13501-1	C _s -s1
Slip resistance	EN 13893	DS: ≥0.30

Our recommended adhesive is 414 Euroflex Lino Plus or 614 Eurostar Lino Plus. Full technical specifications are available at www.forbo-flooring.com




marmoleum® ohmex



Ohmex Static Dissipative Linoleum meets the higher requirements for electrical conductivity.

Electrical resistance is improved to $< 1 \cdot 10^8$ (EN1081), ensuring personal safety and protecting equipment that is sensitive to static electricity. Marmoleum Ohmex, which is 2.5 mm thick, is available in four colours. Typical areas of use are computer/server rooms and areas with sensitive electrical equipment.



Marmoleum Ohmex 73055 | fresco blue



73032 | mist grey LRV 42



73048 | graphite LRV 14



73038 | Caribbean LRV 55

Description		Linoleum sheet
Dimensions	EN-ISO 24341	Roll width 2.0m Roll length \leq 32m
Total thickness	ISO 1765	2.5mm
Collection size		4
Application	EN 1307	Class 23/34/42
Electrical resistance	EN 1081	$1 \cdot 10^8 < R_1 < 1 \cdot 10^9 \Omega$ static dissipative
CE	EN 14041	
Reaction to fire	EN 13501-1	C _{fl} -s1
Slip resistance	EN 13893	DS: \geq 0.30

Our recommended adhesive is 615 Eurostar Lino EL. Full technical specifications are available at www.forbo-flooring.com

marmoleum® acoustic



Marmoleum Acoustic has a total thickness of 4mm and reduces impact sound by 14 dB (ISO 717-2).


It is a twinlayer linoleum built up from 2mm of Marmoleum and 2mm Corkment backing. Using Marmoleum Acoustic reduces installation costs as it can be installed in one go, avoiding the need to first lay Corkment and then Marmoleum. Marmoleum Acoustic is available in six colours.



Marmoleum Acoustic 33048 | graphite



33032 | mist grey LRV 42



33038 | Caribbean LRV 55



33139 | lava LRV 9



33075 | shell LRV 44




33048 | graphite LRV 14



73055 | fresco blue LRV 23



1200 | corkment



Description		Linoleum sheet
Dimensions	EN-ISO 24341	Roll width 2.0m Roll length \leq 32m
Total thickness	ISO 1765	4.0mm
Collection size		6
Application	EN 1307	Class 23/34/41
Acoustical impact noise reduction		\leq 14 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	C _{fl} -s1
Slip resistance	EN 13893	DS: \geq 0.30

Our recommended adhesive is 540 Eurosafe Special or 640 Eurostar Special. Full technical specifications are available at www.forbo-flooring.com

marmoleum® decibel





Marmoleum Decibel is 3.5mm thick and provides an impact sound reduction of 18 dB. The acoustic performance is achieved by laminating 2.5mm Marmoleum onto a 1mm thick layer of polyolefin foam.

Marmoleum Decibel is also available in all Marmoleum colours as a made-to-order item with an 18 dB impact sound rating. Please note that minimum order quantities and lead times will apply. Please contact Forbo Customer Service for more details.

Description	Linoleum sheet	
Dimensions	EN-ISO 24341	Roll width 2.0m Roll length ≤ 32m
Total thickness	ISO 1765	3.5mm
Collection size	33	
Application	EN 1307	Class 23/34/41
Acoustical impact noise reduction	≤ 18 dB	
CE	EN 14041	
Reaction to fire	EN 13501-1	C _s -s1
Slip resistance	EN 13893	DS: ≥0.30

Our recommended adhesive is 540 Eurosafe Special or 640 Eurostar Special. Full technical specifications are available at www.forbo-flooring.com



MARMOLEUM MARBLED SHEET ADDITIONAL OPTIONS BY COLOUR



Design	Gauge		Other functionalities			Available until end of 2028
	2.0mm	3.2mm	Decibel 18dB	Acoustic 14dB	Ohmex static control	
Real – 2499 sand	●					
Real – 2621 dove grey			●			
Real – 2629 eiger	●					
Real – 2713 calico	●					
Real – 2939 black	●				●	●
Real – 3030 blue	●		●			●
Real – 3032 mist grey	●	●		●	●	●
Real – 3038 Caribbean	●	●	●	●	●	●
Real – 3048 graphite	●	●	●	●	●	●
Real – 3053 dove blue	●		●			●
Real – 3055 fresco blue	●	●		●	●	●
Real – 3075 shell	●	●				●
Real – 3120 rosato			●			
Real – 3125 golden sunset	●					
Real – 3126 Kyoto	●					
Real – 3127 Bleeckerstreet	●		●			●
Real – 3136 concrete	●					●
Real – 3139 lava	●	●		●		●
Real – 3141 Himalaya						●
Real – 3146 serene grey	●	●	●		●	●
Real – 3173 Van Gogh	●					●
Real – 3174 Sahara	●					
Real – 3203 henna	●		●			●
Real – 3224 chartreuse	●		●			●
Real – 3225 dandelion			●			●
Real – 3233 shitake	●					
Real – 3234 forest ground	●					
Real – 3236 dark bistre	●					
Real – 3252 sparrow	●	●	●	●		●
Real – 3254 clay	●					
Fresco – 3246 shrike			●			
Fresco – 3251 lemon zest	●					
Fresco – 3825 African desert	●					
Fresco – 3828 blue heaven	●					●
Fresco – 3846 natural corn	●					●
Fresco – 3847 golden saffron	●					
Fresco – 3858 Barbados	●					●
Fresco – 3860 silver shadow	●		●			●
Fresco – 3861 Arabian pearl	●					
Fresco – 3866 eternity	●					●
Fresco – 3872 volcanic ash	●		●			
Fresco – 3874 walnut	●					
Fresco – 3881 green wellness	●					

All of the Marbled colours are available in a 2.5mm gauge. However, a number of colourways are also available in different gauges and functionalities. The table above shows which colours are available in each option.



It is the composition of ingredients that makes Marmoleum Sport so unique. It meets all the requirements of an ecologically superior product construction and combines a wealth of positive performance characteristics, the end result of the material composition as such.

Linseed oil obtained from the seeds of the flax plant is the main component of Marmoleum Sport. Together with natural rosin, limestone and wood flour the linoleum substrate is created, which is coloured by adding natural or nature-based colour pigments.

High level sports flooring performance

- Flexible and elastic
- Multi-purpose (in combination with the appropriate subfloor system)
- Slip resistant
- Durable
- Insensitive to friction heat
- Warm to touch
- Flame retardant
- Suitable for underfloor heating
- Cigarette burn resistant



83283 | light grey



Description	Linoleum sheet	
Dimensions (length x width)	EN-ISO 24341	Roll with 2.00 m Roll length ≤28 m
Total thickness	EN-ISO 24346	3,2 mm / 4,0 mm
Collection size	11	
CE	EN 14041	
Reaction to fire	EN 13501-1	C _s -s1, G, CS



83283 | light grey

LRV 37%
NCS S 3502-Y



83110 | dark blue

LRV 15%
NCS S 4040-B



83056 | blue

LRV 24%
NCS S 4020-B




83020 | beige

LRV 50%
NCS S 2010-Y10R



83147 | grey

LRV 25%
NCS S 5005-G50Y



83707 | black

LRV 7%
NCS S 8500-N



83288 | dark green

LRV 26%
NCS S 3040-G10Y




83285 | green

LRV 37%
NCS S 2050-G50Y



83284 | yellow

LRV 51%
NCS S 1050-Y



83287 | red

LRV 19%
NCS S 1580-Y80R



83286 | orange

LRV 31%
NCS S 1060-Y50R



83287 | red

marmoleum® solid

cocoa | concrete | piano | slate | walton

Marmoleum Solid is a contemporary collection that fits perfectly with the desire for more solid visuals and raw tactility. With its variety of plain to semi-plain aesthetics, it provides a large choice of honest designs that give the collection a strong, modern, identity. Solid has been designed to combine beautifully with other natural materials such as wood, glass and metal.



marmoleum® walton




marmoleum® cocoa

Marmoleum Cocoa, innovation that comes naturally


Marmoleum Cocoa embraces our ethos of sustainable design and is a truly new addition to the collection. By using a waste product from another industry we are collaborating to reduce waste, improve recycling and contribute to a better environment. By adding cocoa shells to the traditional Marmoleum ingredients we have created an innovation in construction and aesthetics. The result is a new and exciting surface texture that is both natural looking and contemporary in feel. The inclusion of cocoa adds a rich look that is fresh, modern and yet uniquely Marmoleum.



reddot award 2017 winner



marmoleum® piano



Description	Linoleum sheet	
Dimensions	EN-ISO 24341	Roll width 2.0m Roll length ≤ 33 lm
Total thickness	EN-ISO 24346	2.5mm
Collection size	78	
Application	EN-ISO 10874	Class 23/34/43
CE	EN 14041	
Reaction to fire	EN 13501-1	C _{fl} -s1
Slip resistance	EN 13893	DS: ≥0.30

Our recommended adhesive is 414 Euroflex Lino Plus or 614 Eurostar Lino Plus. Full technical specifications are available at www.forbo-flooring.com

marmoleum® concrete




Marmoleum Concrete 3704 | satellite + 3724 | orbit



3733 | yellow shimmer LRV 42



3712 | orange shimmer LRV 31



3737 | red shimmer LRV 15



3735 | purple shimmer LRV 18



3734 | blue shimmer LRV 20



3736 | green shimmer LRV 15



3738 | orange glow LRV 27



3743 | red glow LRV 14



3740 | purple glow LRV 21



3739 | blue glow LRV 16



3742 | green glow LRV 39



3741 | yellow glow LRV 58



Marmoleum Concrete 3733 | yellow shimmer + 3741 | yellow glow

Description	Linoleum sheet	
Dimensions	EN-ISO 24341	Roll width 2.0m Roll length ≤ 33 lm
Total thickness	EN-ISO 24346	2.5mm
Collection size	78	
Application	EN-ISO 10874	Class 23/34/43
CE	EN 14041	
Reaction to fire	EN 13501-1	C _{s1}
Slip resistance	EN 13893	DS: ≥0.30

Our recommended adhesive is 414 Euroflex Lino Plus or 614 Eurostar Lino Plus. Full technical specifications are available at www.forbo-flooring.com

Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect. www.forbo-flooring.com



3732 | asteriod LRV 45



3724 | orbit LRV 37



3704 | satellite LRV 23



3723 | nebula LRV 17




3706 | beton LRV 28



3705 | meteorite LRV 16



3703 | comet LRV 14



3707 | black hole LRV 7



3728 | kaolin LRV 36



3708 | fossil LRV 34



3702 | liquid clay LRV 23



3568 | delta lace LRV 13



3711 | cloudy sand LRV 49



3729 | mica LRV 42



3727 | drift LRV 31



3709 | silt LRV 22



3701 | moon LRV 61



3726 | Venus LRV 52



3730 | Stella LRV 17



3731 | flux LRV 22

marmoleum® slate

Inspired by the natural texture of stone, Marmoleum Slate introduces a unique embossed texture that adds a new dimension to our Marmoleum flooring. The result is a surface that has the timeless aesthetic of stone with the warmth and purity of linoleum.



e3747 | Lakeland shale




reddot award 2017
winner



e3745 | Cornish grey LRV 15



e3746 | Newfoundland slate LRV 11



e3725 | Welsh slate LRV 9



e3707 | Highland black LRV 7



Marmoleum Slate e3725 | Welsh slate

marmoleum® linear

striato



Marmoleum Linear is designed to create a contemporary, comfortable environment with a warm and welcoming feel for informal, natural settings with a homely atmosphere. A setting where we will recover faster, feel encouraged to work, share ideas, and to learn. With an intuitive reference to nature, the Linear collection allows you to create various atmospheres within a space, adjusting to changing needs. The neutral, rich colours have the ability to easily adapt and come to life when combined with each other and other materials. With Linear, the floor can act as a canvas offering endless possibilities.



3573 | trace of nature 5250 | blue basalt



5257 | sandy chalk LRV 61



5232 | rocky ice LRV 47



5248 | urban silver LRV 41



5249 | Stonehenge LRV 33



3573 | trace of nature LRV 28



5250 | blue basalt LRV 27



5251 | black glacier LRV 19



5231 | Cliffs of Moher LRV 18

	Striato		Striato Decibel
Description		Linoleum sheet	Linoleum sheet
Dimensions	EN-ISO 24341	Roll width 2.0m Roll length ≤ 33m	Roll width 1.95 / 2.0m Roll length ≤ 33m
Total thickness	EN-ISO 24346	2.5mm	3.5mm
Collection size		16	On request
Acoustical impact noise reduction	EN-ISO 717-2		18 dB
Application	EN-ISO 10874	Class 23/34/43	Class 23/33/41
CE	EN 14041	0100201-DoP-306	0100207-DoP-306
Reaction to fire	EN 13501-1	Cfl-s1,G,CS	Cfl-s1,G,CS
Slip resistance	EN 13893	DS: ≥0.30	DS: ≥0.30

Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product.
Please order a sample to see the full effect. www.forbo-flooring.com



5252 | ivory shades LRV 52



5255 | desert sand LRV 48



5256 | silt stone LRV 44



5253 | bleached gold LRV 47



5217 | withered prairie LRV 25




5218 | Welsh moor LRV 8



5225 | compressed time LRV 34



5254 | red horse 3370 | terracotta (Marmoleum Walton)



5254 | red horse LRV 18

MARMOLEUM® CASE STUDIES



5251 | black glacier 5253 | bleached gold



PROJECT:
Sunderland
Royal Hospital

LOCATION:
Sunderland

DESIGNER: P+HS Architects

FLOORING MATERIAL:
Marmoleum Marbled 3131 | scarlet + 3847 | golden saffron + 3245 | summer pudding + 3885 | spring buds + 3858 | Barbados + 3238 | laguna + Marmoleum Decibel 303035 | blue

See page 54 for the full Marmoleum Marbled range and page 60 for the Decibel range.




PROJECT:
Catapult Energy
Systems

LOCATION:
Birmingham

DESIGNER: Monteith Scott

FLOORING MATERIAL:
Marmoleum Modular Linear t5218 | Welsh Moor + t5225 | compressed time + t3573 | trace of nature

See page 74 for the full Marmoleum Modular Lines range.



PROJECT:
Glasgow
Caledonian
University

LOCATION:
Glasgow

DESIGNER: Toby Paterson

FLOORING MATERIAL: Marmoleum Marbled 3238 | laguna + 3219 | spa + 3882 | relaxing lagoon + Marmoleum Modular Linear t5232 | rocky ice + t3573 | trace of nature + t5226 | grey granite

See page 54 for the full Marmoleum Marbled range and page 74 for the Marmoleum Modular Lines range.

marmoleum® modular


MARMOLEUM IN TILE AND PLANK FORMAT

Marmoleum Modular is a collection with a twist, offering over 50 colours and 3 different tile and plank sizes, that enable individual and sustainable flooring designs to be created. Similarly to Marmoleum Sheet, the Marmoleum Modular collection is split into six design styles – Lines, Textura, Shade, Slate, Colour and Marbled.

88%
natural
raw materials

76%
rapidly
renewable

58%
recycled
content



With our Committed to the Health of One programme, we strive to create better indoor environments and Marmoleum is a prime example of this commitment. Naturally bacteriostatic, Marmoleum does not harbour allergens and holds the Allergy UK Seal of Approval™. It has low VOCs contributing to positive indoor air quality and has high LRVs which help create positive environments in which to work, live and play. Marmoleum is also protected by a unique water based finish 'Topshield2' which ensures no hiding place for dirt or bacteria.

MARMOLEUM MODULAR COLLECTION AT A GLANCE

marmoleum® modular | lines

Bringing the linearity trend into the colour spectrum of the 21st Century, the new Marmoleum Modular Lines range features a palette of 11 striated colours – from cool whites and greys to warm and softer wood tones.



marmoleum® modular | textura

Reflecting both the warm and cool tones of natural wood, our wood grain and saw cut embossing effects bring another dimension to Marmoleum Modular.




marmoleum® modular | shade

The shade colourways are designed to complement each other and the palette is presented in delicate steps of colour intensity and hue to create natural realistic stone and concrete patterns.



marmoleum® modular | slate

Featuring a cool concrete palette with our unique slate embossing delivering a contemporary yet natural finish to floor design.



marmoleum® modular | colour

The Colour range features fashionable pastels alongside a modern mix of colourful concrete varieties and a full spectrum of bright warm colours which liven up the palette.



marmoleum® modular | marbled

Classic and contemporary marbled colours have been created to mix and match giving an extra dimension to your floor plan.



marmoleum® modular | lines



Lines: Bringing the linearity trend into the colour spectrum of the 21st Century, the new Marmoleum Modular Lines range features a palette of 11 striated colours – from cool whites and greys to warm and softer wood tones.

Available as 100 x 25cm planks, Marmoleum Modular Lines can be used on its own to striking effect or can be combined with elements from the Marmoleum Modular Textura, Colour, Shade, Slate or Marbled ranges to create truly unique flooring designs.

Plank size
100 x 25 cm



Marmoleum Modular Lines **t3573** | trace of nature + **t5231** | Cliffs of Moher + **t5232** | rocky ice



t3575 | white cliffs LRV 57



t5232 | rocky ice LRV 44



t5226 | grey granite LRV 29



t3573 | trace of nature LRV 27



t5230 | white wash LRV 49



t5235 | North Sea coast LRV 32



t5225 | compressed time LRV 34



t5237 | black sheep LRV 18



t5231 | Cliffs of Moher LRV 17



t5218 | welsh moor LRV 8



t5217 | withered prairie LRV 23

Description	Linoleum tile
Dimensions (length x width)	EN-ISO 24342 100 x 25cm
Packaging per carton	3m ² (12 tiles)
Total thickness	EN-ISO 24346 2.5mm
Collection size	11
Application	EN-ISO 10874 Class 23/34/43
CE	EN 14041
Reaction to fire	EN 13501-1 C _s -s1
Slip resistance	EN 13893 DS: ≥0.30

Our recommended adhesive is 414 Euroflex Lino Plus or 646 Eurostar Premium. Full technical specifications are available at www.forbo-flooring.com

marmoleum® modular | textura



A succinct collection of 7 tones, each featuring either a wood grain or saw cut embossed finish to complement the design, Marmoleum Modular Textura can be used on its own or alongside its Lines counterparts to add depth and texture to flooring concepts.

Plank size
100 x 25 cm



Marmoleum Modular Textura **te3573** | trace of nature

Description	Linoleum tile
Dimensions (length x width)	EN-ISO 24342 100 x 25cm
Packaging per carton	3m ² (12 tiles)
Total thickness	EN-ISO 24346 2.5mm
Collection size	7
Application	EN-ISO 10874 Class 23/34/43
CE	EN 14041
Reaction to fire	EN 13501-1 C _s -s1
Slip resistance	EN 13893 DS: ≥0.30

Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect. www.forbo-flooring.com
Our recommended adhesive is 414 Euroflex Lino Plus or 646 Eurostar Premium. Full technical specifications are available at www.forbo-flooring.com



te3573 | trace of nature LRV 27



te5231 | Cliffs of Moher LRV 17



te5230 | white wash LRV 49



te5235 | North Sea coast LRV 32



te5217 | withered prairie LRV 23



te5229 | fresh walnut LRV 15



te5218 | Welsh moor LRV 8




Marmoleum Modular Textura **te5218** | Welsh moor

marmoleum® modular | shade | slate



Shade offers a collection of concrete structures in cool and warm greys as well as classic black and white, all designed to complement each other, while the embossed finish on Slate brings a contemporary finish to the design.



Tile sizes
50 x 25 cm
50 x 50 cm



Description	Linoleum tile
Dimensions (length x width)	EN-ISO 24342 50 x 25cm / 50 x 50cm
Packaging per carton	5m ² (40 tiles) / 5m ² (20 tiles)
Total thickness	EN-ISO 24346 2.5mm
Collection size	10/4/8/11
Application	EN-ISO 10874 Class 23/34/43
CE	EN 14041
Reaction to fire	EN 13501-1 C _{s1} -s1
Slip resistance	EN 13893 DS: ≥0.30

Our recommended adhesive is 414 Euroflex Lino Plus or 646 Eurostar Premium. Full technical specifications are available at www.forbo-flooring.com

marmoleum® modular | colour



Colour: a range featuring a modern mix of colourful concrete varieties and a full spectrum of bright warm colours which liven up the palette. This is the heart of the collection and embodies one of the best known features of Marmoleum, that of colour on the floor. Colours can be used as focus, accents or as a different way to express the environment.




Tile size
50 x 50 cm



marmoleum® modular | marbled

Marble: classic and contemporary marbled colours have been created to mix and match giving an extra dimension to your floor plan. Bring Marmoleum Modular to life by combining marbles to reflect a stone like floor.



BREEAM generic ratings
Marmoleum – Linoleum (plain and decorative EN548)
Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.

marmoleum® click




Our Marmoleum Click panels are very durable and simple to care for. The smooth surface is easy to clean while its beautiful colours won't fade over time. Marmoleum Click is available in 23 colours and 3 panel sizes, which offers great design opportunities to create your own unique floor.

Marmoleum Click also improves live for people with asthmatic allergies and similar disorders. Not only is it anti-static (which is why it is so easy to keep dust-free), but its proven bacteriostatic properties inhibit micro-organisms as well.



Marmoleum Modular Click 333355 | rosemary green

Tile sizes
30 x 30 cm
60 x 30 cm

		
silver shadow LRV 48 % 30 x 30 cm 333860 60 x 30 cm 633860	moon LRV 61 % 30 x 30 cm 333701 60 x 30 cm 633701	Barbados LRV 65 % 30 x 30 cm 333858 60 x 30 cm 633858
		
eternity LRV 21 % 30 x 30 cm 333866 60 x 30 cm 633866	orbit LRV 37 % 30 x 30 cm 333724 60 x 30 cm 633724	cloudy sand LRV 49 % 30 x 30 cm 333711 60 x 30 cm 633711
		
volcanic ash LRV 10 % 30 x 30 cm 333872 60 x 30 cm 633872	nebula LRV 17 % 30 x 30 cm 333723 60 x 30 cm 633723	liquid clay LRV 23 % 30 x 30 cm 333702 60 x 30 cm 633702
		
raven LRV 5 % 30 x 30 cm 333209 60 x 30 cm 633209	black hole LRV 7 % 30 x 30 cm 333707 60 x 30 cm 633707	delta lace LRV 13 % 30 x 30 cm 333568 60 x 30 cm 633568



333866 - 333355 - 333885 - 333360



Tile sizes
30 x 30 cm

	
333363 lilac LRV 38 % 30 x 30 cm	333360 vintage blue LRV 29 % 30 x 30 cm
	
333355 rosemary green LRV 21 % 30 x 30 cm	333358 petrol LRV 9 % 30 x 30 cm
	
333885 spring buds LRV 46 % 30 x 30 cm	333238 laguna LRV 30 % 30 x 30 cm
	
333251 lemon zest LRV 52 % 30 x 30 cm	333131 scarlet LRV 13 % 30 x 30 cm



933573 - 633702

Tile sizes
90 x 30 cm

		
935216 Pacific beaches LRV 48 % 90 x 30 cm	933573 trace of nature LRV 27 % 90 x 30 cm	935217 withered prairie LRV 23 % 90 x 30 cm

Description	Linoleum tile
Dimensions (length x width)	30 x 30 cm 60 x 30 cm 90 x 30 cm
Packaging per carton	5m ² (40 tiles) / 5m ² (20 tiles)
Total thickness	EN-ISO 24346 9,8mm
Collection size	20/12/3
Application	EN-ISO 10874 Class 23/33
CE	EN 14041
Reaction to fire	EN 13501-1 C _{fl} -s1
Slip resistance	EN 13893 DS: ≤0.30



Bulletin Board 2204 poppy seed | 2214 blue berry

OFF THE FLOOR LINOLEUM COLLECTION AT A GLANCE

bulletin board®

Pinboard linoleum, or Bulletin Board, offers a practical, simple solution to collect and exchange thoughts and ideas wherever people plan, create and meet. Simply share your thoughts by pinning your idea onto the wall.



furniture linoleum | desktop

Furniture Linoleum is a decorative surfacing material that can be applied to vertical, horizontal and curved surfaces, providing interior furniture with a truly distinctive and individual look.



bulletin board®



Pinboard linoleum, or Bulletin Board, offers a practical, simple solution to collect and exchange thoughts and ideas wherever people plan, create and meet. Simply share your thoughts by pinning your idea onto the wall.

Bulletin Board is an all natural material that can be applied in framed pin boards or directly onto the wall. Its surface is tactile and colourful, creating a decorative element in your space, in addition to being a practical aid in your day to day activity.



Bulletin Board 2162 | duck egg + 2166 | nutmeg spice + 2186 | blanched almond + 2210 | hot salsa



Description	Bulletin Board
Dimensions	EN-ISO 24341 Roll width 1.22m *(3 items available in 1.83m) Roll length ≤ 28m
Total thickness	ISO 1765 6.0mm
Collection size	15
Force on pins – Perpendicular to pin direct LH000421	25 N (typical)
Force on pins – Perpendicular to pin at 7mm LH000421	10 N (typical)
Force on pins – Parallel to pin (pulling the pin out) LH000421	15 N (typical)

Our recommended adhesive is 414 Euroflex Lino plus and 530 Eurosafe Cork. Full technical specifications are available at www.forbo-flooring.com

furniture linoleum | desktop




Elegant and natural

Forbo's Furniture Linoleum Desktop is a natural surfacing material that delivers the finishing touch for all high end 3D furniture designs such as desks, chairs, stools, cabinets, doors and displays. The material is flexible and can be applied as a surface on all kinds of constructions. Furniture Linoleum is renowned for its elegance and durability, radiating high quality and finesse.

Warm and tactile

Furniture Linoleum delivers a combination of a satin matt surface with a warm, fine texture creating interior furniture with a truly distinctive, genuinely individual look and feel that really is unlike any other surface material available. The natural character of Furniture Linoleum Desktop means that the material achieves a beautiful patina over time.



Bulletin Board 4184 | olive



4180 | aquavert

LRV 35



Description	Linoleum sheet
Dimensions	EN-ISO 24341 Roll width 1.83m (2.0m – Nero only) Roll length ≤ 30m
Total thickness	ISO 1765 2.0mm
Collection size	21

Our recommended adhesive is 233 Eurosol Contact. Full technical specifications are available at www.forbo-flooring.com

Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.

PROJECT VINYL

Forbo Flooring Systems has been producing floor coverings for over 100 years and our project vinyl brands are well established in the world of flooring.

Our complete vinyl portfolio offers flooring solutions that encompass general purpose (both heterogeneous and homogeneous), safety, acoustic, adhesive free, static control, design tiles and wetroom solutions.

Produced and designed in Europe, Forbo's project vinyl ranges offer eye-catching designs with exceptional performance and a low maintenance, stain resistant finish.

allura®

Luxury vinyl tiles

Produced and designed in Europe, Allura is a versatile luxury vinyl tile (LVT) collection with products that suit a wide range of applications and functionalities including loose lay, click and safety options.



sphera®

General purpose homogeneous vinyl

Sphera is Forbo's homogeneous vinyl collection. Styled by our European design team and using the latest production technology. The Sphera collection also contains ESD options.



eternal®

Heterogeneous vinyl


Forbo's Eternal general purpose vinyl collection offers a superb combination of state-of-the-art designs in a strong, durable, fit-for-purpose range; suitable for any commercial interior. Create your own, truly individual floor with Forbo's bespoke digital printed vinyl.



sarlon®

Acoustic vinyl

Acoustic floors have an important contribution when it comes to reducing noise in buildings. Forbo Flooring is a specialist in acoustic floors with more than 30 years of experience. In our Sarlon acoustic vinyl range we offer floors with an impact sound reduction of up to 19dB in a wide variety of colours and designs.



PROJECT VINYL COLLECTION AT A GLANCE

modul'up®

Adhesive free project vinyl

Modul'up is the best loose lay floor covering available for high traffic applications. It can be installed quickly without adhesives, but is even more time and cost efficient at time of replacement.



step®

Safety vinyl

The Step collection combines highly differentiated aesthetics with outstanding slip resistant properties (with ratings from R10 to R12). In addition, our Surestep Decibel range offers a selection of 12 items with 17dB impact sound reduction, while the new Surestep Digital Print option takes safety flooring to the next dimension.



step® onyx+

Wetroom vinyl

Our Wetroom collection offers a variety of options suitable for use in barefoot and wetroom application areas, along with our Onyx+ range of complementary wall coverings.



colorex®

Static control flooring

For areas that require a more specialised type of flooring, such as electro static discharge (ESD) protected facilities and ISO standard Cleanrooms, Forbo has a range of Colorex products that meet the very highest standards. Colorex is the ideal static control flooring system for sectors such as electronics, pharmaceuticals, health, data centres and server rooms.



LUXURY VINYL TILES

allura® for life

Life is a play with many acts. And every act has its floor to perform on. Which is when the new Allura Luxury Vinyl Tiles collection shows off its ability to meet your creative demands and inspire. A flooring system that suits any scene imaginable. Allura is carefully designed to be flexible, easy to apply, durable and – vitally - give you the design freedom to bring any interior to life.



ALLURA COLLECTION AT A GLANCE

allura® dryback

Allura Dryback offers the largest choice in design, color, size and shape. From classic wood planks to modern concrete and terrazzo tiles. Combine maximum performance from a glued down LVT with great design possibilities with our Dryback ranges Allura Wood & Allura Material.



allura® decibel

Allura Decibel luxury acoustic vinyl tiles. 42 Wood and Material designs combines beautiful floor design with high performance and excellent acoustic properties of 19dB.



allura® flex

Forbo Allura Flex LVT solves many of today's challenges through its tackified installation. Allura Flex offers a selection of natural wood designs, Allura Flex Wood, and a range of robust concretes and modern stones: Allura Flex Material.



allura® colour plus

Featuring our unique dovetail locking system, Allura Colour Plus is ideal for installations when quick refurbishment and high performance are required.



allura® click pro

Our new Allura Click LVT collection provides a clickable design solution for any area up to 1000 m². The 20 natural wood and stone designs allow for beautiful floor designs.



allura® puzzle

Our Allura Puzzle loose lay vinyl tiles have a unique puzzle shaped size of 96x96 cm and are specially designed for loose lay installation. The 12 wood and concrete designs form a well balanced palette that suit a wide range of applications.





allura[®]

for life

Life is a play with many acts. And every act has its floor to perform on. Which is when the new Allura Luxury Vinyl Tiles collection shows off its ability to meet your creative demands and inspire. A flooring system that suits any scene imaginable. Allura is carefully designed to be flexible, easy to apply, durable and – vitally – give you the design freedom to bring any interior to life.

This book is designed to inspire you. To make daring combinations. To conceive plans that have your signature. And to surprise you with strong and durable application solutions. The possibilities, with Allura, are endless.

All the designs here are available in Allura Dryback 0.70 and 0.55 and most as Allura Flex 1.0. A wide selection of designs is also available as Dryback 0.40, Allura Flex 0.55, Allura Click Pro and Allura Puzzle. This offers you the best choice - including circular economy requirements - all in one Allura concept.

Before diving into the designs, here's a quick overview of the application solutions we have to offer:


allura[®] dryback



FULLY ADHERED

- Total design freedom with the largest choice of shapes and sizes
- Most durable and reliable for applications of any size
- Maximum certainty and performance with a glued down product


allura[®] flex^{II}



LOOSE LAY

- Easy and quick
- No need for any adhesive, up to 150 m²
- Tackified loose lay for larger applications
- The stable yet flexible solution for demanding applications of any size
- Special backing for extra comfort and improved acoustics

allura[®] click pro



CLICK CONNECTED

- Clickable solution for any area up to 1000 m²
- Suitable for uneven subfloors and 100% adhesive-free
- Balanced high quality product that will continue to perform, year after year

allura[®] puzzle



PUZZLE CONNECTED LOOSE LAY

- Highest traffic solution with a long-lasting durable performance and stunning look
- Minimal subfloor preparation, quick to install and ready to use immediately
- Strong and stable puzzle connection between the large tile format, in woods and materials

In addition to all these products there is **Allura Decibel**, our silent hero. The best solution for 19dB acoustic requirements in combination with Allura looks and performance.

Okay, it's showtime!

ENDLESS CHOICE FOR YOUR ULTIMATE ALLURA FLOOR!

Under each design/colour in this samplebook we indicate which constructions it is available in:

DR **FL** **CL** **PZ**

The project requirements dictate which product is most suitable.

DR7 – allura dryback wear layer 0.70 mm
DR5 – allura dryback wear layer 0.55 mm
DR4 – allura dryback wear layer 0.40 mm
FL1 – allura flex wear layer 1.00 mm
FL5 – allura flex wear layer 0.55 mm
CL5 – allura click pro wear layer 0.55 mm
PZ7 – allura puzzle wear layer 0.70 mm

The colourway numbers are mentioned below the sample. Add the code above as a suffix after the colourway number to get the right format of the product. Items with multiple executions (size or shape) each have a different colourway number. Please note that not all designs are available from stock in every product construction.

THE SYMBOLS AND ABBREVIATIONS UNDER THE SAMPLES EXPLAINED:



2 or 4 sides bevelled



in register embossing



natural colour variation



Trapezoid shape. Two of the trapezoids together form a 50 x 50 square.

DR

DR | allura dryback (0.70/0.55/0.40)
DR7 | 0.70 **DR5** | 0.55 **DR4** | 0.40

DR * Only available in **DR7** | 0.70 and **DR5** | 0.55

FL

FL | allura flex (1.00/0.55)
FL1 | 1.0 **FL5** | 0.55

FL * Only available in **FL1** | 1.0

CL

CL | allura click pro 0.55
CL5 | 0.55

PZ

PZ | allura puzzle 0.70
PZ7 | 0.70



allura® dryback 0.70 | 0.55 | 0.40

The Allura collection contains our largest range of wood designs including classic, contemporary and modern. The varieties offer excellent realism as they reflect the style and format of their natural inspiration, including the size and shape of the grain and plank.



light giant oak **60288** | 180 x 32 cm | DR FL CL



natural giant oak **60284** | 180 x 32 cm | DR FL CL PZ



grey giant oak **60280** | 180 x 32 cm | DR FL PZ



60280 | grey giant oak



63706 | bleached timber, **63712** | blond timber



bleached timber **63406** | 120 x 20 cm | DR FL CL
63706 | 75 x 15 cm | DR FL



blond timber **63412** | 120 x 20 cm | DR FL CL
63712 | 75 x 15 cm | DR FL



greywashed timber **63408** | 120 x 20 cm | DR FL*



light honey oak **60305** | 150 x 28 cm | DR FL CL



central oak **60300** | 150 x 28 cm | DR FL CL



deep country oak **60302** | 150 x 28 cm | DR FL



rustic anthracite oak **60306** | 150 x 28 cm | DR FL

	Allura 0.70	Allura 0.55	Allura 0.40
Total thickness	EN-ISO 24346 2.5 mm	2.2 mm	2.0 mm
Wear layer thickness	EN-ISO 24340 0.70 mm	0.55 mm	0.40 mm
Domestic use	EN-ISO 10874 Class 23	Class 23	Class 23
Commercial use	EN-ISO 10874 Class 34	Class 33	Class 32
Light industrial use	EN-ISO 10874 Class 43	Class 42	Class 41
DoP	0200130-Dop_105	0200130-Dop_105	0200130-Dop_105
Reaction to fire	EN 13501-1 B _g -s1,G,CS	B _g -s1,G,CS	B _g -s1,G,CS
Thermal conductivity	EN 12524 0.25 W/mK	0.25 W/mK	0.25 W/mK



63534 | light timber gradient



| light serene oak, **63645** | dark serene oak



light serene oak **63641** | 150 x 20 cm | DR FL CL



natural serene oak **63643** | 150 x 20 cm | DR FL CL



dark serene oak **63645** | 150 x 20 cm | DR FL



natural timber **63535** | 120 x 20 cm | DR FL CL



light timber **63533** | 120 x 20 cm | DR FL CL




light timber gradient **63534** | 120 x 20 cm | DR FL*

Image shows multiple planks. Gradient is random and runs length of the plank.

allura® dryback 0.70 | 0.55 | 0.40



warm natural stone DR FL
63695 | 100 x 50 cm



pink natural stone DR FL
63691 | 100 x 50 cm



cool natural stone DR FL
63693 | 100 x 50 cm



whitewash elegant oak DR FL CL
60064 | 120 x 20 cm
Also available in strip
(60064DR7ST/60064DR5ST)



honey elegant oak DR FL PZ
60065 | 120 x 20 cm
60165 | 75 x 15 cm



amber elegant oak DR FL
60068 | 120 x 20 cm
60168 | 75 x 15 cm



60064 | whitewash elegant oak, 63695 | warm natural stone



shell twine DR FL
63659 | 75 x 25 cm



grigio twine DR FL PZ
63658 | 75 x 25 cm



63632 light cement, 63658 grigio twine



63751 | light twine, 63655 | dark twine



blackened oak DR FL
60061 | 100 x 15 cm | ↕
Also available in strip
(60061DR7ST/60061DR5ST)



waxed oak DR FL
60063 | 100 x 15 cm | ↕



dark twine DR FL CL PZ
63655 | 150 x 20 cm
63755 | 75 x 25 cm



natural twine DR FL
63653 | 150 x 20 cm
63753 | 75 x 25 cm



light twine DR FL PZ
63651 | 150 x 20 cm
63751 | 75 x 25 cm



sand cement DR FL CL PZ
63634 | 50 x 50 cm | ↕
63734 | 50 x 50 cm | ↕ DR



light cement DR FL CL
63632 | 50 x 50 cm | ↕
63732 | 50 x 50 cm | ↕ DR



rock cement DR FL
63638 | 50 x 50 cm | ↕
63738 | 50 x 50 cm | ↕



canyon cement DR FL CL PZ
63636 | 50 x 50 cm | ↕
63736 | 50 x 50 cm | ↕ DR



60374 | natural collage oak, 60375 | grey collage oak 63675 | oxidized strata



natural collage oak DR FL
60374 | 120 x 20 cm | ↕



grey collage oak DR FL
60375 | 120 x 20 cm | ↕



corroded strata DR FL PZ
63673 | 100 x 100 cm



oxidized strata DR FL PZ
63675 | 100 x 100 cm

allura® dryback 0.70 | 0.55 | 0.40



pale speckled ceramic **63722** | 100 x 50 cm | DR FL



rust speckled ceramic **63724** | 100 x 50 cm | DR FL



iron speckled ceramic **63726** | 100 x 50 cm | DR FL



63722 | pale speckled ceramic, 60293 | steamed oak, 63724 | rust speckled ceramic



pure oak **60295** | 120 x 20 cm | DR FL



steamed oak **60293** | 120 x 20 cm | DR FL



63845 | magical sky, 63661 | natural ash



magical sky **63845** | 75 x 25 cm
63745 | 100 x 50 cm



dreamy sky **63843** | 75 x 25 cm
63743 | 100 x 50 cm



calming sky **63841** | 75 x 25 cm
63741 | 100 x 50 cm



bleached rustic pine **60084** | 120 x 20 cm | DR FL



white raw timber **60151** | 120 x 20 cm | DR FL



grigio concrete **62523** | 50 x 50 cm
62513 | 100 x 100 cm



natural concrete **62522** | 50 x 50 cm
62512 | 100 x 100 cm



charcoal concrete **62418** | 50 x 50 cm
62518 | 100 x 100 cm




ochre marble **63682** | 50 x 50 cm
63782 | 50 x 50 cm



terra marble **63686** | 50 x 50 cm
63786 | 50 x 50 cm



peach marble **63688** | 50 x 50 cm
63788 | 50 x 50 cm



forest marble **63684** | 50 x 50 cm
63784 | 50 x 50 cm



white autumn oak **60350** | 100 x 15 cm | DR FL CL



grey autumn oak **60356** | 100 x 15 cm | DR FL CL



60350 | white autumn oak



ochre ash **63662** | 75 x 15 cm



terra ash **63663** | 75 x 15 cm



63662 | ochre ash, 63663 | terra ash, 63666 | indigo ash

allura® dryback 0.70 | 0.55 | 0.40



grey clouds
63847 | 75 x 25 cm
63747 | 100 x 50 cm



blue clouds
63849 | 75 x 25 cm
63749 | 100 x 50 cm



natural ash
63661 | 75 x 15 cm



sage ash
63664 | 75 x 15 cm



forest ash
63665 | 75 x 15 cm



indigo ash
63666 | 75 x 15 cm



63665 | forest ash, 63664 | sage ash, 63684 | forest marble, 63661 | natural ash

allura® flex

FL | allura flex (1.00/0.55) FL1 | 1.0 FL5 | 0.55

FL* Only available in FL1 | 1.0



Life is a play with many acts. And while they are performed, creativity is key. Whatever life throws at your feet, the new Allura Flex collection is here to support you every step of the way. With its 50 true-to-life wood and material patterns, it's a flooring system that suits any scene imaginable. The non-adhesive application solution makes Allura Flex quick to install. What's more, it's easy to remove, re-use and recycle. Allura Flex has the flexibility and durability to give you the design freedom to bring any interior to life.



60280 | grey giant oak



light giant oak
60288 | 150 x 28 cm



natural giant oak
60284 | 150 x 28 cm



grey giant oak
60280 | 150 x 28 cm

		Flex " 1.00	Flex " 0.55
Total thickness	EN-ISO 24346	5 mm	4 mm
Wear layer thickness	EN-ISO 24340	1 mm	0.55 mm
Domestic use	EN-ISO 10874	Class 23	Class 23
Commercial use	EN-ISO 10874	Class 34	Class 33
Light industrial use	EN-ISO 10874	Class 42	Class 42
DoP		0200131-Dop_209	0200131-Dop_209
Reaction to fire	EN 13501-1	B _{fl} -s1,L,CS	B _{fl} -s1,L,CS
Thermal conductivity	EN 12524	0.25 W/mK	0.25 W/mK



light honey oak
60305 | 150 x 28 cm



central oak
60300 | 150 x 28 cm



deep country oak
60302 | 150 x 28 cm



rustic anthracite oak
60306 | 150 x 28 cm



63643 | natural serene oak



light serene oak
63641 | 150 x 20 cm



natural serene oak
63643 | 150 x 20 cm



dark serene oak
63645 | 150 x 20 cm



63712 | blond timber



bleached timber **FL**
63406 | 120 x 20 cm | ↕ ⊕
63706 | 75 x 15 cm | ↕ ⊕

blond timber **FL**
63412 | 120 x 20 cm | ↕ ⊕
63712 | 75 x 15 cm | ↕ ⊕

grey washed timber **FL***
63408 | 120 x 20 cm | ↕ ⊕



whitewash elegant oak **FL**
60064 | 120 x 20 cm

honey elegant oak **FL**
60065 | 120 x 20 cm
60165 | 75 x 15 cm

amber elegant oak **FL**
60068 | 120 x 20 cm
60168 | 75 x 15 cm



60168 | amber elegant oak




natural timber **FL**
63535 | 120 x 20 cm | ↕ ⊕

light timber **FL**
63533 | 120 x 20 cm | ↕ ⊕

light timber gradient **FL***
63534 | 120 x 20 cm | ↕ ⊕

Image shows multiple planks.
 Gradient is random and runs length of the plank.



63533 | light timber, 63534 | light timber gradient




60063 | waxed oak, 60061 | blackened oak



blackened oak **FL**
60061 | 100 x 15 cm | ↕ ⊕

waxed oak **FL**
60063 | 100 x 15 cm | ↕ ⊕



dark twine **FL**
63655 | 150 x 20 cm
63755 | 75 x 25 cm

natural twine **FL**
63653 | 150 x 20 cm
63753 | 75 x 25 cm


light twine **FL**
63651 | 150 x 20 cm
63751 | 75 x 25 cm



shell twine **63659** | 75 x 25 cm
grigio twine **63658** | 75 x 25 cm



63659 | shell twine



sand cement **63634** | 50 x 50 cm
light cement **63632** | 50 x 50 cm
rock cement **63638** | 50 x 50 cm
canyon cement **63636** | 50 x 50 cm



63675 | oxidized strata



natural collage oak **60374** | 120 x 20 cm
grey collage oak **60375** | 120 x 20 cm



corroded strata **63673** | 100 x 100 cm
oxidized strata **63675** | 100 x 100 cm



pale speckled ceramic **63722** | 100 x 50 cm
rust speckled ceramic **63724** | 100 x 50 cm
iron speckled ceramic **63726** | 100 x 50 cm



63722 | pale speckled ceramic



pure oak **60295** | 120 x 20 cm
steamed oak **60293** | 120 x 20 cm



bleached rustic pine **60084** | 120 x 20 cm
white raw timber **60151** | 120 x 20 cm



grigio concrete **62523** | 50 x 50 cm
natural concrete **62522** | 50 x 50 cm
charcoal concrete **62418** | 50 x 50 cm
62513 | 100 x 100 cm
62512 | 100 x 100 cm
62518 | 100 x 100 cm




white autumn oak **60350** | 100 x 15 cm
grey autumn oak **60356** | 100 x 15 cm



60350 | white autumn oak



63666 | indigo ash, 63749 | blue sky, 60084 | bleached rustic pine



grey clouds 63847 | 75 x 25 cm
63747 | 100 x 50 cm
blue sky 63849 | 75 x 25 cm
63749 | 100 x 50 cm
magical sky 63845 | 75 x 25 cm
63745 | 100 x 50 cm
dreamy sky 63843 | 75 x 25 cm
63743 | 100 x 50 cm
calming sky 63841 | 75 x 25 cm
63741 | 100 x 50 cm

allura® click pro



light giant oak 60288 | 150.5 x 23.7 cm
natural giant oak 60284 | 150.5 x 23.7 cm



60288 | light giant oak, 60284 | natural giant oak

Click pro		
Total thickness	EN-ISO 24346	5 mm
Wear layer thickness	EN-ISO 24340	0.55 mm
Domestic use	EN-ISO 10874	Class 23
Commercial use	EN-ISO 10874	Class 33
Light industrial use	EN-ISO 10874	Class 42
DoP	0200132-Dop_105	
Reaction to fire	EN 13501-1	B _s -s1,L,CS with and without Forbo underlay
Thermal conductivity	EN 12524	0.25 W/mK



light honey oak 60305 | 150.5 x 23.7 cm
central oak 60300 | 150.5 x 23.7 cm
white autumn oak 60350 | 121.2 x 18.7 cm
grey autumn oak 60356 | 121.2 x 18.7 cm



light serene oak 63641 | 150.5 x 23.7 cm
natural serene oak 63643 | 150.5 x 23.7 cm



whitewash elegant oak **60064** | 121.2 x 18.7 cm |
 bleached timber **63406** | 121.2 x 18.7 cm |
 blond timber **63412** | 121.2 x 18.7 cm |
 light timber **63533** | 121.2 x 18.7 cm |
 natural timber **63535** | 121.2 x 18.7 cm |
 dark twine **63655** | 150.5 x 23.7 cm |



63632 | light cement



sand cement **63634** | 60 x 31.7 cm |
 canyon cement **63636** | 60 x 31.7 cm |
 light cement **63632** | 60 x 31.7 cm |
 grigio concrete **62523** | 60 x 31.7 cm |
 natural concrete **62522** | 60 x 31.7 cm |
 charcoal concrete **62418** | 60 x 31.7 cm |

allura® puzzle



Life is a play with many acts. Whatever life throws at your feet, the new Allura Luxury Vinyl Tiles collection is here to support you every step of the way. Different solutions for different circumstances that will suit any scene imaginable. Even the most demanding ones where Allura Puzzle gives the perfect answer with a high aesthetic and reliable performance that is future proof.




honey elegant oak **60065** | 96 x 96 cm |
 natural giant oak **60284** | 96 x 96 cm |
 grey giant oak **60280** | 96 x 96 cm |
 grigio twine **63658** | 96 x 96 cm |
 light twine **63651** | 96 x 96 cm |
 dark twine **63655** | 96 x 96 cm |




63675 | oxidized strata

Puzzle		
Total thickness	EN-ISO 24346	5 mm
Wear layer thickness	EN-ISO 24340	0.70 mm
Domestic use	EN-ISO 10874	Class 23
Commercial use	EN-ISO 10874	Class 34
Light industrial use	EN-ISO 10874	Class 43
DoP	0200134-Dop_909	
Reaction to fire	EN 13501-1	B _s -s1,L,CS
Thermal conductivity	EN 12524	0.25 W/mK



corroded strata **63673** | 96 x 96 cm |
 oxidized strata **63675** | 96 x 96 cm |



sand cement **63634** | 96 x 96 cm |
 canyon cement **63636** | 96 x 96 cm |
 natural concrete **62522** | 96 x 96 cm |
 charcoal concrete **62418** | 96 x 96 cm |



ALLURA AT A GLANCE

DR7 Allura Dryback 0.70

Name	Article number	Size in cm	Bevel	IR emboss	Pcs in box DR7	m² in box DR7
whitewash elegant oak**	60064DR7	120x20			12	2.88
honey elegant oak	60065DR7	120x20			12	2.88
amber elegant oak	60068DR7	120x20			12	2.88
honey elegant oak	60165DR7	75x15			36	4.05
amber elegant oak	60168DR7	75x15			36	4.05
grey giant oak	60280DR7	180x32	2 sided		8	4.608
natural giant oak	60284DR7	180x32	2 sided		8	4.608
light giant oak	60288DR7	180x32	2 sided		8	4.608
central oak	60300DR7	150x28	4 sided	V	12	5.04
deep country oak	60302DR7	150x28	4 sided	V	12	5.04
light honey oak	60305DR7	150x28	4 sided	V	12	5.04
rustic anthracite oak	60306DR7	150x28	4 sided	V	12	5.04
bleached timber	63406DR7	120x20	4 sided	V	12	2.88
grey washed timber	63408DR7	120x20	4 sided	V	12	2.88
blond timber	63412DR7	120x20	4 sided	V	12	2.88
light timber	63533DR7	120x20	4 sided	V	12	2.88
light timber gradient	63534DR7	120x20	4 sided	V	12	2.88
natural timber	63535DR7	120x20	4 sided	V	12	2.88
light cement	63632DR7	50x50	4 sided		12	3
sand cement	63634DR7	50x50	4 sided		12	3
canyon cement	63636DR7	50x50	4 sided		12	3
rock cement	63638DR7	50x50	4 sided		12	3
light serene oak	63641DR7	150x20			16	4.8
natural serene oak	63643DR7	150x20			16	4.8
dark serene oak	63645DR7	150x20			16	4.8
light twine	63651DR7	150x20			16	4.8
natural twine	63653DR7	150x20			16	4.8
dark twine	63655DR7	150x20			16	4.8
grigio twine	63658DR7	75x25			22	4.125
shell twine	63659DR7	75x25			22	4.125
warm natural stone	63695DR7	100x50			12	6
bleached timber	63706DR7	75x15	4 sided	V	36	4.05
blond timber	63712DR7	75x15	4 sided	V	36	4.05
light cement (trapezoid)	63732DR7	50x50 (35/15)	4 sided		12	3
sand cement (trapezoid)	63734DR7	50x50 (35/15)	4 sided		12	3
canyon cement (trapezoid)	63736DR7	50x50 (35/15)	4 sided		12	3
rock cement (trapezoid)	63738DR7	50x50 (35/15)	4 sided		12	3
light twine	63751DR7	75x25			22	4.125
natural twine	63753DR7	75x25			22	4.125
dark twine	63755DR7	75x25			22	4.125
blackened oak**	60061DR7	100x15	4 sided		20	3
waxed oak	60063DR7	100x15	4 sided		20	3
bleached rustic pine	60084DR7	120x20	4 sided	V	12	2.88
white raw timber	60151DR7	120x20	4 sided	V	12	2.88
steamed oak	60293DR7	120x20	4 sided		12	2.88
pure oak	60295DR7	120x20	4 sided		12	2.88
white autumn oak*	60350DR7	100x15	4 sided		20	3

** Also available in strip (60061DR7ST)

DR5 Allura Dryback 0.55

Name	Article number	Size in cm	Bevel	IR emboss	Pcs in box DR5	m² in box DR5
whitewash elegant oak**	60064DR5	120x20			14	3.36
honey elegant oak	60065DR5	120x20			14	3.36
amber elegant oak	60068DR5	120x20			14	3.36
honey elegant oak	60165DR5	75x15			41	4.613
amber elegant oak	60168DR5	75x15			41	4.613
grey giant oak	60280DR5	180x32	2 sided		9	5.184
natural giant oak	60284DR5	180x32	2 sided		9	5.184
light giant oak	60288DR5	180x32	2 sided		9	5.184
central oak	60300DR5	150x28	4 sided	V	14	5.88
deep country oak	60302DR5	150x28	4 sided	V	14	5.88
light honey oak	60305DR5	150x28	4 sided	V	14	5.88
rustic anthracite oak	60306DR5	150x28	4 sided	V	14	5.88
bleached timber	63406DR5	120x20	4 sided	V	14	3.36
grey washed timber	63408DR5	120x20	4 sided	V	14	3.36
blond timber	63412DR5	120x20	4 sided	V	14	3.36
light timber	63533DR5	120x20	4 sided	V	14	3.36
light timber gradient	63534DR5	120x20	4 sided	V	14	3.36
natural timber	63535DR5	120x20	4 sided	V	14	3.36
light cement	63632DR5	50x50	4 sided		14	3.5
sand cement	63634DR5	50x50	4 sided		14	3.5
canyon cement	63636DR5	50x50	4 sided		14	3.5
rock cement	63638DR5	50x50	4 sided		14	3.5
light serene oak	63641DR5	150x20			18	5.4
natural serene oak	63643DR5	150x20			18	5.4
dark serene oak	63645DR5	150x20			18	5.4
light twine	63651DR5	150x20			18	5.4
natural twine	63653DR5	150x20			18	5.4
dark twine	63655DR5	150x20			18	5.4
grigio twine	63658DR5	75x25			25	4.688
shell twine	63659DR5	75x25			25	4.688
warm natural stone	63695DR5	100x50			13	6.5
bleached timber	63706DR5	75x15	4 sided	V	41	4.613
blond timber	63712DR5	75x15	4 sided	V	41	4.613
light cement (trapezoid)	63732DR5	50x50 (35/15)	4 sided		14	3.5
sand cement (trapezoid)	63734DR5	50x50 (35/15)	4 sided		14	3.5
canyon cement (trapezoid)	63736DR5	50x50 (35/15)	4 sided		14	3.5
rock cement (trapezoid)	63738DR5	50x50 (35/15)	4 sided		14	3.5
light twine	63751DR5	75x25			25	4.688
natural twine	63753DR5	75x25			25	4.688
dark twine	63755DR5	75x25			25	4.688
blackened oak**	60061DR5	100x15	4 sided		23	3.45
waxed oak	60063DR5	100x15	4 sided		23	3.45
bleached rustic pine	60084DR5	120x20	4 sided	V	14	3.36
white raw timber	60151DR5	120x20	4 sided	V	14	3.36
steamed oak	60293DR5	120x20	4 sided		14	3.36
pure oak	60295DR5	120x20	4 sided		14	3.36
white autumn oak*	60350DR5	100x15	4 sided		23	3.45

** Also available in strip (60061DR5ST)

DR4 Allura Dryback 0.40

Name	Article number	Size in cm	Bevel	IR emboss	Pcs in box DR4	m² in box DR4
whitewash elegant oak	60064DR4	120x20			15	3.6
honey elegant oak	60065DR4	120x20			15	3.6
amber elegant oak	60068DR4	120x20			15	3.6
honey elegant oak	60165DR4	75x15			46	5.175
amber elegant oak	60168DR4	75x15			46	5.175
grey giant oak	60280DR4	180x32	2 sided		10	5.76
natural giant oak	60284DR4	180x32	2 sided		10	5.76
light giant oak	60288DR4	180x32	2 sided		10	5.76
central oak	60300DR4	150x28	4 sided	V	15	6.3
deep country oak	60302DR4	150x28	4 sided	V	15	6.3
light honey oak	60305DR4	150x28	4 sided	V	15	6.3
rustic anthracite oak	60306DR4	150x28	4 sided	V	15	6.3
bleached timber	63406DR4	120x20	4 sided	V	15	3.6
grey washed timber						
blond timber	63412DR4	120x20	4 sided	V	15	3.6
light timber	63533DR4	120x20	4 sided	V	15	3.6
light timber gradient						
natural timber	63535DR4	120x20	4 sided	V	15	3.6
light cement	63632DR4	50x50	4 sided		15	3.75
sand cement	63634DR4	50x50	4 sided		15	3.75
canyon cement	63636DR4	50x50	4 sided		15	3.75
rock cement						
light serene oak	63641DR4	150x20			20	6
natural serene oak	63643DR4	150x20			20	6
dark serene oak	63645DR4	150x20			20	6
light twine	63651DR4	150x20			20	6
natural twine	63653DR4	150x20			20	6
dark twine	63655DR4	150x20			20	6
grigio twine	63658DR4	75x25			28	5.25
shell twine	63659DR4	75x25			28	5.25
warm natural stone						
bleached timber	63706DR4	75x15	4 sided	V	46	5.175
blond timber	63712DR4	75x15	4 sided	V	46	5.175
light cement (trapezoid)	63788DR5	50x50 (35/15)	4 sided		14	3.5
peach marble (trapezoid)						
sand cement (trapezoid)						
canyon cement (trapezoid)						
rock cement (trapezoid)						
light twine	63751DR4	75x25			28	5.25
natural twine	63753DR4	75x25			28	5.25
dark twine	63755DR4	75x25			28	5.25
blackened oak	60061DR4	100x15	4 sided		25	3.75
waxed oak	60063DR4	100x15	4 sided		25	3.75
bleached rustic pine	60084DR4	120x20	4 sided	V	15	3.6
white raw timber	60151DR4	120x20	4 sided	V	15	3.6
steamed oak	60293DR4	120x20	4 sided		15	3.6
pure oak	60295DR4	120x20	4 sided		15	3.6
white autumn oak*	60350DR4	100x15	4 sided		25	3.75

Name	Article number	Size in cm	Bevel	IR emboss	Pcs in box DR4	m² in box DR4
grey autumn oak*	60356DR4	100x15	4 sided		25	3.75
natural collage oak	60374DR4	120x20	4 sided		15	3.6
grey collage oak	60375DR4	120x20	4 sided		15	3.6
charcoal concrete	62418DR4	50x50			15	3.75
natural concrete	62512DR4	100x100			1	1
grigio concrete	62513DR4	100x100			1	1
charcoal concrete	62518DR4	100x100			1	1
natural concrete	62522DR4	50x50			15	3.75
grigio concrete	62523DR4	50x50			15	3.75
natural ash						
ochre ash						
terra ash						
sage ash						
forest ash						
indigo ash						
corroded strata						
oxidized strata	63675DR4	100x100			1	1
ochre marble						
forest marble						
terra marble						
peach marble						
pink natural stone						
cool natural stone						
pale speckled ceramic	63722DR4	100x50	4 sided		15	7.5
rust speckled ceramic	63724DR4	100x50	4 sided		15	7.5
iron speckled ceramic	63726DR4	100x50	4 sided		15	7.5
calming sky						
dreamy sky						
magical sky						
grey clouds						
blue clouds						
ochre marble (trapezoid)						
forest marble (trapezoid)						
peach marble (trapezoid)						
terra marble (trapezoid)						
calming sky						
dreamy sky						
magical sky						
grey clouds						
blue clouds						

ALLURA AT A GLANCE

FL5 Allura Flex 0.55

Name	Article number	Size in cm	Bevel	IR emboss	Pcs in box FL5	m² in box FL5
whitewash elegant oak	60064FL5	120x20			13	3.12
honey elegant oak	60065FL5	120x20			13	3.12
amber elegant oak	60068FL5	120x20			13	3.12
honey elegant oak	60165FL5	75x15			23	2.588
amber elegant oak	60168FL5	75x15			23	2.588
grey giant oak	60280FL5	150x28	4 sided		9	3.78
natural giant oak	60284FL5	150x28	4 sided		9	3.78
light giant oak	60288FL5	150x28	4 sided		9	3.78
central oak	60300FL5	150x28	4 sided	V	9	3.78
deep country oak	60302FL5	150x28	4 sided	V	9	3.78
light honey oak	60305FL5	150x28	4 sided	V	9	3.78
rustic anthracite oak	60306FL5	150x28	4 sided	V	9	3.78
bleached timber	63406FL5	120x20	4 sided	V	13	3.12
grey washed timber						
blond timber	63412FL5	120x20	4 sided	V	13	3.12
light timber	63533FL5	120x20	4 sided	V	13	3.12
light timber gradient						
natural timber	63535FL5	120x20	4 sided	V	13	3.12
light cement	63632FL5	50x50	4 sided		13	3.25
sand cement	63634FL5	50x50	4 sided		13	3.25
canyon cement	63636FL5	50x50	4 sided		13	3.25
rock cement	63638FL5	50x50	4 sided		13	3.25
light serene oak	63641FL5	150x20			10	3
natural serene oak	63643FL5	150x20			10	3
dark serene oak	63645FL5	150x20			10	3
light twine	63651FL5	150x20			10	3
natural twine	63653FL5	150x20			10	3
dark twine	63655FL5	150x20			10	3
grigio twine	63658FL5	75x25			14	2.625
shell twine	63659FL5	75x25			14	2.625
warm natural stone						
bleached timber	63706FL5	75x15	4 sided	V	23	2.588
blond timber	63712FL5	75x15	4 sided	V	23	2.588
light cement (trapezoid)						
sand cement (trapezoid)						
canyon cement (trapezoid)						
rock cement (trapezoid)						
light twine	63751FL5	75x25			14	2.625
natural twine	63753FL5	75x25			14	2.625
dark twine	63755FL5	75x25			14	2.625
blackened oak	60061FL5	100x15	4 sided		15	2.25
waxed oak	60063FL5	100x15	4 sided		15	2.25
bleached rustic pine	60084FL5	120x20	4 sided	V	13	3.12
white raw timber	60151FL5	120x20	4 sided	V	13	3.12
steamed oak	60293FL5	120x20	4 sided		13	3.12
pure oak	60295FL5	120x20	4 sided		13	3.12
white autumn oak*	60350FL5	100x15	4 sided		15	2.25

FL1 Allura Flex 1.00

Name	Article number	Size in cm	Bevel	IR emboss	Pcs in box FL1	m² in box FL1
whitewash elegant oak	60064FL1	120x20			10	2.4
honey elegant oak	60065FL1	120x20			10	2.4
amber elegant oak	60068FL1	120x20			10	2.4
honey elegant oak	60165FL1	75x15			18	2.025
amber elegant oak	60168FL1	75x15			18	2.025
grey giant oak	60280FL1	150x28	4 sided		7	2.94
natural giant oak	60284FL1	150x28	4 sided		7	2.94
light giant oak	60288FL1	150x28	4 sided		7	2.94
central oak	60300FL1	150x28	4 sided	V	7	2.94
deep country oak	60302FL1	150x28	4 sided	V	7	2.94
light honey oak	60305FL1	150x28	4 sided	V	7	2.94
rustic anthracite oak	60306FL1	150x28	4 sided	V	7	2.94
bleached timber	63406FL1	120x20	4 sided	V	10	2.4
grey washed timber	63408FL1	120x20	4 sided	V	10	2.4
blond timber	63412FL1	120x20	4 sided	V	10	2.4
light timber	63533FL1	120x20	4 sided	V	10	2.4
light timber gradient	63534FL1	120x20	4 sided	V	10	2.4
natural timber	63535FL1	120x20	4 sided	V	10	2.4
light cement	63632FL1	50x50	4 sided		10	2.5
sand cement	63634FL1	50x50	4 sided		10	2.5
canyon cement	63636FL1	50x50	4 sided		10	2.5
rock cement	63638FL1	50x50	4 sided		10	2.5
light serene oak	63641FL1	150x20			8	2.4
natural serene oak	63643FL1	150x20			8	2.4
dark serene oak	63645FL1	150x20			8	2.4
light twine	63651FL1	150x20			8	2.4
natural twine	63653FL1	150x20			8	2.4
dark twine	63655FL1	150x20			8	2.4
grigio twine	63658FL1	75x25			11	2.063
shell twine	63659FL1	75x25			11	2.063
warm natural stone	63695FL1	100x50			6	3
bleached timber	63706FL1	75x15	4 sided	V	18	2.025
blond timber	63712FL1	75x15	4 sided	V	18	2.025
light cement (trapezoid)						
sand cement (trapezoid)						
canyon cement (trapezoid)						
rock cement (trapezoid)						
light twine	63751FL1	75x25			11	2.063
natural twine	63753FL1	75x25			11	2.063
dark twine	63755FL1	75x25			11	2.063
blackened oak	60061FL1	100x15	4 sided		12	1.80
waxed oak	60063FL1	100x15	4 sided		12	1.80
bleached rustic pine	60084FL1	120x20	4 sided	V	10	2.4
white raw timber	60151FL1	120x20	4 sided	V	10	2.4
steamed oak	60293FL1	120x20	4 sided		10	2.4
pure oak	60295FL1	120x20	4 sided		10	2.4
white autumn oak*	60350FL1	100x15	4 sided		12	1.80

CL5 Allura Click Pro 0.55

Name	Article number	Size in cm	Bevel	IR emboss	Pcs in box CL5	m² in box CL5
whitewash elegant oak	60064CL5	121.2x18.7	4 sided		8	1.81
honey elegant oak						
amber elegant oak						
honey elegant oak						
amber elegant oak						
grey giant oak						
natural giant oak	60284CL5	150.5x23.7	4 sided		6	2.14
light giant oak	60288CL5	150.5x23.7	4 sided		6	2.14
central oak	60300CL5	150.5x23.7	4 sided	V	6	2.14
deep country oak						
light honey oak	60305CL5	150.5x23.7	4 sided	V	6	2.14
rustic anthracite oak						
bleached timber	63406CL5	121.2x18.7	4 sided	V	8	1.81
grey washed timber						
blond timber	63412CL5	121.2x18.7	4 sided	V	8	1.81
light timber	63533CL5	121.2x18.7	4 sided	V	8	1.81
light timber gradient						
natural timber	63535CL5	121.2x18.7	4 sided	V	8	1.81
light cement	63632CL5	60x31.7	4 sided		10	1.9
sand cement	63634CL5	60x31.7	4 sided		10	1.9
canyon cement	63636CL5	60x31.7	4 sided		10	1.9
rock cement						
light serene oak	63641CL5	150.5x23.7	4 sided		6	2.14
natural serene oak	63643CL5	150.5x23.7	4 sided		6	2.14
dark serene oak						
light twine						
natural twine						
dark twine	63655CL5	150.5x23.7	4 sided		6	2.14
grigio twine						
shell twine						
warm natural stone						
bleached timber						
blond timber						
light cement (trapezoid)						
sand cement (trapezoid)						
canyon cement (trapezoid)						
rock cement (trapezoid)						
light twine						
natural twine						
dark twine						
blackened oak						
waxed oak						
bleached rustic pine						
white raw timber						
steamed oak						
pure oak						
white autumn oak*	60350CL5	121.2x18.7	4 sided		8	1.81

Name	Article number	Size in cm	Bevel	IR emboss	Pcs in box CL5	m² in box CL5
grey autumn oak*	60356CL5	121.2x18.7	4 sided		8	1.81
natural collage oak						
grey collage oak						
charcoal concrete	62418CL5	60x31.7			10	1.9
natural concrete						
grigio concrete						
charcoal concrete						
natural concrete	62522CL5	60x31.7			10	1.9
grigio concrete	62523CL5	60x31.7			10	1.9
natural ash						
ochre ash						
terra ash						
sage ash						
forest ash						
indigo ash						
corroded strata						
oxidized strata						
ochre marble						
forest marble						
terra marble						
peach marble						
pink natural stone						
cool natural stone						
pale speckled ceramic						
rust speckled ceramic						
iron speckled ceramic						
calming sky						
dreamy sky						
magical sky						
grey clouds						
blue clouds						
ochre marble (trapezoid)						
forest marble (trapezoid)						
peach marble (trapezoid)						
terra marble (trapezoid)						
calming sky						
dreamy sky						
magical sky						
grey clouds						
blue clouds						

ALLURA AT A GLANCE

PZ7 Allura Puzzle 0.70

Name	Article number	Size in cm	Pcs PZ7	m² PZ7
whitewash elegant oak				
honey elegant oak	60065PZ7	96x96	1	0.92
amber elegant oak				
honey elegant oak				
amber elegant oak				
grey giant oak	60280PZ7	96x96	1	0.92
natural giant oak	60284PZ7	96x96	1	0.92
light giant oak				
central oak				
deep country oak				
light honey oak				
rustic anthracite oak				
bleached timber				
grey washed timber				
blond timber				
light timber				
light timber gradient				
natural timber				
light cement				
sand cement	63634PZ7	96x96	1	0.92
canyon cement	63636PZ7	96x96	1	0.92
rock cement				
light serene oak				
natural serene oak				
dark serene oak				
light twine	63651PZ7	96x96	1	0.92
natural twine				
dark twine	63655PZ7	96x96	1	0.92
grigio twine	63658PZ7	96x96	1	0.92
shell twine				
warm natural stone				
bleached timber				
blond timber				
light cement (trapezoid)				
sand cement (trapezoid)				
canyon cement (trapezoid)				
rock cement (trapezoid)				
light twine				
natural twine				
dark twine				
blackened oak				
waxed oak				
bleached rustic pine				
white raw timber				
steamed oak				
pure oak				
white autumn oak*				
grey autumn oak*				

* natural colour variation

Name	Article number	Size in cm	Pcs PZ7	m² PZ7
natural collage oak				
grey collage oak				
charcoal concrete	62418PZ7	96x96	1	0.92
natural concrete				
grigio concrete				
charcoal concrete				
natural concrete	62522PZ7	96x96	1	0.92
grigio concrete				
natural ash				
ochre ash				
terra ash				
sage ash				
forest ash				
indigo ash				
corroded strata	63673PZ7	96x96	1	0.92
oxidized strata	63675PZ7	96x96	1	0.92
ochre marble				
forest marble				
terra marble				
peach marble				
pink natural stone				
cool natural stone				
pale speckled ceramic				
rust speckled ceramic				
iron speckled ceramic				
calming sky				
dreamy sky				
magical sky				
grey clouds				
blue clouds				
ochre marble (trapezoid)				
forest marble (trapezoid)				
peach marble (trapezoid)				
terra marble (trapezoid)				
calming sky				
dreamy sky				
magical sky				
grey clouds				
blue clouds				

allura® decibel



6714 | honey twine

THE SYMBOLS AND ABBREVIATIONS UNDER THE SAMPLES EXPLAINED:



4 sides bevelled

All items in this book have 4 bevelled edges.

The coloured codes alongside each colourway number in this book show the availability per construction.




AD | allura decibel (0.35/0.8)
AD3 | 0.35 **AD8** | 0.8

AD* Only available in **AD8** | 0.8

Example:

When you want the weathered serene oak in Allura decibel with wear layer thickness 0.8 mm. Take the colourway number of weathered serene oak which is 5513 and add AD8 to the number.


This is how you would specify this example order:



Large size:

When you want the large size of the weathered serene oak in Allura decibel with wear layer thickness 0.8 mm. Take the colourway number of the large size which is 5513L and add AD8 to the number.

This is how you would specify this example order:





smoke smooth oak **AD** 5301 | 120 x 20 cm
 dune smooth oak **AD** 5303 | 120 x 20 cm
 golden smooth oak **AD** 5313 | 120 x 20 cm



sun-bleached serene oak **AD** 5503 | 100 x 20 cm
 5503L | 150 x 20 cm
 weathered serene oak **AD** 5513 | 100 x 20 cm
 5513L | 150 x 20 cm
 espresso serene oak **AD** 5524 | 100 x 20 cm
 5524L | 150 x 20 cm



5513 | weathered serene oak



5404 | natural antique oak



light honey antique oak **AD** 5403 | 100 x 16.6 cm
 natural antique oak **AD** 5404 | 100 x 16.6 cm
 taupe antique oak **AD** 5424 | 100 x 16.6 cm



5203 | honey authentic oak



pale authentic oak **AD** 5201 | 100 x 20 cm
 honey authentic oak **AD** 5203 | 100 x 20 cm
 classic authentic oak **AD** 5204 | 100 x 20 cm



deep authentic oak **AD** 5224 | 100 x 20 cm
 smoked authentic oak **AD** 5202 | 100 x 20 cm

		Decibel 0.35	Decibel 0.80
Total thickness	EN-ISO 24346	3.15 mm	4.00 mm
Wear layer thickness	EN-ISO 24340	0.35 mm	0.80 mm
Domestic use	EN-ISO 10874	Class 23	Class 23
Commercial use	EN-ISO 10874	Class 32	Class 34
Light industrial use	EN-ISO 10874	Class 42	Class 42
DoP		0200861-Dop_010	0200861-Dop_010
Reaction to fire	EN 13501-1	CS ₂ -s1	CS ₂ -s1
Thermal conductivity	EN 12524	0.25 W/mK	0.25 W/mK



Summer harvest oak **AD** 5113 | 100 x 16.6 cm
 golden harvest oak **AD** 5103 | 100 x 16.6 cm
 rustic harvest oak **AD** 5104 | 100 x 16.6 cm
 Winter harvest oak **AD** 5101 | 100 x 16.6 cm



5113 | Summer harvest oak



honey twine
6714 | 100 x 20 cm



taupe twine
6724 | 100 x 20 cm



smoke twine
6712 | 100 x 20 cm



fossil twine
6709 | 100 x 20 cm




lively beige emperador
9024 | 75 x 50 cm



light grey emperador
9011 | 75 x 50 cm



dark grey emperador
9019 | 75 x 50 cm



jade emperador
9008 | 75 x 50 cm



limestone stromboli
6903 | 75 x 50 cm



Burgundy stromboli
6913 | 75 x 50 cm



quartz stromboli
6901 | 75 x 50 cm



basalt stromboli
6902 | 75 x 50 cm



silt slabstone
6604 | 50 x 50 cm



fog slabstone
6601 | 50 x 50 cm
6601L | 100 x 100 cm



smoke slabstone
6602 | 50 x 50 cm



charcoal slabstone
6609 | 50 x 50 cm
6609L | 100 x 100 cm



6913 | burgundy stromboli



natural scott
9558 | 50 x 50 cm




traditional scott
9557 | 50 x 50 cm



saffron ash
9715 | 100 x 20 cm



ruby ash
9716 | 100 x 20 cm



9557 | traditional scott, 9715 | saffron ash, 9716 | burgundy ash



9668 | stormy sky, 9717 | deep blue ash, 9718 | sage green ash, 5513 | weathered serene oak



deep blue ash
9717 | 100 x 20 cm



sage green ash
9718 | 100 x 20 cm



stormy sky
9668 | 100 x 20 cm



evening sky
9666 | 100 x 20 cm

allura®




colour | colour plus

Allura Colour Plus, a high quality and rapid flooring solution for demanding environments, ready to use after overnight installation. The invisible dovetail construction of Allura Colour Plus ensures a strong and stable connection which smoothly seals the floor surface.

The honeycomb system on the reverse of the tile provides effective moisture control. This prevents build-up of mould and bacteria keeping the sub-floor dry and overcomes the need for a mould barrier.

Description	Interlocking vinyl tiles
Dimensions	607 x 607mm
Impact sound reduction	EN-ISO 717-2 ≥ 12 dB
Total thickness	ISO 24346 10.3mm
Slip resistance	DIN 51130 R9
Collection size	14
Application	EN-ISO 10874 Class 34/43
CE	EN 14041
Reaction to fire	EN 13501-1 B _{fl} -s1
Slip resistance	EN 13893 DS: ≥0.30

Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect. Contact 0800 731 2369.



Allura Colour Plus c68014 | cafe au lait

HOMOGENEOUS PROJECT VINYL

Sphera is Forbo's premium, homogeneous vinyl collection, styled by our European design team and produced in an advanced purpose-built plant using the latest manufacturing technology.

Versatile and colourful

Sphera homogeneous vinyl floor coverings add character and style to floors across numerous applications. Whether in demanding, hygienic healthcare environments, in flexible, multi-purpose modern public buildings or in education facilities and offices where durability and colour are key, Sphera will never disappoint.



Sphera Element 50004 | contrast mid grey, 50074 | dark peach, 50068 | hay

Forbo Sphera has very low emissions of <math><10\mu\text{g}/\text{m}^2</math> after 28 days, is phthalate free and also offers colourways with high light reflectance values ensuring that it can contribute to a healthy indoor environment. Its SMART-top PUR surface treatment resists stains and is easy to clean ensuring safe and hygienic floors.

SPHERA COLLECTION AT A GLANCE

sphera® element

Sphera Element offers a fresh, light and contemporary colour palette which adds a sophistication to floor design. The collection includes warm and cool neutrals which complement interior finishes such as wood and stone along with pastels and bright accent colours for areas requiring way-finding or zoning.




sphera® energetic

Sphera Energetic offers a bold and contemporary colour palette which is both fresh and playful. The design reflects the aesthetics of rubber, concrete and resin flooring with 11 highlight visuals featuring vivid accent chips. These highlight colours are complemented by a range of 41 flecked colours to inspire creative floor designs.



sphera® elite

For the Elite collection, we created a completely new visual which has a more natural, terrazzo-like look with lots of depth and colour tones within. The lightweight and durable Sphera Elite has an intriguing, sophisticated appearance and will transform your area into an appealing place.



sphera® SD | EC

Sphera SD | EC is Forbo's homogeneous vinyl collection with conductive properties in sheet format. The collection is specifically designed to control static discharges and particles in the most sensitive environments, such as pharmaceutical, life sciences and healthcare facilities.





Sphera Elite 50493 | iris agate

The Forbo Sphera collection is setting new standards in homogeneous vinyl due to its design, technology and performance. Forbo's brand new purpose built manufacturing plant means that all the latest insights and technology have been used to create 'smart' and innovative solutions resulting in a premium collection.

We've made a massive investment in a brand new, state-of-the-art production facility in Coevorden, Holland, our European centre of expertise for vinyl flooring production.

This has enabled us to manufacture a premium homogeneous vinyl sheet that offers not only the freshest, cleanest palette ever seen in this product category but one that also benefits from SMART technology which delivers best in class performance.



- Sustainable*
- Modern*
- Advanced*
- Robust*
- Technology*

DESIGN COLOUR

- In-house design and colour development ensures the palette complements a broad range of commercial spaces
- New technology delivers bright and saturated hues, resulting in striking colours and tones, many with high light reflection values

TECHNOLOGY SUSTAINABILITY

- State of the art steel-belt press and thermofix technology ensure consistent quality
- Green energy and zero waste technology ensure efficient and sustainable manufacturing
- Low emissions and phthalate free manufacturing ensure Sphera can contribute to a healthy indoor environment

PERFORMANCE DURABILITY

- Unique embossing process following lacquer application delivers durable performance
- In-line coating and subsequent embossing process for superior appearance
- Evenly distributed top-layer provides superior all over protection
- SMART-top surface finish ensures Sphera has a high resistance to chemicals, scratches and stains
- Achieves highest abrasion wear rating group T tested to EN660-2




Sphera Element 51037 | contrast China blue, 50070 | soft violet, 50071 | violet

FORBO'S HOMOGENEOUS FLOORING TECHNOLOGY



Forbo's Sphera homogeneous vinyl is leading the product category by design, technology and performance.











Sphera Element offers a fresh, light and contemporary colour palette which adds a sophistication to floor design. The collection includes warm and cool neutrals which complement interior finishes such as wood and stone along with pastels and bright accent colours for areas requiring way-finding or zoning.



Description	Homogeneous sheet vinyl	
Dimensions	ISO 24341/ EN 426	Roll width 2.0m Roll length ≤ 27m
Total thickness	ISO 24340/ EN 428	2.0mm
Binder content	ISO 24340/ EN 429	Type 1
Surface finish	SMART top	
Collection size	52	
Application	EN 10874	Class 23/34/43
Dimension stability	ISO 23999	≤0.4%
CE	EN 14041	0200301-DoP-605
Reaction to fire	EN 13501-1	B _{fl} -s1
Slip resistance	EN 13893	DS - μ ≥ 0.30

Sphera Energetic offers a bold and contemporary colour palette which is both fresh and playful. The design reflects the aesthetics of rubber, concrete and resin flooring with 11 highlight visuals featuring vivid accent chips. These highlight colours are complemented by a range of 41 flecked colours to inspire creative floor designs. Transparent granules provide depth and dirt hiding properties ensuring that Sphera can be used in all contemporary spaces.



Description	Homogeneous sheet vinyl	
Dimensions	ISO 24341/ EN 426	Roll width 2.0m Roll length ≤ 25m
Total thickness	ISO 24340/ EN 428	2.0mm
Binder content	ISO 24340/ EN 429	Type 1: binder
Surface finish	SMART top	
Collection size	52	
Application	EN 10874	Class 34/43
Dimension stability	ISO 23999	≤0.2%
Abrasion resistance	EN 660-2	Group T
CE	EN 14041	0200301-DoP-605
Reaction to fire	EN 13501-1	B _s -s1
Slip resistance	EN 13893	DS - μ ≥ 0.30




sphera® elite



For the Elite collection, we created a completely new visual which has a more natural, terrazzo-like look with lots of depth and colour tones within. The lightweight and durable Sphera Elite has an intriguing, sophisticated appearance and will transform your area into an appealing place. For an even more luxurious appearance, 4 items with metallics can be used.



Description	Homogeneous sheet vinyl	
Dimensions	EN ISO 24341	Roll width 2.0m Roll length ≤ 27m
Total thickness	EN ISO 24346	2.0mm
Binder content	EN ISO 10581	Type 1: binder
Surface finish	SMART top	
Collection size	18	
Application	EN ISO 10874	Class 23/34/43
Dimension stability	EN ISO 23999	≤0.4%
CE	EN 14041	0200301-DoP-605
Reaction to fire	EN 13501-1	B ₂ -s1, L, CS
Slip resistance	EN 13893	D5 - μ ≥ 0.30



The Forbo Sphera SD | EC sheet collection offers a trustworthy solution delivering consistently high quality for the most demanding of controlled environments. Our technical flooring system will perform regardless of the conditions of the area.

Forbo's new purpose-built European manufacturing plant means that all the latest insights and technology have been used to create 'smart' and innovative solutions resulting in a premium collection.



The benefits of Sphera SD | EC

- Innovative product development and carefully controlled production processes ensure a solution with permanent conductive properties, which comply with all ESD standards.
- Sphera SD | EC will retain its optimal performance throughout the product's lifetime, regardless of the conditions of the environment, such as humidity levels.
- Low emissions and phthalate free manufacturing ensures Sphera SD | EC can contribute to a healthy indoor environment
- The unique SMART control top makes Sphera SD | EC resistant to stains and scratches, for a durable and hygienic solution.
- Thanks to the conductive backing, there is no need for conductive adhesive underneath the full sheet, only to affix the copper strip. This reduces installation costs and risks of installation errors.
- Sphera SD | EC is produced in a zero waste environment, ensuring efficient and sustainable manufacturing.

Forbo's homogeneous conductive sheet vinyl

SMART control top resists stains and scratches

Permanent dissipative properties which comply with all ESD standards


Extremely low emissions and outgassing


Performs regardless of the humidity level of the area

Produced in a zero waste environment

No need for conductive adhesive underneath the full sheet, only to affix the copper strip

Sheet format requires less welding, ensuring the highest hygienic properties





	Sphera SD	Sphera EC
Description	Homogeneous sheet vinyl	Homogeneous sheet vinyl
Dimensions	ISO 24341/ EN 426 Roll width 2.0m Roll length 27m	Roll width 2.0m Roll length 27m
Total thickness	ISO 24340/ EN 428 2.0mm	2.0mm
Binder content	ISO 24340/ EN 429 Type 1: binder	Type 1: binder
Surface finish	SMART control top	SMART control top
Collection size	14	13
Application	EN 10874 Class 34/43	Class 34/43
Dimension stability	ISO 23999 ≤0.4%	≤0.4%
CE	EN 14041 0200304-DoP-003	0200305-DoP-003
Reaction to fire	EN 13501-1 B _s -s1, G, NCS	B _s -s1, G, NCS
Slip resistance	EN 13893 DS - μ ≥ 0.30	DS - μ ≥ 0.30

Our recommended adhesive is 540 Eurosafe Special or 640 Eurostar Special. Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.



GENERAL PURPOSE PROJECT VINYL

Forbo's Eternal collection offers designers an extensive range of designs, all with the same performance specification, including realistic wood effects, stone and abstract designs, a broad palette of colours and some imaginative digitally printed visuals which are designed to inspire.

Eternal design vinyl sheet meets all the functional and practical requirements demanded in such segments as Health and Aged Care, Education, Office, Retail and Leisure & Hospitality.

PUR Pearl & PUR wood Pearl

The majority of our Eternal designs feature Forbo's proven PUR Pearl lacquering protection technique. The technique for applying the lacquering layer ensures an even distribution of PUR Pearl on both the surface and in the deeper areas of the embossing. This helps to prevent the surface of Eternal becoming soiled and reduces maintenance costs.



Eight items in the Eternal Wood range are finished with a specific PUR Wood embossing, offering the best possible performance on an all over wood grain design with integrated Pearl effect. The matt embossed lacquer layer ensures the highest level of both chemical and scuff resistance.

New for 2018, our Eternal de Luxe range delivers high design and exceptional embossing with the convenience of a sheet vinyl product.

Creating better environments

- Our general purpose vinyl ranges contain approximately 50% recycled content in their backing.
- We produce all our vinyl in Europe where it meets the highest possible current and future REACH compliance standards for chemical content.
- 100% of electricity comes from renewable sources and our vinyl production sites are part of an effective environmental management system, achieving ISO 14001 certification.
- We use smart material constructions and durable finishes on our vinyl. A micro-embossing technology reduces the need for chemical cleaning and increases the floor's lifespan.
- Through our Back to the Floor scheme, we can collect installation off-cuts from our smooth vinyl floor coverings.

Buildings such as care centres, education facilities and public offices benefit from having clean, hygienic and safe floor coverings. Eternal heterogeneous sheet is available in a wide variety of close-to-nature designs of wood, stone and material expressions that allow an interior space to take on a homely, natural look and feel whilst offering an easy to clean and maintain solution. Eternal is phthalate free, REACH® compliant, low emitting and guarantees lasting appearance retention in heavy traffic environments.

ETERNAL COLLECTION AT A GLANCE

eternal® wood

The Eternal Wood collection contains a large variety of realistic wood designs and plank sizes, including some multi-width plank designs.



eternal® material

This modern collection of textiles, metals and stones which create a soft, elegant look and feel.



eternal® colour

From bold solid colours, to subtle colour gradients that run along the full width of a roll, Eternal Colour offers an inspiring choice of colour and design.



eternal® original

Eternal Original is offering you many possibilities for use in many different applications. The quality of Eternal Original will never disappoint you, it has a very good performance and long lifetime, guaranteed by the proven technology of our PUR protection.



eternal® de luxe

Eternal de Luxe is part of the Eternal product offer. It creates better environments in which to work, live, interact, relax, heal, learn and play. Eternal is always giving you reliable and beautiful solutions. Eternal de Luxe is focused on high end design, performance and comfort.





The Eternal Wood collection contains a large variety of realistic wood designs and plank sizes, including some multi-width plank designs.



40232 | night 10132 | bright colourful planks



10132 | bright colourful planks



10112 | soft colourful planks



11912 | whitewashed oak

LRV 30



11952 | steamed oak

LRV 22



11932 | rustic oak*

LRV 20



11942 | dark grey oak*

LRV 12



40672 | ocean | 12802 elegant oak



12802 | elegant oak*

LRV 32



12832 | natural oak

LRV 27



12862 | grey oak*

LRV 25



13442 | light oak

LRV 33



13412 | shadow oak

LRV 22

* Also available in Step Safety vinyl



13932 | pale timber LRV 31



13802 | blond timber LRV 26



13922 | bleached timber LRV 36



13942 | classic timber LRV 22



13952 | greywashed timber LRV 23



13002 | silver concrete 13952 | greywashed timber



11632 | light oak LRV 31



11652 | vintage oak LRV 26



10842 | cream oak LRV 44



10832 | hazelnut oak LRV 21



10852 | chocolate oak LRV 17

* Also available in Step Safety vinyl



36022 | classic herringbone 13322 | grey marble



36022 | classic herringbone LRV 21



36042 | brown herringbone LRV 18



36062 | grey herringbone LRV 13



10322 | white chestnut* LRV 34



10362 | warm chestnut LRV 17




10342 | dark chestnut LRV 12



11542 | traditional oak LRV 22



10232 | dark walnut LRV 18



11162 | tropical beech LRV 27




11442 | washed beech LRV 28


Description	Sheet vinyl
Dimensions	Roll width 2m Roll length 24-30 lm
Total thickness	EN ISO 24346 2.0mm
Thickness wear layer	EN ISO 24340 0.7mm
Collection size	96
Application	EN 10874 Class 34/43
CE	EN 14041
Reaction to fire	EN 13501-1 B ₁ -s1, L, NCS
Slip resistance	EN 13893 $\mu \geq 0.30$



A modern collection of textiles, metals and stones which create a soft, elegant look and feel.



Description	Sheet vinyl
Dimensions	Roll width 2m Roll length 24-30 lm
Total thickness	EN ISO 24346 2.0mm
Thickness wear layer	EN ISO 24340 0.7mm
Collection size	31
Application	EN 10874 Class 34/43
CE	EN 14041
Reaction to fire	EN 13501-1 B ₁ -s1, L, NCS
Slip resistance	EN 13893 $\mu \geq 0.30$






eternal® colour

From bold solid colours, to subtle colour gradients that run along the full width of a roll, Eternal Colour offers an inspiring choice of colour and design.



Description	Sheet vinyl
Dimensions	Roll width 2m Roll length 24-30 lm
Total thickness	EN ISO 24346 2.0mm
Thickness wear layer	EN ISO 24340 0.7mm
Collection size	34
Application	EN 10874 Class 34/43
CE	EN 14041
Reaction to fire	EN 13501-1 B ₁ -s1, L, NCS
Slip resistance	EN 13893 $\mu \geq 0.30$



* Also available in Step Safety vinyl

eternal® original

Eternal Original is offering you many possibilities for use in many different applications. The quality of Eternal Original will never disappoint you, it has a very good performance and long lifetime, guaranteed by the proven technology of our PUR protection. The high % of recycled content in the backing contributes to a positive sustainability profile. The collection offers a wide variety of wood types and sizes, a contemporary pallet of colour choices and much appreciated original concrete and smaragd design.

Description	Sheet vinyl
Dimensions	Roll width 2m Roll length ≤25m
Total thickness	EN ISO 24346 2.0mm
Thickness wear layer	EN ISO 24340 0.7mm
Collection size	30
Application	EN 10874 34/43
CE	EN 14041
Reaction to fire	EN 13501-1 B _{f1} -s1, L, NCS
Slip resistance	EN 13893 μ ≥0.30



11122 | natural beech LRV 41



11132 | dark beech LRV 15



12562 | light oak LRV 38



68952 | natural oak LRV 30



11612 | mid oak LRV 28



10432 | grey washed oak LRV 38




68962 | grey oak LRV 27



10452 | dark oak LRV 10



10562 | real oak LRV 23



68972 | country oak LRV 20




13452 | loam LRV 33




13432 | silt LRV 33



13482 | concrete LRV 26




13512 | anthracite LRV 15



13482 | concrete




61052 | white smaragd LRV 61




61062 | greige smaragd LRV 34



61042 | mist smaragd LRV 39




61962 | grey smaragd LRV 21



61032 | nero smaragd LRV 8



68702 | pebble LRV 32



68712 | rock LRV 23



68752 | cornflower LRV 19



68762 | papaya LRV 25



68772 | lychee LRV 15



68752 | cornflower, 68762 | papaya



68802 | dune LRV 46




68792 | asparagus LRV 30



68722 | olive LRV 18



68732 | lemon LRV 53




68792 | asparagus LRV 30




68742 | blueberry LRV 12



68782 | mint LRV 31



68752 | cornflower LRV 19



68742 | blueberry LRV 12

eternal® de luxe

Eternal de Luxe is part of the Eternal product offer. It creates better environments in which to work, live, interact, relax, heal, learn and play. Eternal is always giving you reliable and beautiful solutions. Eternal de Luxe is focused on high end design, performance and comfort. The Comfort construction (number starts with a 2) of 3 mm thickness has a 17 dB acoustic rating and ergonomic construction. The Compact construction (number starts with a 3) of 2 mm thickness is offering best possible residual indentation and durability

	compact	comfort
Dimensions	Roll width 2m / 4m Roll length ≤25m	Roll width 2m / 4m Roll length ≤25m
Total thickness	EN ISO 24346 2.0mm	3.0mm
Thickness wear layer	EN ISO 24340 0.7mm	0.7mm
Collection size	10	20
Application	EN 10874 Class 23/34/43	Class 23/33/42
CE	EN 14041 0200105-DoP-306	0200403-DoP-306
Reaction to fire	EN 13501-1 B ₁ -s1, G, NCS	B ₁ -s1, G, NCS
Slip resistance	EN 13893 μ ≥0.30	μ ≥0.30



3074 | classic large herringbone



3073 | blond large herringbone

LRV 32



3074 - 2754 | classic large herringbone

LRV 21



3092 - 2712 | bleached elegant oak

LRV 30



3018 - 2558 | whitewashed oak

LRV 37



3093 | warm elegant oak

LRV 26



3016 - 2856 | light honey oak

LRV 36



3094 | dark elegant oak

LRV 17



3010 | warm honey oak

LRV 22



3048 | pale oak

LRV 38



3024 - 2894 | grey pine

LRV 30



3045 - 2865 | natural oak

LRV 29



3052 - 2842 | golden oak

LRV 24



3005 | multisize light oak

LRV 33



3006 - 2816 | multisize hazelnut oak

LRV 16



3066 | mortar concrete



3066 | mortar concrete

LRV 37




3117 | white neutral grey

LRV 34



3067 | graphite concrete

LRV 23




3011 - 2781 | light neutral grey

LRV 25



3068 | warm concrete

LRV 21



3112 - 2782 | mid neutral grey

LRV 14

SARLON COLLECTION AT A GLANCE

This collection is available both in Sarlon 15dB and 19dB and in Modul'up 19dB and compact.

See page 164 for the Modul'up collection.



XTREM PUR

- EXTREMELY HIGH-PERFORMANCE LACQUER PROTECTION WITH
- Best possible chemical resistance, blocking even the toughest stains on surface for an easy maintenance
 - Durable resistance against scuff, scratch and other appearance disturbances
 - Easy to clean surface, giving no room for bacteria to grow, and perfectly hygienic
 - Natural matt appearance to enhance the design and comes with an R10



sarlon® 19dB

THE BEST ACOUSTIC HIGH TRAFFIC PRODUCT IN THE MARKET

- Highest acoustic sound reduction of 19dB
- Best residual indentation for a 19dB acoustic product
- High performance characteristics on all relevant aspects



sarlon® 15dB

THE BEST COMPROMISE ON ACOUSTIC AND HIGH LOAD REQUIREMENTS

- Low residual indentation, suitable for heavy loads
- 15dB acoustic performance for additional comfort at high performance
- A unique product proposition in the market

Both constructions have very low emissions, are phthalate free and made with green energy and meet all relevant environmental and quality standards.

sarlon®

Diversity, better together

The known high quality acoustic vinyl of Sarlon and the market leading concept of Modul'up are combined into one dedicated collection. It offers the highest diversity, in meeting your specific project requirements, in today's environment.

The diversity in design in this range with over 90 designs and colour options gives you enough choice for any dynamic in your building. The constellation of the design concept is built in such a way that next to offering very strong individual solutions on the different types of design there are also strong links created to connect the whole concept.



Sound reduction

There are two different types of sound that can impact your working or living environment. The **in-room impact** sound is related to impact sound in the room itself. You want to reduce this to create a more calm and pleasant environment. All products in this range offer a lot of sound reduction and are rated Class A, so best possible class and will bring this benefit to create a better environment.

Impact sound relates to the sound that is transmitted through the floor from one level to the level below. Reducing this impact sound is a critical characteristic in more and more environments and with our 19dB products we offer the best possible improvement on impact sound from rooms above, as measured in EN ISO 717-2. In combination with the other superior performance characteristics Forbo Flooring is really leading in this important contributor to well being in many occasions.

Indentation resistance


Floors need to be strong to remain beautiful and indentation under pressure can be a major issue. For projects where sound reduction is the key priority, our 19 dB solutions offer excellent acoustic properties with residual indentation performance that's best in class. For areas where sound reduction is required but the floor covering may be subjected to very heavy or rolling loads, Sarlon 15 dB will give you the optimum balance between acoustic performance and residual indentation.

When pressure is applied continuously or with very acute pressure points (for example, a table leg) then a compact solution is recommended. Modul'up Compact offers the highest resistance to residual indentation, with the additional benefit of an adhesive free installation.



Sarlon 15dB

The **best compromise** on acoustic and high load requirements. **Low residual indentation**, suitable for heavy loads. 15dB acoustic performance for additional comfort at **high performance**. A **unique** product proposition in the market.




Offering excellent residual indentation performance for an acoustic floor covering and perfect for high traffic environments

	Pressure level $L_{p,r}$ concrete slab floor	Pressure level $L_{p,r}$ with Sarlon 15dB		Typical needs in hospital environments	Sarlon 15dB is the acoustic solution for areas where the highest indentation performance is key.
18 cm	74 dB	59 dB	✓	 ≤ 60 dB	 PR 0.05 mm ≤ 0.10 mm Requirement for compact flooring NF EN ISO 24343-1
20 cm	72 dB	57 dB	✓		
22 cm	70 dB	55 dB	✓		

Sarlon 19dB

The best acoustic **high traffic** product in the market. Highest acoustic sound reduction of 19dB. **Best residual indentation** for a 19 dB acoustic product. High performance characteristics in all other areas.




Underneath each colour on the next pages you only find the colour number. To order the right construction, please add the following codes as suffix to the colour number.

- Sarlon 19 dB** **T4319**
- Sarlon 15 dB** **T4315**

Example:

When you want the item blond chill oak in Sarlon 19dB, you take colour number 8513 and add T4319 at the end.

This is how you would specify this example order:




Technical specifications

Sarlon 19 dB meets the requirements of EN 651 and ISO 11638



		Sarlon 15 dB	Sarlon 19 dB
Total thickness	EN ISO 24346	2.6 mm	3.4 mm
Wear layer thickness	EN ISO 24340	0.70 mm	0.70 mm
Total weight	EN ISO 23997	2.700 g/m ²	2.900 g/m ²
Impact sound reduction	EN ISO 717-2	$\Delta L_w = 15$ dB	$\Delta L_w = 19$ dB
In-room impact noise	NF S 31-074	$L_{n,e,w} < 65$ dB, Class A	$L_{n,e,w} < 65$ dB, Class A
Sound absorption	EN ISO 354 EN ISO 11654	$\alpha_w = \pm 0.05$	$\alpha_w = \pm 0.05$
Residual indentation typical value Requirement	EN ISO 24343-1	0.05 mm ≤ 0.20 mm	0.08 mm ≤ 0.20 mm
Slip resistance	DIN 51130	R10	R10
Dimensional stability	EN ISO 23999	≤ 0.10 %	≤ 0.10 %
Surface treatment		XtremPUR™	XtremPUR™
Abrasion resistance	EN 660-2	T	T
Stain resistance	EN ISO 26987	Excellent	Excellent
Emissions into air : TVOC* at 28 days	EN 16516	≤ 0.01 mg/m ³	≤ 0.01 mg/m ³
Reaction to fire	EN 13501-1	B _{fl} - s1, L, NCS	B _{fl} - s1, L, NCS



The Wood range consists of a nice variety of relevant wood designs and colours, including the new Chill Oak design with a realistic colour variation within the planks. A design statement is the Hybrid Wood Concrete design; combining herringbone wood with concrete planks in a repeat of 300x200cm, combining well with wood and concrete designs.



Cement and concrete designs are widely appreciated and used and the range now also includes subtle metallic Slabstone, natural lively stone Stromboli and hybrid Dissolved Stone concrete/stone effects.





The Material range presents a modern range of designs based on popular flooring materials like cement, concrete, stones and textiles. Nairobi and Canvas are textile weave effects with different scale and sophistication levels, both very suitable for shading combinations where low contrast is required. Cement and concrete designs are widely appreciated and used.



302 | light grey nairobi LRV 30 312 | anthracite nairobi LRV 22 303 | sand nairobi LRV 26 304 | taupe nairobi LRV 13



307 | pastel blue nairobi LRV 40



337 | indigo blue canvas LRV 15




337 | indigo blue canvas, 307 | pastel blue nairobi



332 | light grey canvas LRV 20



342 | natural grey canvas LRV 26



333 | warm sand canvas LRV 28



339 | brown canvas LRV 13



713 | peanut concrete LRV 28




771 | silver concrete LRV 28




761 | steel concrete LRV 16



742 | pewter concrete LRV 12



267 | cobalt blue canyon LRV 42




248 | lime green canyon LRV 49



235 | lemon canyon LRV 60




235 | lemon canyon, 406 | red doodle



223 | sand canyon RV 53




223 | sand canyon, 409 | black & white doodle



200 | ivory canyon LRV 50



211 | light grey canyon LRV 34




212 | grey canyon LRV 27




209 | medium grey canyon LRV 19



The Graphic range consists of stunning graphical and organic patterns that really can make statements on your floor. Hand drawn textures of Topography and the new Doodle design transfer in to the graphical interpretation of a terrazzo in the Graphito. The Terrazzo is based on real stones. The most daring design, incorporating the Doodle and Graphito design, is the statement design Kubik. All items in the Graphic range give inspiration for combination with other parts of the range.



9602 | grey graphito




9609 | black graphito

LRV 18




9602 | grey graphito, 9609 | black graphito, 307 | pastel blue nairobi



402 | grey & white doodle

LRV 48



409 | black & white doodle

LRV 33



922 | steel grey topography

LRV 29




919 | grey topography

LRV 13



409 | black & white doodle



405 | yellow doodle

LRV 55



928 | lime topography

LRV 54



406 | red doodle

LRV 27



408 | dark green doodle

LRV 13




9608 | green graphito, 878 | dark green uni, 235 | lemon canyon




407 | blue doodle

LRV 10




9608 | green graphito

LRV 17



9607 | blue graphito

LRV 15




9307 | pastel kubik

LRV 31



9307 | pastel kubik, 877 | dark blue uni



9309 | dark kubik

LRV 40




651 | silver slabstone, 9402 | natural terrazzo



9402 | natural terrazzo


LRV 39



9406 | coral terrazzo, 659 | mercury slabstone



8513 | blond chill oak, 9406 | coral terrazzo




9406 | coral terrazzo

LRV 46



The Colour range presents uni and fine textured all over designs. The designs Uni and Stardust have a coloured wearlayer. This gives an intense deep colour effect. The range reflects the latest developments in colour trends and is easy to combine with almost all designs in the total range. Colourful statement of positivity is the playful Color Splash design. This organic, daring, colourful design consists of 24 colours and has a repeat of 600x200 cm!



9100 | multi color splash

LRV 31




9100 | multi color splash




9107 | indigo color splash

LRV 14



868 | lime uni LRV 48 878 | dark green uni LRV 14 867 | blue uni LRV 17 877 | dark blue uni LRV 6




865 | yellow uni LRV 61 866 | mandarine uni LRV 33 876 | orange uni LRV 22 886 | red uni LRV 13




9608 | green graphito, 878 | dark green uni, 235 | lemon cayon




863 | beige grey uni LRV 39 861 | light grey uni LRV 41 862 | stone grey uni LRV 27 869 | charcoal uni LRV 13



3811 | grey beige cristal LRV 47 3801 | pearl cristal LRV 41 3812 | light grey cristal LRV 29 3819 | medium grey cristal LRV 18



9107 | indigo color splash, 405 | yellow doodle



4807 | lilac stardust LRV 64 4803 | vanilla stardust LRV 69 4806 | soft peach stardust LRV 57



4803 | vanilla stardust, 307 | pastel blue nairobi



4808 | soft pistache stardust LRV 69 4818 | lime stardust LRV 70 4817 | soft blue stardust LRV 61 4827 | deep blue stardust LRV 24



4804 | copper stardust, 4806 | soft peach stardust



4801 | silver stardust LRV 35 4805 | golden stardust LRV 52 4804 | copper stardust LRV 20



761 | steel concrete, 4804 | copper stardust

MODUL'UP LOOSE LAY VINYL AT A GLANCE

This collection is available in loose lay Modul'up 19dB and compact but also in Sarlon 15dB and 19dB.

See page 148 for the Sarlon acoustic collection.

XTREM PUR



- EXTREMELY HIGH-PERFORMANCE LACQUER PROTECTION WITH
- Best possible chemical resistance, blocking even the toughest stains on surface for an easy maintenance
 - Durable resistance against scuff, scratch and other appearance disturbances
 - Easy to clean surface, giving no room for bacteria to grow, and perfectly hygienic
 - Natural matt appearance to enhance the design and comes with an R10

modul'up® 19dB



- THE BEST FULLY LOOSE LAID SHEET ACOUSTIC SOLUTION
- Quick installation (without disturbing occupied areas), immediate use possible
 - Long term benefit of very quick replacement and removal, saving money over time
 - Offering all benefits of the best performing acoustic with less overall material

modul'up® compact



- THE BEST FULLY LOOSE LAY SHEET COMPACT SOLUTION
- Speed of installation and renewal reduces downtime and is immediately ready for use after installation
 - Compact and strong solution for heavy traffic and intense use
 - Possibility to use over existing flooring, no the need to remove on many occasions

Modul'up products are part of the circular economy product design concept and do not require any glue or tape.

Both constructions have very low emissions, are phthalate free and made with green energy and meet all relevant environmental and quality standards.

modul'up®

Diversity, better together

The known high quality acoustic vinyl of Sarlon and the market leading concept of Modul'up are combined into one dedicated collection. It offers the highest diversity, in meeting your specific project requirements, in today's environment.

The diversity in design in this range with over 90 designs and colour options gives you enough choice for any dynamic in your building. The constellation of the design concept is built in such a way that next to offering very strong individual solutions on the different types of design there are also strong links created to connect the whole concept.

Loose lay flooring, the circular solution

modul'up® 19dB and compact

Modul'up is the best loose lay floor covering available for high traffic applications. It can be installed quickly without adhesives, but is even more time and cost efficient at time of replacement. Millions of m² has been sold around the world which has proven that the Modul'up adhesive free concept is trusted and reliable. The range is suitable for sustainable solutions due to the reusability of the product.

Modul'up is available in an acoustic (19 dB) and compact version. Both formats offer the best possible quality and durability, now


NEW BUILDS

- Shorter installation times
- Reduced maintenance and service costs
- Same supplied & fitted price as a glue-down floor covering (initial installation)


enhanced with the introduction of XtremPUR™ protection on all products. Both have the benefit of not having to use installation adhesive and are very suitable for busy areas: installation time is reduced by up to 50% compared to standard, glued down products and there is minimal disruption or lingering adhesive odours. Modul'up can be walked on immediately after installation. As minimal subfloor preparation is required, over 20% of costs can be saved when using Modul'up compared to a standard, glued down product.

RENOVATIONS

- Installation while premises are in use without any disruption (noise, dust, adhesive odours etc.)
- Instantly ready for use after installation
- Possibility of covering old floor tiles (ceramic tiles, compact vinyl, etc.)



Modul'up adhesive free floors, the advantages at a glance



Modul'up 19 dB

- The adhesive free acoustic sheet solution
- Rapid installation with minimal downtime and disturbance, and can be walked on immediately after use
- Long term benefit of very quick removal, replacement and end of life recycling or reuse, saving money over time
- As part of Forbo's Fast Flooring collection, Modul'up can reduce downtime by over 50% compared to standard, glued down products

XtremPUR

The high performance surface protection with double (laser + UV) curing technology further developed and evolved for the future.


D3s Core

Double structural stabilisation system

- Loose-lay installation
- Perfect dimensional stability
- Heavy-duty resistance




Loose Lay flooring



19dB impact sound reduction
High-performance base foam

Modul'up compact

- The adhesive free compact solution
- Speed of installation and renewal reduces downtime and is immediately ready for use after installation.
- High performance for heavy traffic and intense use, including where rolling loads may be part of the everyday use
- Can be installed over existing flooring in many instances, removing the need for expensive and time-consuming subfloor preparation



XtremPUR

The high performance surface protection with last generation double (laser + UV) curing technology

- Easy cleaning
- Extreme resistance to stain and chemicals
- Enhance design look
- Lifetime wear resistance?

D3s Core

Double structural stabilisation system

- Loose-lay installation
- Perfect dimensional stability
- Heavy-duty resistance

Compact backing dimensionally stable

- Very low indentation value
- Easy rolling



Loose Lay flooring

Underneath each colour on the next pages you only find the colour number. To order the right construction, please add the following codes as suffix to the colour number.

Modul'up 19 dB



UP4319

Modul'up compact



UP43C

Example:

When you want the item blond chill oak in Modul'up 19dB, you take colour number 8513 and add UP4319 at the end.

This is how you would specify this example order:

8513 UP4319

colourway number

construction type


Technical specifications

Modul'up 19dB meet the requirements of EN 651 and ISO 11638. Modul'up Compact meet the requirements of EN 10582



		Modul'up 19 dB	Modul'up Compact	
	Total thickness	EN ISO 24346	3.45 mm	2.0 mm
	Wear layer thickness	EN ISO 24340	0.70 mm	0.70 mm
	Total weight	EN ISO 23997	2.830 g/m ²	2.600 g/m ²
	Impact sound reduction	EN ISO 717-2	ΔL _w = 19 dB	n.a.
	In-room impact noise	NF S 31-074	L _{n,e,w} < 65 dB, Class A	L _{n,e,w} < 75 dB, Class B
	Sound absorption	EN ISO 354 EN ISO 11654	α _w = ± 0.05	α _w = ± 0.05
	Residual indentation typical value Requirement	EN ISO 24343-1	0.08 mm ≤ 0.20 mm	0.02 mm ≤ 0.10 mm
	Slip resistance	DIN 51130	R10	R10
	Dimensional stability	EN ISO 23999	≤ 0.10 %	≤ 0.10 %
	Surface treatment		XtremPUR™	XtremPUR™
	Abrasion resistance	EN 660-2	T	T
	Stain resistance	EN ISO 26987	Excellent	Excellent
	Emissions into air: TVOC* at 28 days	EN 16516	≤ 0.01 mg/m ³	≤ 0.01 mg/m ³
	Reaction to fire	EN 13501-1	B _{fl} -s1, L, NCS	B _{fl} -s1, L, NCS



The Wood range consists of a nice variety of relevant wood designs and colours, including the new Chill Oak design with a realistic colour variation within the planks. A design statement is the Hybrid Wood Concrete design; combining herringbone wood with concrete planks in a repeat of 300x200cm, combining well with wood and concrete designs.




Cement and concrete designs are widely appreciated and used and the range now also includes subtle metallic Slabstone, natural lively stone Stromboli and hybrid Dissolved Stone concrete/stone effects.






The Material range presents a modern range of designs based on popular flooring materials like cement, concrete, stones and textiles. Nairobi and Canvas are textile weave effects with different scale and sophistication levels, both very suitable for shading combinations where low contrast is required. Cement and concrete designs are widely appreciated and used.






The Graphic range consists of stunning graphical and organic patterns that really can make statements on your floor. Hand drawn textures of Topography and the new Doodle design transfer in to the graphical interpretation of a terrazzo in the Graphito. The Terrazzo is based on real stones. The most daring design, incorporating the Doodle and Graphito design, is the statement design Kubik. All items in the Graphic range give inspiration for combination with other parts of the range.



9602 | grey graphito

LRV 44




9609 | black graphito

LRV 18




9607 | blue graphito, 637299 | cement medium grey, nose black



402 | grey & white doodle

LRV 48



409 | black & white doodle

LRV 33



922 | steel grey topography

LRV 29




919 | grey topography

LRV 13



9607 | blue graphito, 637299 | cement medium grey, nose black



405 | yellow doodle

LRV 55




928 | lime topography

LRV 54




406 | red doodle

LRV 27




408 | dark green doodle

LRV 13




9607 | blue graphito, 637299 | cement medium grey, nose black




407 | blue doodle

LRV 10




9608 | green graphito

LRV 17



9607 | blue graphito

LRV 15




9307 | pastel kubik

LRV 31



9307 | pastel kubik, 877 | dark blue uni



9309 | dark kubik

LRV 40




9100 | multi color splash



9402 | natural terrazzo


LRV 39



9406 | coral terrazzo, 659 | mercury slabstone



8513 | blond chill oak, 9406 | coral terrazzo




9406 | coral terrazzo

LRV 46



The Colour range presents uni and fine textured allover designs. The designs Uni and Stardust have a coloured wearlayer. This gives an intense deep colour effect. The range reflects the latest developments in colour trends and is easy to combine with almost all designs in the total range. Colourful statement of positivity is the playful Color Splash design. This organic, daring, colourful design consists of 24 colours and has a repeat of 600x200 cm!



9100 | multi color splash

LRV 31




9100 | multi color splash




9107 | indigo color splash

LRV 14



868 | lime uni LRV 48 878 | dark green uni LRV 14 867 | blue uni LRV 17 877 | dark blue uni LRV 6



865 | yellow uni LRV 61 866 | mandarine uni LRV 33 876 | orange uni LRV 22 886 | red uni LRV 13




9608 | green graphito, 878 | dark green uni, 235 | lemon cayon




863 | beige grey uni LRV 39 861 | light grey uni LRV 41 862 | stone grey uni LRV 27 869 | charcoal uni LRV 13



3811 | grey beige cristal LRV 47 3801 | pearl cristal LRV 41 3812 | light grey cristal LRV 29 3819 | medium grey cristal LRV 18



9107 | indigo color splash, 405 | yellow doodle



4807 | lilac stardust LRV 64 4803 | vanilla stardust LRV 69 4806 | soft peach stardust LRV 57




4803 | vanilla stardust, 307 | pastel blue nairobi



4808 | soft pistache stardust LRV 69 4818 | lime stardust LRV 70 4817 | soft blue stardust LRV 61 4827 | deep blue stardust LRV 24



4804 | copper stardust, 4806 | soft peach stardust



4801 | silver stardust LRV 35 4805 | golden stardust LRV 52 4804 | copper stardust LRV 20



761 | steel concrete, 4804 | copper stardust

SAFETY VINYL

Your steps: Sure and Safe

Forbo's Step safety flooring collection provides a complete range of products designed to meet safety demands across a wide range of applications, from general areas to more extreme areas such as commercial kitchens, wetroom (barefoot) areas and industrial applications.

The Step range meets all HSE and European safety norms and delivers safety with minimal compromise in terms of cleaning and maintenance due to the PUR Pearl finish.

All Step safety vinyl flooring has a guaranteed slip resistant performance throughout the life of the product.



Slips are amongst the most frequent accidents in the indoor environment. In our effort to make a positive contribution to the quality of indoor spaces our Step collection offers a wide variety of genuine safety flooring solutions. Many offer natural visuals such as wood and natural stone allowing customers to have the functionality of a true safety floor combined with the feeling of well-being which can be achieved through natural designs avoiding a 'cold' and institutional look and feel. Our Step ranges are also phthalate free for improved indoor air quality.

STEP COLLECTION AT A GLANCE

surestep® original

R10

Surestep Original offers a fresh alternative to conventional safety flooring with an improved cleaner aesthetic. 4 items in the range are also available in decibel construction.



184

surestep® laguna

R10

This product combines barefoot and footwear slip resistance, for areas where both are likely and frequently will take place. Complying with the relevant norms for the application, Laguna is suitable for use in transition areas such as changing rooms and circulation areas.



189

surestep® star

R10

Innovative, muted and sophisticated. The 9 contemporary tones offer hints of grey and a unique aesthetic. Surestep Star offers a brighter visual with holographic particles colour matched to the terazzo or natural base colour of each item. 3 items in the range are also available in a barefoot construction suitable for wetroom use.



186

safestep® R11

R11

Available in 9 colours and designed specifically to match the areas where a high level of slip resistance is needed such as professional kitchens. All items are colour co-ordinated with the R12 range.




190

surestep® steel

R10

Surestep Steel delivers a new visual to the collection, with a smooth concrete look and a metallic sparkle effect in the background across a palette of 4 colours.



186

safestep® R12

R12

Safestep R12 is a high slip resistant R12 rated floor which ensures slip resistance under even the most extreme conditions. All items are colour coordinated with the R11 range.



190

surestep® material

R10

A concise mix of stone, textured and mineral structures add depth and refinement to the collection.



187

surestep® decibel

R10

A genuine Health and Safety Executive compliant safety floor, Surestep Decibel offers sustainable R10 slip resistance underfoot, beautiful designs and a 17dB impact sound reduction.



191

surestep® wood

R10

Realistic natural designs provide a warm ambience to all areas. The Surestep Wood palette of 11 colourways contains our most popular bestselling colours alongside new abstract woods and all-over designs. 4 items feature our new PUR Wood Pearl embossing and 4 are available in a decibel construction.



188

surestep® digital print

R10

Safety flooring design now knows no bounds with our new digitally printed options.



192

For our wetroom floor and wall covering solutions, please see page 194.

SAFETY VINYL

HSE Compliance – Wet Pendulum Test ≥ 36

All Step floors are tested using the TRRL Pendulum test, the preferred test method of the HSE which is used to assess the slip resistance of a floor surface. Floors can be tested with different rubber sliders to assess either footwear or barefoot use. Using this test, a Pendulum test value (PTV) of ≥ 36 or higher is considered to offer a low slip risk.

Surestep, Safestep R11 and R12 products offer wet Pendulum test values of ≥ 36 to ≥ 50 for footwear applications. In addition, Surestep Laguna, Safestep Aqua and Surestep Star barefoot offer wet Pendulum test values of ≥ 36 for barefoot use areas.



≥ 20 microns
surface roughness

≥ 36
Wet Pendulum

≥ 40
Wet Pendulum

≥ 50
Wet Pendulum

Step Crystals

Many of the products in the Forbo Step range include Step Crystals which offer a clear and light aesthetic and also reduced soiling. As Step Crystals are made from recycled material, they also enhance the environmental performance of the collection.

Dual functionality

The Surestep Decibel range is a genuine Health and Safety Executive compliant safety floor which has a 17dB impact sound reduction.



R10

Creating better environments

- Our Step range contains up to 70% controlled vinyl waste in the backing.
- Many of the products in the Step range contain Step Crystals. They are made from recycled material so enhance the environmental performance of the product.
- We produce all our vinyl in Europe where it meets the highest possible REACH compliance standards for chemical content.
- Of all the electricity we buy, 100% comes from renewable sources. This means our vinyl production sites are part of an effective environmental management system and achieve ISO14001 certification.
- We use smart material constructions and durable finishes on our vinyl. A micro-embossing technology reduces the need for chemical cleaning and increases the floor's lifespan.
- All ranges in our Step collection are phthalate free.

APPLICATIONS – STEP COLLECTION

surestep[®] R10

General and spillage areas with increased (a higher) slip risk

- High traffic areas, ramps or corridors
- Tea and coffee points
- General workrooms
- Service areas
- Kitchens, dining rooms to food servery areas
- Washroom areas



184

safestep[®] R11

Areas with increased slip risk due to continuous contamination

- Professional kitchens
- Florist shops
- Laundrettes



190

safestep[®] R12

Intensive use and high contamination areas

- Light industrial food production areas
- Woodworking rooms and other workshops
- Store rooms
- Commercial kitchens



190

surestep® original






Surestep Original offers a fresh alternative to conventional safety flooring with an improved cleaner aesthetic. A palette of 33 colours combines gradations of hue and lightness.

Specifications: R10, ESf, TRRL ≥36, Rz ≥20

*4 colours of the Surestep original range are available with 17dB impact sound reduction as Surestep original decibel. Speckled welds are available for all colours in the range.

Description	Sheet safety vinyl	
Dimensions	Roll width 2m Roll length 20-27 lm	
Total thickness	ISO 1765	2.0mm
Thickness wear layer	EN-ISO 24340	0.7mm
Collection size	33	
Application	EN 10874	Class 34/43
Slip resistance	EN 13845 Annex C	ESf
	DIN 51130	R10
	TRRL Pendulum – Wet test – slider 96	≥ 36
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1
Slip resistance	EN 13893	DS: ≥0.30

See page 191 for the Surestep decibel technical specification.



Full technical specifications are available at www.forbo-flooring.com. Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.


surestep® star surestep® steel



Innovative, muted and sophisticated. The 13 contemporary tones offer hints of grey and a unique aesthetic. Surestep Star offers a brighter visual with holographic particles colour matched to the terazzo or natural base colour of each item.

Surestep Steel offers a smooth concrete look with a subtle metallic sparkle in the background.



*3 colours of the Surestep star range shown below are available in an Esb (barefoot) option.



Description	Sheet safety vinyl
Dimensions	Roll width 2m Roll length 20-27 Im
Total thickness	ISO 1765 2.0mm
Thickness wear layer	EN-ISO 24340 0.7mm
Collection size	9 / 4
Application	EN 10874 Class 34/43
Slip resistance	EN 13 845 Annex C ESf DIN 51130 R10
	TRRL Pendulum – Wet test – slider 96 ≥ 36
CE	EN 14041
Reaction to fire	EN 13501-1 B _{fl} -s1
Slip resistance	EN 13893 DS: ≥0.30

For Surestep Star Barefoot technical specification, please visit www.forbo-flooring.co.uk/step

Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product.
Please order a sample to see the full effect.



surestep® material




A concise mix of stone, textured and mineral structures add depth and refinement to the collection.

*4 colours of the Surestep material range shown below are available with 17dB impact sound reduction as Surestep material decibel.

Description	Sheet safety vinyl	
Dimensions	Roll width 2m Roll length 20-27 Im	
Total thickness	ISO 1765	2.0mm
Thickness wear layer	EN-ISO 24340	0.7mm
Collection size	11	
Application	EN 10874	Class 34/43
Slip resistance	EN 13845 Annex C	ESf
	DIN 51130	R10
	TRRL Pendulum – Wet test – slider 96	≥ 36
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1
Slip resistance	EN 13893	DS: ≥0.30

See page 191 for the Surestep decibel technical specification.



Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product.
Please order a sample to see the full effect.

surestep® wood



Realistic natural designs provide a warm ambience to all areas. The Surestep Wood palette of 11 colourways contains our most popular bestselling colours alongside new abstract woods and all-over designs. All the wood designs have a clear and sharp visual due to the use of the almost invisible 'Step Crystals', which also guarantee lifetime slip resistance. Four items also feature our new PUR Wood Pearl embossing.

*4 colours of the Surestep wood range shown are available with 17dB impact sound reduction as Surestep decibel. Please see page 191 for full range overview.



Description	Sheet safety vinyl	
Dimensions	Roll width 2m	Roll length 20-27 lm
Total thickness	ISO 1765	2.0mm
Thickness wear layer	EN-ISO 24340	0.7mm
Collection size	11	
Application	EN 10874	Class 34/43
Slip resistance	EN 13845 Annex C	ESf
	DIN 51130	R10
	TRRL Pendulum – Wet test – slider 96	≥ 36
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1
Slip resistance	EN 13893	DS: ≥0.30

See page 191 for the Surestep decibel technical specification.



18372 | white chestnut **PUR Wood Pearl** LRV 34



18962 | whitewash oak* LRV 25



18802 | elegant oak* LRV 32



18972 | rustic oak* **PUR Wood Pearl** LRV 18



18882 | classic oak* LRV 24




18942 | natural oak LRV 25



18382 | chestnut **PUR Wood Pearl** LRV 22



18792 | dark oak LRV 12



18832 | grey oak LRV 23



18952 | dark grey oak **PUR Wood Pearl** LRV 12



18982 | shadow oak LRV 20


surestep® laguna



This product combines barefoot and footwear slip resistance, for areas where both are likely and frequently will take place. Complying with the relevant norms for this application, Laguna is suitable for use in transition areas such as changing rooms and circulation areas. The subtle, soil hiding design is available in 15 colourways, offering a clean and fresh look. Suitable for wheelchair use.

Surestep Laguna's plain and non-reflective decoration makes it ideal for use in dementia applications. Visit www.forbo-flooring.com for more information.

Description	Sheet safety vinyl	
Dimensions	EN-ISO 24341	Roll width 2.0m Roll length 20-27 lm
Total thickness	ISO 1765	2.0mm
Thickness wear layer	EN-ISO 24340	0.7mm
Collection size	15	
Application	EN 10874	Class 34/43
Slip resistance	EN 13845 Annex C	ESb/ESf
	DIN 51130	R10
	TRRL Pendulum – Wet test – slider 96	≥ 36
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1
Slip resistance	EN 13893	DS: ≥0.30



181262 | trout LRV 55 181862 | silver grey LRV 42 181482 | greige LRV 38



181692 | mouse LRV 28 181072 | pewter LRV 26 181922 | concrete LRV 28



181912 | flamingo LRV 35 181982 | aquamarine LRV 33 181802 | lemon LRV 70



181592 | lava LRV 10 181632 | coal LRV 16 181092 | elephant LRV 18



181972 | magenta LRV 12 181822 | lagoon LRV 16 181882 | emerald LRV 19



Surestep Laguna 181802 | lemon + 181912 | flamingo + 181982 | aquamarine

safestep® R11 safestep® R12




With a palette of 9 colours available in both constructions, the Safestep ranges offer increased slip resistance for areas with increased slip risk due to contamination issues (R11) and intensive use and high contamination areas (R12).



Safestep R11 174922 | concrete

Description	Sheet safety vinyl	
Dimensions	Roll width 2m Roll length 20-27 lm	
Total thickness	ISO 1765	2.0mm
Thickness wear layer	EN-ISO 24340	0.7mm
Collection size	9 / 9	
Application	EN 10874	Class 34/43
Slip resistance	EN 13845 Annex C ESf	
	DIN 51130	R11 / R12
	TRRL Pendulum –	≥ 40 (R11)
	Wet test – slider 96	≥ 50 (R12)
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1
Slip resistance	EN 13893	DS: ≥0.30



Our recommended adhesive is 540 Eurosafe Special or 640 Eurostar Special.
Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product.
Please order a sample to see the full effect.

surestep® decibel




A genuine Health and Safety Executive compliant safety floor, Surestep Decibel offers sustainable R10 slip resistance underfoot, beautiful designs and a 17dB impact sound reduction.



Surestep Decibel 717122 | cool concrete + 718962 | whitewash oak

Description	Sheet safety vinyl	
Dimensions	Roll width 2/4m Roll length 20-27 lm	
Total thickness	ISO 1765	3.0mm
Thickness wear layer	EN-ISO 24340	0.7mm
Collection size	12	
Application	EN 10874	Class 34/42
Slip resistance	EN 13845 Annex C ESf	
	DIN 51130	R10
	TRRL Pendulum –	≥ 36
	Wet test – slider 96	≥ 36
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1
Slip resistance	EN 13893	DS: ≥0.30



surestep® digital print



Our Digitally Printed Step range takes safety flooring into a new design dimension. Still featuring all the product performance benefits of our standard Surestep ranges, Surestep Digital Print allows you to create custom safety flooring. Choose from our two stocked Ice Cream or Moon designs, or create your own design.

Description	Sheet safety vinyl	
Dimensions	Roll width 2m Roll length 20-27 Im	
Total thickness	ISO 1765	2.0mm
Thickness wear layer	EN-ISO 24340	0.7mm
Collection size	2 stocked, bespoke on request	
Application	EN 10874	Class 34/43
Slip resistance	EN 13845 Annex C	ESf
	DIN 51130	R10
	TRRL Pendulum – Wet test – slider 96	≥ 36
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1
Slip resistance	EN 13893	DS: ≥0.30



Surestep Digital Print 17992 | ice cream



17992 | ice cream



17982 | moon



Surestep Digital Print 17982 | moon



Surestep Digital Print 17982 | moon

SURESTEP CASE STUDIES



PROJECT:
The Fun Factory
at Brewers Fayre

LOCATIONS:
Various

DESIGNER: Brewers Fayre internal design team

FLOORING MATERIAL:
Surestep Wood 18882 | classic oak +
Flotex Vision bespoke design

See page 188 for the full Surestep Wood range.



PROJECT:
Naomi House

LOCATION:
Basingstoke

DESIGNER: Building Surveying & Project
Management Ltd

FLOORING MATERIAL:
Surestep Laguna 181822 | lagoon + 181262 | trout +
Marmoleum Real 3055 | fresco blue + Marmoleum
Striato 5221 | colourstream + Flotex Vision 000348 |
cobblestone + Allura Wood w60063 | waxed oak



PROJECT:
University of
Bedford The Hub

LOCATION:
Luton

DESIGNER: Facilities and Estates Department

FLOORING MATERIAL:
Safestep R11 174922 | concrete + Tessera
Alignment 208 | Nucleus + 209 celcius + 210 |
climate + Westbond Flex bespoke colourway

See page 190 for the full Safestep R11 range.

FORBO'S WETROOM SOLUTIONS

The popularity of the wetroom (watertight walk-in shower room) is growing and not just in hospitals and care homes, but also in student accommodation, sports centres and hotels. The continuously sealed floor and wall system stops moisture ingress and therefore prevents bacterial growth.

Easy to access, even for wheelchair users, hygienic and quick to clean (with no sharp corners or crevices for dirt and bacteria to collect), it's not surprising that this type of facility, which originated in Scandinavia, is becoming so popular.

Co-ordinated wall and safety floor surfaces

Our Safestep Aqua and Surestep Laguna ranges are perfect for wetroom applications. They were specifically developed for use in continuously wet areas, where water flows frequently and barefoot traffic is the standard; or where there is a combination of barefoot and footwear traffic.

Three colours in the Surestep Star range are also available in a barefoot construction. To complement these well established safety flooring options, we have introduced Onyx+, a range of stylishly co-ordinated vinyl wall coverings.

For installation, cleaning and maintenance advice, including which accessories to use when installing wetroom products, please visit www.forbo-flooring.com



Slips are amongst the most frequent accidents in the indoor environment. In our effort to make a positive contribution to the quality of indoor spaces our Step collection offers a wide variety of genuine safety flooring solutions. Many offer natural visuals such as wood and natural stone allowing customers to have the functionality of a true safety floor combined with the feeling of well-being which can be achieved through natural designs avoiding a 'cold' and institutional look and feel.


WETROOM COLLECTION AT A GLANCE

surestep® laguna surestep® star barefoot

This product combines barefoot and footwear slip resistance, for areas where both are likely and frequently will take place. Complying with the relevant norms for the application, Laguna is suitable for use in transition areas such as changing rooms and circulation areas. Three colours in the Surestep Star range are also available in a barefoot construction.

Wetroom areas

- Continuously wet areas, mainly barefoot but also footwear
- Changing rooms in combination with footwear
- Bathrooms in combination with footwear



safestep® aqua

This modern, organic design with a new and unique embossing shape is designed for barefoot (and soft soled shoes) areas.

A flexible product, available across 12 colours, can easily be installed to meet the specific requirements of the wetroom sector.

Showers, swimming pool areas

- Continuously wet areas, barefoot and soft shoes
- Walk in showers
- Hydrotherapy areas
- Indoor swimming pools



onyx +

To complement our well established safety flooring options for wetroom applications, we have introduced Onyx+, a range of stylishly co-ordinated vinyl wall coverings.

Showers, swimming pool areas

- Available in 2m wide rolls
- Suited to commercial applications in health centres, hospitals and care homes
- Can be installed horizontally where required





Innovation in wetroom flooring

Safestep Aqua and Surestep Laguna combine functionality with beautiful design. Both products are available in a fresh, contemporary palette suitable for all types of wetroom applications.

Surestep Laguna


This product combines barefoot and footwear slip resistance, for areas where both are likely and frequently will take place. Complying with the relevant norms for this application, Laguna is suitable for use in transition areas such as changing rooms and circulation areas. The subtle, soil hiding design is available in 15 colourways, offering a clean and fresh look. Suitable for wheelchair use.

3 items in the Surestep Star range are also available in a barefoot construction.

Description		Sheet safety vinyl
Dimensions	EN-ISO 24341	Roll width 2.0m Roll length 20-27 lm
Total thickness	ISO 1765	2.0mm
Thickness wear layer	EN-ISO 24340	0.7mm
Collection size		15
Application	EN 10874	Class 34/43
Slip resistance	EN 13845 Annex C	ESb/ESf
	DIN 51130	R10
	TRRL Pendulum – Wet test – slider 96	≥ 36
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1
Slip resistance	EN 13893	DS: ≥0.30



Surestep Laguna 181692 | mouse




Safestep Aqua

This modern, organic design with a new and unique embossing shape is designed for barefoot (and soft soled shoes) areas. A flexible product, available across 8 colours, Safestep Aqua can easily be installed to meet the specific requirements of the wetroom sector. The clean and modern collection meets the hygienic and aesthetic requirements of application areas such as bathrooms and swimming pool surrounds. Suitable for wheelchair use.

Description		Sheet safety vinyl
Dimensions	EN-ISO 24341	Roll width 2.0m Roll length 20-27 lm
Total thickness	ISO 1765	2.0mm
Thickness wear layer	EN-ISO 24340	0.7mm
Collection size		8 (Aqua) 3 (Barefoot)
Application	EN 10874	Class 34/43
Slip resistance	EN 13845 Annex C	ESb (Aqua) ESb/ESf (Barefoot)
	DIN 51130	R10
	TRRL Pendulum – Wet test – slider 55	≥ 36
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1
Slip resistance	EN 13893	DS: ≥0.30



Safestep Aqua 180232 | taupe + 180482 | griege



Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.



Onyx+ is a **durable vinyl wall covering** perfectly suited for commercial wetroom applications in health care facilities, nursing homes and care homes.

Onyx+ has been designed to complement our Step Safety flooring wetroom collection of Surestep Laguna, Safestep Aqua and Surestep Star Barefoot. The palette features a selection of neutral tones along with some vivid accent colours.



26501 light grey LRV 70	26520 graphite ivory LRV 75	
26500 ivory LRV 82	26511 grey LRV 63	26521 grey accent LRV 45
26524 graphite greige LRV 58	26504 greige LRV 59	26514 greige accent LRV 41
26508 soft almond LRV 62	26505 soft yellow LRV 65	26506 soft peach LRV 61
26517 soft blue LRV 64	26518 soft teal LRV 63	26507 soft lilac LRV 60
26547 blue accent LRV 28	26548 teal accent LRV 29	26537 lilac accent LRV 26

Description	Vinyl wall covering	
Dimensions	EN-ISO 24341	Roll width 2.0m Roll length 30 m
Total thickness	ISO 1765	0.92mm
Collection size	17	
CE	EN 14041	
Reaction to fire	EN 13501-1	B-s2,d0*

**Based on product glued to A2-s1.d0 paper-faced gypsum plasterboard.*
 For adhesive recommendations and installation guidance visit www.forbo-flooring.co.uk/wetroom. Full technical specifications are available at www.forbo-flooring.com
 Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.



PROTECTING YOUR TECHNOLOGY

Colorex is an advanced technical flooring system specifically designed to control static discharge in sensitive areas such as cleanrooms, operating theatres and the electronics industry. Not only does Colorex provide an advanced technical solution, it is also aesthetically pleasing, enhancing any commercial interior from industrial to healthcare establishments.

Providing peace of mind

Forbo Flooring Systems is an international market leader with a wealth of experience in providing ESD and cleanroom flooring through one of the most trusted brands on the market - Colorex. You can have peace of mind that Colorex complies to every standard and norm that is required today and likely to be required tomorrow.

Environmental credentials

We constantly strive to produce sustainable flooring solutions that create better environments across all application areas. At the same time we help take care of the natural environment through our commitment to sustainable development, responsible raw material procurement and manufacturing processes.

COLOREX SD	COLOREX EC	COLOREX PLUS EC	COLOREX PLUS R10	COLOREX PLUS BASIC
<p>Permanently dissipative Connection between tiles through conductive adhesive and connected to earth through copper strip. Also available in signal colours.</p> <p>Application areas Places where dissipative flooring is required: new build laboratories, cleanrooms, production sites (electronics, manufacturing, life sciences) and operating theatres.</p>	<p>Permanently conductive Connection between tiles through conductive adhesive and connected to earth through copper strip. Compliant to IEC 61340-4-5 with appropriate ESD shoes.</p> <p>Application areas Places where conductive flooring is required: ESD facilities, cleanrooms, pharmaceutical laboratories, production sites (electronics, manufacturing, life sciences) and operating theatres.</p>	<p>Permanently conductive Colorex plus EC is a heavy duty loose lay floor system. It is permanently conductive via the connection between tiles through the dovetail system and connected to earth with a copper strip. Colorex plus EC performs regardless the humidity level of the area. Compliant to IEC 61340-4-5 with appropriate ESD shoes.</p> <p>Application areas Renovation of ESD facilities, cleanrooms, pharmaceutical laboratories and production sites. Suitable when down time, damp floors or poor sub floors are an issue.</p>	<p>Antistatic Colorex plus R10 is a heavy duty loose lay floor system with a textured surface for enhanced slip resistance (R10). The surface structure improves safety when there is a risk of contamination of the floor for example through powder or water spillage.</p> <p>Application areas Places where slip resistance is required: production sites (electronics, manufacturing, life sciences).</p>	<p>Antistatic Colorex plus basic is a heavy duty loose lay floor system. Which provides excellent chemical resistance. The floor can also be repaired in case of heavy damages.</p> <p>Application areas Shops, stores, warehouses. Areas with high traffic needing daily intensive cleaning. Suitable when downtime, damp floors or poor sub floors are an issue.</p>

The benefits of Colorex

1. The technology assures a permanently conductive product guaranteeing optimal performance throughout the life of the product. Colorex® fully complies with all ESD standards.
2. The surface of Colorex® can be fully repaired extending the useful life of the product.
3. The low plasticizer content in Colorex® tile creates a unique dimensional stability and prevents shrinkage. The tiles can be perforated for air flow systems.
4. The low plasticizer content also ensures extremely low emissions and outgassing making Colorex® the right choice for cleanrooms. Colorex fully complies with all cleanroom standards including the Fraunhofer Institute.
5. The dense construction of Colorex® provides excellent resistance to heavy loads making it an ideal solution for commercial and industrial environments.
6. Colorex® is available in tile format, a prerequisite for raised access floors found in many commercial environments such as data centres and server rooms.
7. Option to add safety signs and guiding with Colorex signal and Colorex signal glow.

COLOREX COLLECTION AT A GLANCE

colorex® SD

Our Colorex SD tiles enable safe electrostatic discharge through the entire surface and mass of the tile. The conductive carbon black forms a dense network of tiny black veins. Colorex SD is permanently static dissipative.



colorex® EC

Colorex EC is an Ideal floor covering for laboratories, IT-rooms and cleanrooms. Colorex EC satisfies the strictest requirements for particle release behaviour, helping to reduce any threat of contamination. Reducing the generation of electrostatic charges is the main purpose of control measures in ESD protected areas (EPA).



colorex® plus EC

Colorex plus EC is Ideal for quick installation and renovation of sensitive areas such as laboratories, IT-rooms and cleanrooms. Colorex plus EC satisfies the strictest requirements for particle release behaviour, helping to reduce any threat of contamination.



colorex® plus R10

Colorex plus R10 is a heavy duty loose lay floor system with a textured surface for enhanced slip resistance (R10). The surface structure improves safety when there is a risk of contamination of the floor for example through powder or water spillage.



colorex® basic plus

Colorex Basic Plus is a loose lay floor system with Colorex on top without conductive properties. This ensures all the benefits of Colorex like high density, easy repair and stain resistance. But also combines the benefits of a heavy duty loose lay tile.




Hygiene and safety for sensitive healthcare areas

In sensitive healthcare areas such as operating theatres, intensive care units and diagnostic imaging facilities, flooring presents its own unique challenges. Not only must it comply with stringent hygiene regulations to help prevent hospital acquired infections, it must also demonstrate that it meets any necessary safety requirements. Most importantly, it must prevent any electrostatic discharges as these can cause malfunctions, or even failures, in highly sensitive medical equipment and devices and may endanger the health of patients and personnel.



SD 150265 | blue ridge SD 150222 | niagara



ESD flooring that is future proof

The right floor makes the difference Reducing the generation of electrostatic charges is the main purpose of control measures in ESD protected areas (EPA). In such areas such as electronics assembly, mechatronics and data centres the right floor covering plays a crucial role. Not only does it drain electrostatic charges from personnel and equipment, but it also reduces the generation of charges where they occur at the interface between the soles of shoes and the floor.

Industrial flooring for heavy duty areas


Suitable for the most demanding applications Industrial environments present their own flooring problems, particularly in areas with high wear and tear. Our Colorex high performance floor covering systems are designed for all industrial areas, including the most demanding of applications. Cut from a homogeneous, solid block of highly compressed material with a high vinyl content and a well balanced volume of mineral filler for optimum performance.



SD 150206 | moonstone SD 150263 | massif

Cleanroom flooring for the highest standards

In cleanroom environments in the pharmaceutical, life sciences and manufacturing industries, airborne particles can be a major source of contamination. Not only can they cause yield loss, the particles can also lead to corrosion and product degradation. Colorex EC satisfies the strictest requirements for particle release behavior and outgassing, helping to reduce any threat of contamination.




Surface can be fully repaired




Dense construction provides excellent resistance to heavy loads


Complies with all cleanroom standards




Unique dimensional stability and no shrinkage



Suitable for Raised Access Flooring and perforated air flow systems



Has permanent conductive properties which comply with all ESD standards



The low plasticizer content ensures extremely low emissions and outgassing.



everest
SD
EC
plus EC




etna
SD
EC




montblanc
SD
EC
plus EC
plus basic



moonstone
SD
EC




sahara
SD
EC
plus EC
plus basic



kiwi
SD
EC




pacific
SD
EC




adula
SD
EC
plus EC
plus basic




nebo
SD
EC



meru
SD
EC




twilight
SD
EC



niagara
SD
EC
plus
plus basic




quartz
SD
EC
plus EC
plus basic
plus R10




massif
SD
EC




assuan
SD
EC



pelion
SD
EC



blue ridge
SD
EC



montserrat
SD
EC

colorex® signal



Colorex signal glow under light



Colorex signal glow in the dark



glow
EC



sole
SD



amazonas
SD



fuego
SD

Colorex signal can be used as an additional, permanent safety measure to indicate emergency exits, to mark escape routes or indeed other spaces.

Colorex signal glow

The luminous quality of Colorex signal glow is determined by the length of exposure to, and the strength of, the light source. The effect is strongest in the first few minutes and remains visible up to 4 hours

after being exposed to light. Testing according to DIN 67510-1 2009-11 confirmed class A.

Colorex signal

The bright yellow, green and red colours of Colorex signal have been specifically chosen to aid in high-lighting potential danger or drawing attention to specific areas within a floor plan.

Technical specifications

Colorex® meets the requirements of EN ISO 10581 and ASTM 1700

		Colorex® SD	Colorex® EC	Colorex® Plus EC	Colorex® Plus Basic	Colorex® Plus R10
Binder content	EN ISO 10581	type 1	type 1	type 1	type 1	type 1
Total thickness	EN ISO 24346	2.0 mm / 3.0 mm*	2.0 mm / 3.0 mm*	10.3 mm	10.3 mm	10.3 mm
Commercial use	EN ISO 10874	34 very heavy	34 very heavy	34 very heavy	34 very heavy	34 very heavy
Light industrial use	EN ISO 10874	43 heavy	43 heavy	43 heavy	43 heavy	43 heavy
Tile size	EN ISO 24342	615x615 mm 615x1230 mm*	615x615 mm 615x1230 mm*	607x607 mm	607x607 mm	607x607 mm
Total weight	EN ISO 23997	3.2 kg/m²	3.2 kg/m²	12.0 kg/m²	12.0 kg/m²	12.0 kg/m²
Electrostatics (general requirements)	IEC 61340-5-1	Compliant	Compliant	Compliant	n.a.	n.a.
Electrical resistance	IEC 61340-4-1 ESD STM7.1	1 x 10 ⁶ ≤ R ≤ 10 ⁹ Ω	5 x 10 ⁴ ≤ R ≤ 10 ⁶ Ω	2.5 x 10 ⁴ ≤ R ≤ 10 ⁶ Ω	n.a.	n.a.
Electrical resistance in combination with ESD control footwear	IEC 61340-4-5 ESD STM97.1	R ≤ 1 x 10 ⁹ Ω	R ≤ 3.5 x 10 ⁷ Ω	R ≤ 3.5 x 10 ⁷ Ω	n.a.	n.a.
Body Voltage Generation, in combination with ESD control footwear Typical value	IEC 61340-4-5 ESD STM97.2	< 100 V ~ 40 V	< 100 V ~ 20 V	< 100 V ~ 20 V	< 2 kV n.a.	< 2 kV n.a.
Dimensional stability	EN ISO 23999	≤ 0.05%	≤ 0.05%	≤ 0.25%	≤ 0.25%	≤ 0.25%
Residual indentation Typical value	EN ISO 24343-1	≤ 0.10 mm ~ 0.02 mm	≤ 0.10 mm ~ 0.02 mm	≤ 0.10 mm ~ 0.05 mm	≤ 0.10 mm ~ 0.07 mm	≤ 0.10 mm ~ 0.07 mm
Resistance to loads		Powered pallet truck and forklifts: total weight up to 2.5 t with hard wheels and up to 5 t with air tyres. Static loads: 50 kg/cm² - dynamic loads: 90 kg/cm² (performance may vary, subject to local conditions)				
Castor chair continuous use	ISO 4918	pass	pass	pass	pass	pass
Impact sound reduction	EN ISO 140-8	2 dB	2 dB	12 dB	12 dB	12 dB
Light fastness	EN ISO 105-B02	≥ 6	≥ 6	≥ 6	≥ 6	≥ 6
Resistance to chemicals	EN ISO 26987	Excellent	Excellent	Excellent	Excellent	Excellent
Slip resistance	DIN 51130	R9	R9	R9	R9	R10
Bacteria resistance	ISO 846	Pass	Pass	Pass	Pass	n.a.
Thermal dilatation coefficient		0.07 mm/m°C	0.07 mm/m°C	0.07 mm/m°C	0.07 mm/m°C	0.07 mm/m°C
Outgassing	IDEMA M11-99	total < 1 µg/cm²	total < 1 µg/cm²	total < 2 µg/cm²	total < 2 µg/cm²	total < 2 µg/cm²
Indoor Air Emissions: TVOC after 28 days	EN 16516	≤ 0.025 mg/m³	≤ 0.025 mg/m³	≤ 0.025 mg/m³	≤ 0.025 mg/m³	≤ 0.025 mg/m³
Cleanroom particle emission	ISO 14644-1	ISO 4	ISO 2	ISO 2	ISO 4	ISO 6
Creating better environments						
Renewable electricity		Colorex SD and Colorex EC are manufactured using 100% electricity from renewable sources				
Recycled content		Colorex Plus contains up to 95% recycled content in the backing				
		EN 14041 CE 0201083-DuP-003	EN 14041 CE 0201083-DuP-003	EN 14041 CE 0201083-DuP-003	EN 14041 CE 0201076-DuP-003	EN 14041 CE 0201076-DuP-003
All Colorex® products meet the requirements of EN 14041						
Reaction to fire**	EN 13501-1	B _f -s1, G, CS	B _f -s1, G, CS	B _f -s1, L, CS	B _f -s1, L, CS	B _f -s1, L, CS
Slip resistance	EN 13893	µ ≥ 0.30	µ ≥ 0.30	µ ≥ 0.30	µ ≥ 0.30	µ ≥ 0.30
Thermal conductivity	EN 12524	0.25 W/(m·K)	0.25 W/(m·K)	0.25 W/(m·K)	0.25 W/(m·K)	0.25 W/(m·K)
Body voltage	EN 1815	≤ 2 kV	≤ 2 kV	≤ 2 kV	≤ 2 kV	≤ 2 kV
Electrical behaviour - static dissipative	EN 1081	≤ 1 x 10 ⁹ Ω	n.a.	n.a.	n.a.	n.a.
Electrical behaviour - conductive	EN 1081	n.a.	≤ 1 x 10 ⁶ Ω	≤ 1 x 10 ⁶ Ω	n.a.	n.a.

* Available on request

** Product also tested to ASTM. Fire ASTM E648: class 1, Smoke ASTM 662: pass

All Forbo Flooring Systems' sales organisations worldwide have a certified Quality Management System in accordance with ISO 9001. All Forbo Flooring Systems' manufacturing operations have a certified Environmental Management System in accordance with ISO 14001. The Life Cycle Assessment (LCA) of Forbo Flooring Systems' products is documented in individual Environmental Product Declarations (EPDs) which can be found on all of our websites.





5802 | natural oak

sportline

Every solution. One supplier.

Forbo Flooring Systems has been manufacturing and supplying floor coverings for education for more than a century. Our extensive range of floor coverings is used across a wide portfolio of educational establishments around the globe. Whether it's a nursery or a university, educational environments demand attractive, low maintenance, hardwearing, safe and sustainable flooring solutions. Durability and hygiene are especially vital in areas used by children and young adults. From entrance to exit, our integrated flooring portfolio can help select the ideal flooring solutions. Forbo also offers another area-elastic sports floor solution in Marmoleum Sports. The most sustainable sports flooring choice thanks to its natural ingredients. Forbo Eurocol can complete the installation of your sports floor with the application of game lining in all relevant colours.



5030 | green

sportline

The Sportline collection is a specially designed heterogeneous PVC flooring product for multipurpose sports and community halls. Sportline has a proven performance over many years with users worldwide, providing safety and good conditions for healthy sports environments.



208

sportline




The flexible and resilient floor covering has a 100% PVC top layer for reliable protection and the collection consists of the right colours and designs for various design projects. The most popular and higher intensity 6.0 mm is available from stock, but a 4.3 mm product is also available on request.



5804 | grey oak



7603 | light beech



5802 | natural oak



7601 | warm beech

	standard	classic
Description	Sheet vinyl	Sheet vinyl
Dimensions	Roll width 2m Roll length ≤ 25 m	Roll width 2m Roll length ≤ 18 m
Total thickness	EN ISO 24346 4.3mm	6.0mm
Thickness wear layer	EN ISO 24340 0.6mm	1.0mm
Collection size	12	12
Application	EN 10874 Class 33/42	Class 34/42
CE	EN 14041	
Reaction to fire	EN 13501-1 B _{fl} -s1, L, NCS	B _{fl} -s1, L, NCS
Slip resistance	EN 13893 μ ≥ 0.30	μ ≥ 0.30



2040 | light blue




4502 | grey



1070 | yellow



3040 | lime



2040 | light blue



0570 | orange



5030 | green



5040 | dark blue



2070 | red

CARPET TILES

Carpet tiles are renowned for their aesthetic styling and outstanding performance in the most demanding heavy traffic environments. Forbo Flooring offers a wide portfolio of carpet tiles of 50x50 cm with which stunning floor designs can be created.

tessera® inline



tessera® cloudscape



tessera® basis pro



tessera® create space 1



tessera® barcode



tessera® diffusion



TESSERA COLLECTION AT A GLANCE

tessera® struktur 1



tessera® struktur 2 linear



tessera® perspective



tessera® infused



tessera® layout | outline



tessera® contour



tessera® inline




Featuring a contemporary yet concise palette of 10 useable colourways, Inline combines soft geometric structure with intermittent linearity. The strong use of differential texture creates a natural, randomised appearance enabling monolithic installation. Tessera Inline can also be co-ordinated with Allura Flex loose lay LVTs or other Forbo products to add elements of colour, interest and value to a variety of interior schemes.



Tessera Inline 878 | steam (foreground)
+ Layout 2125 | tonic + 2112 | frosting




871 | syllabus LRV 25




878 | steam LRV 23




875 | banoffee LRV 20




877 | mallard LRV 23



879 | mellow LRV 25



873 | tungsten LRV 15



874 | tiramisu LRV 16



872 | onyx LRV 8




870 | molasses LRV 8



876 | celestial LRV 8

Description	tufted multi-height loop pile carpet tile
Dimensions	50cm x 50cm
Total thickness	6.5mm ± 10%
Pile height	3.9mm ± 0.5mm
Pile weight	605gsm ± 10%
Yarn	100% polyamide 6
Dye method	100% solution dyed
Collection size	10 (4m ² per box)
Application	EN 1307 Class 33
Impact sound reduction	ISO 10140-3 ΔL _w = 25 dB
Recycled content	63%
CE	EN 14041
Reaction to fire	EN 13501-1 B ₁ -s1




Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product.
Please order a sample to see the full effect.

tessera® cloudscape



Tessera Cloudscape loop pile carpet tiles offer a tonal progression of colours ranging from dark to very pale, ideal for a wide range of applications and LRV requirements. In today's crowded urban environment we often risk losing touch with nature. Our only connection being the sky above us. Tessera Cloudscape is inspired by the constantly changing vista of cloud formations and the rich spectrum of light and colour, which provide a bridge to the outside, helping us to reconnect. Cloudscape can be fitted non-directional or monolithic



Description	tufted multi-pile height loop pile carpet tile
Dimensions	50cm x 50cm
Total thickness	7.2mm
Pile height	4.4mm
Pile weight	665gsm ± 10%
Dye method	100% solution dyed
Collection size	16 (4m ² per box)
Application	EN 1307 Class 33
Impact sound reduction	ISO 10140-3 ΔL _w = 26 dB
Recycled content	58%
CE	EN 14041
Reaction to fire	EN 13501-1 B ₁ -s1



Tessera Cloudscape 3400 | nimbus grey

tessera® basis pro





Basis Pro is the universally selected flooring for a wide range of commercial applications where a reliable, hardwearing textile floor covering is required. Selected for its practical colour choice, availability and durability, Basis Pro is constructed with 100% solution dyed yarn, and is the trusted choice for installations in education, office and other commercial sectors.



4357 | mid grey + 4378 | malt




4123 | midnight blue, 4385 | neptune




Description	Tufted low loop pile carpet tile	
Dimensions	50cm x 50cm	
Total thickness	5.7mm	
Pile height	2.8mm	
Pile weight	540gsm	
Dye method	100% solution dyed	
Collection size	32 (5m ² per box)	
Application	EN 1307	Class 33
Impact sound reduction	ISO 10140-3	$\Delta L_{w} = 25$ dB
Recycled content	62%	
CE	EN 14041	
Reaction to fire	EN 13501-1	B ₁ -s1, G, NCS



An exceptionally flexible range of 18 commercial colourways, Create Space 1 is suitable for any commercial space, large or small. Styled for today's interiors, Create Space 1 lends itself to single colourway installations, feature area designs and bespoke creative schemes.




Description	Tufted low level loop pile carpet tile
Dimensions	50cm x 50cm
Total thickness	5.5mm ± 10%
Pile height	2.7mm ± 0.5mm
Pile weight	500gsm ± 10%
Yarn	100% ECONYL®/Altochroma regenerated polyamide 6
Dye method	100% solution dyed
Collection size	18 (5m ² per box)
Application	EN 1307 Class 33
Impact sound reduction	ISO 140-8 ΔL _w = 21 dB
Recycled content	71%
CE	EN 14041
Reaction to fire	EN 13501-1 B _{fl} -s1




Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product.
Please order a sample to see the full effect.



Barcode challenges the uniformity and rigidity of conventional linear low level loop pile tiles and, with its confident bands of contrasting colours in varying widths, delivers a more eclectic and exuberant look that is right on trend for today's commercial environments.




311 double yellow line	LRV 14	315 branch line	LRV 11
318 goal line	LRV 11	309 party line	LRV 7
Description		Tufted low level loop pile carpet tile	
Dimensions		50cm x 50cm	
Total thickness		6.0mm ± 10%	
Pile height		3.0mm ± 0.5mm	
Pile weight		580gsm ± 10%	
Yarn		100% Aquafil polyamide 6	
Dye method		100% solution dyed	
Collection size		18 (4m ² per box)	
Application		EN 1307 Class 33	
Impact sound reduction		ISO 140-8 ΔL _w = 22 dB	
Recycled content		65%	
CE		EN 14041	
Reaction to fire		EN 13501-1 B _{fl} -s1	





Diffusion reflects an evolution towards softer more organic geometry observed in nature. Inspired by crystalline structures, the fractal shapes fade in and out creating appealing contemporary floor spaces.




2003 | glacial flow LRV 27 2007 | perpetual motion LRV 34

2002 | paradigm shift LRV 19 2006 | passing place LRV 18


2001 | magnetic flux LRV 8 2005 | nomadic journey LRV 18

2000 | space quest LRV 4 2004 | pivotal moment LRV 8



2015 | arctic voyage LRV 14


Description	Tufted multi-height loop pile carpet tile	
Dimensions	50cm x 50cm	
Total thickness	6.5mm ± 10%	
Pile height	3.7mm ± 0.5mm	
Pile weight	570gsm ± 10%	
Yarn	Refresh™ by Universal Fibers™ 100% polyamide 6.6	
Dye method	100% solution dyed	
Collection size	10 (4m ² per box)	
Application	EN 1307	Class 33
Impact sound reduction	ISO 10140-3	ΔL _w = 22 dB
Recycled content	66%	
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1



Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product.
Please order a sample to see the full effect.



Every so often we need to pause, reflect, take a moment to focus on the important things. We need to find time to re-establish our balance and appreciate the value and integrity of a simpler, less cluttered existence. In Tessera Struktur 1, we find a familiar sense of wellbeing and equilibrium.



3700 | måne LRV 19




3703 | grå LRV 11



3704 | malm LRV 11



3707 | järn LRV 8



3706 | svart LRV 7



Tessera Struktur1 3707 | järn



3702 | korn LRV 25



3705 | kaffe LRV 19



3701 | sten LRV 17



3708 | brun LRV 8




tessera® struktur 2 linear



Description	Microtuft carpet tile
Dimensions	50cm x 50cm
Total thickness	5.1mm ± 10%
Pile height	1mm ± 15% - 10%
Pile weight	350gsm ± 10%
Pile composition	100% polyamide 6
Dye method	100% solution dyed
Collection size	18 (5m ² per box)
Application	EN 1307 Class 33
Impact sound reduction	ISO 10140-3 ΔL _w = 17 dB
Recycled content	65%
CE	EN 14041
Reaction to fire	EN 13501-1 C _{fl} -s1, G, NCS

Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product.
Please order a sample to see the full effect.



Tessera Struktur1 3714 | grön



3709 | gul

LRV 27



3711 | mossa

LRV 19



3710 | rosa

LRV 21



3714 | grön

LRV 8



3712 | flamma

LRV 20



3717 | påfågel

LRV 6



3715 | rost

LRV 9



3716 | blå

LRV 6



3713 | lila

LRV 10




Tessera Struktur2 4405 | järn + malm



4400 | grå + måne

LRV 17



4401 | järn + grå

LRV 8



4402 | svart + järn

LRV 5



Tessera Struktur2 4403 | kaffe + korn

Description	Microtuft carpet tile
Dimensions	50cm x 50cm
Total thickness	5.1mm
Pile height	1mm
Pile weight	350gsm
Pile composition	100% polyamide 6
Dye method	100% solution dyed
Collection size	6
Impact sound reduction	ISO 10140-3 $\Delta L_W = 17$ dB
Recycled content	65%
CE	EN 14041
Reaction to fire	EN 13501-1 B ₁ -s1, G, NCS

Full technical specifications are available at www.forbo-flooring.com
 Please note: Digital representations may vary from the actual product.
 Please order a sample to see the full effect.


A patterned cut & loop carpet tile, creating a luxurious, opulent surface texture.
 Perspective creates a timeless surface visual adding warmth and subtle interest to any interior space.




4403 | kaffe + korn LRV 25



4404 | malm + kaffe LRV 17




4405 | j arm + malm LRV 9




3901 | esprit LRV 14


Description	Tufted cut and loop pile carpet tile
Dimensions	50cm x 50cm
Total thickness	6.1mm
Pile height	3.0mm
Pile weight	670gsm
Yarn	Refresh™ by Universal Fibers™ Nylon 66 and Nylon 6 with 30% recycled content
Dye method	100% solution dyed
Collection size	14 (4m ² per box)
Application	EN 1307 Class 33
Impact sound reduction	ISO 10140-3 $\Delta L_W = 25$ dB
Recycled content	65%
CE	EN 14041
Reaction to fire	EN 13501-1 B ₁ -s1, G, NCS




3902 | fantasy LRV 2



3904 | mirage LRV 15



3905 | ethereal LRV 16




3909 | aura LRV 12



3908 | vivacious LRV 6




Tessera Perspective 3906 | lyrical, 3901 | esprit, 3910 | rhapsody



3910 | rhapsody LRV 4




3913 | iridescent LRV 3



3912 | mystique LRV 4



3900 | sensory LRV 9




3906 | lyrical LRV 8



3907 | melodious LRV 11



3911 | zestful LRV 8



3903 | illusion LRV 5

Full technical specifications are available at www.forbo-flooring.com
 Please note: Digital representations may vary from the actual product.
 Please order a sample to see the full effect.


tessera® infused




Inspired by the elements and designed to work effortlessly within commercial interiors, Tessera Infused is available in 12 colourways which blend easily with interior schemes as well as other ranges from the Tessera portfolio.



Tessera Infused 4504 | linen ruffle



4500 | magic mood LRV 15




4501 | morning cloud LRV 19



4503 | enduring storm LRV 8



4504 | linen ruffle LRV 25




4506 | coffee cream LRV 13




4505 | coral dream LRV 25




4507 | pickled spice LRV 14



4502 | noir flame LRV 8




4510 | wistful walk LRV 14



4509 | silver feather LRV 20



4508 | whimsy wood LRV 21



4511 | idyllic air LRV 8

Description	Tufted multi-pile height loop carpet tile	
Dimensions	50cm x 50cm	
Total thickness	6.7mm	
Pile height	3.6mm	
Pile weight	720gsm	
Yarn	Refresh™ by Universal Fibers™ Nylon 66 and Nylon 6 with 30% recycled content	
Dye method	100% solution dyed	
Collection size	12	
Application	EN 1307	Class 33
Impact sound reduction	ISO 10140-3	$\Delta L_w = 26$ dB
Recycled content	60%	
CE	EN 14041	
Reaction to fire	EN 13501-1	B ₁ -s1, G, NCS



Infused 4510 | wistful walk

tessera® layout | outline



Following on from the success of our Tessera Layout and Outline carpet tile collection, the Layout and Outline planks range also provides a contemporary and co-ordinated colour palette with the added benefit of a plank format.

We've introduced a total of 18 carpet tiles in a new 100cm x 25cm plank format, which provides the maximum flexibility for creating stunning floor designs. Available in 14 sophisticated and bright colourways, Layout planks are offered in a very versatile palette.

A contemporary two-colour striped pattern, Outline planks combine flexibility with design over 4 engaging colourways.

Contains 63% recycled content by weight.



Layout 2104PL | alloy LRV 9



Layout 2112PL | frosting LRV 28



Layout 2107PL | brulee LRV 7



Layout 2122PL | drench LRV 7



Layout 2120PL | apple LRV 20



Layout 2123PL | candy LRV 23




Tessera Layout 2100PL | mono + 2104PL | alloy + 2112PL | frosting + 2120PL | apple + Outline 3100PL | plasmatron



Tessera Layout 2119PL | maraschino + 2100PL | mono + 2104PL | alloy + Tessera Outline 3100PL | plasmatron



Layout 2100PL | mono LRV 4



Layout 2108PL | calcium LRV 13




Layout 2103PL | balsamic LRV 13




Layout 2118PL | oceanis LRV 5




Layout 2129PL | menthe LRV 16




Layout 2131PL | mango LRV 18



Tessera Layout 2112PL frosting + 2130PL icepop + 2118PL oceanis



Outline 3100PL | plasmatron LRV 6




Outline 3102PL | soda LRV 21



Outline 3101PL | colabottle LRV 9



Outline 3107PL | bubblegum LRV 6




Layout 2130PL | icepop LRV 12



Layout 2119PL | maraschino LRV 7

Description	Tufted low loop pile carpet tile
Dimensions	100cm x 25cm
Total thickness	5.8mm ± 10%
Pile height	2.9mm ± 0.5mm
Pile weight	580gsm ± 10%
Yarn	100% polyamide 6
Dye method	100% solution dyed
Collection size	Layout 14 Outline 4 4.5m ² per box
Application	EN 1307 Class 33
Impact sound reduction	ISO 10140-3 $\Delta L_w = 27$ dB
Recycled content	63%
CE	EN 14041
Reaction to fire	EN 13501-1 B _{fl} -s1



Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product.
Please order a sample to see the full effect.

tessera® contour



Influenced by lines in architecture and relieved by softer more natural elements, Contour offers a geometric framework across a palette of 13 naturally inspired colourways.

The cut and loop pile construction provides the gentle, striated form and with 68% recycled content, Contour also offers a low environmental impact. The yarn is solution dyed Refresh™ by Universal fibres ensuring premium quality and improved cleanability and longevity.



Tessera Contour 1908 | classic cloud



1904 | lava core LRV 2




Non-directional Monolithic



Tessellated Half drop




Description	Tufted multi-height cut and loop pile carpet tile
Dimensions	50cm x 50cm
Total thickness	6.3mm ± 10%
Pile height	3.5mm ± 0.5mm
Pile weight (after shearing)	580gsm ± 10%
Yarn	Refresh™ by Universal Fibers™ 100% polyamide 6.6
Dye method	100% solution dyed
Collection size	13 (4m ² per box)
Application	EN 1307 Class 33
Impact sound reduction	ISO 10140-3 ΔL _w = 23 dB
Recycled content	68%
CE	EN 14041
Reaction to fire	EN 13501-1 B _{fl} -s1



Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product.
Please order a sample to see the full effect.

TESSERA CASE STUDIES



PROJECT:
New Bridewell
Student
Accommodation

LOCATION:
Bristol

DESIGNER: Jasper Sanders and Partners

FLOORING MATERIAL:
Tessera Layout and Outline 2117 | surf +
2125 | tonic + 2015 | aniseed + 2128 | custard

See page 226 for the full Layout & Outline range



PROJECT:
Zebra
Technologies

LOCATION:
Bourne End,
Buckinghamshire

DESIGNER: Oktra

FLOORING MATERIAL: Tessera Layout and
Outline 2117 | surf + 2125 | tonic + Tessera
Synergy Clarity 7910115 | Peacock + Allura Flex
0.55 1992 | weathered oak + 1987 | charcoal solid
oak

See page 226 for the full Layout & Outline range
and page 99 for the Allura Flex range

needlefelt

Ultimate functionality

The high quality of Forbo Flooring Needlefelt is based on over 40 years' experience in the manufacture and supply of this hard-wearing flooring. It is available in 3 qualities designed to meet different requirements.



Benefits of Forbo Needlefelt:

Extremely robust

- Hard-wearing performance approved in class 33 in accordance with EN 1307.
- GUT seal of approval for "contaminant-tested textile floor coverings."
- Withstands heavy use such as castor chairs in offices or rolling suitcases in airports.

Sustainable

- Our needlefelt backing consists of 100% recycled polyester.
- The high production quality ensures a long lifespan and therefore do not need regular replacement.
- Our high quality polyamide fibres are designed to provide extra protection from dirt and soiling, saving on cleaning costs and contributes to a sustainable building.

Acoustic

- Noise reduction levels between 20dB and 22dB which means reduced ambient noise, ideal for use in places which require a tranquil atmosphere, such as offices.

Electrical resistance

- Enhanced electrical dissipative properties ($\leq 10^7$ Ohm (Ω)) as standard on Forte Sheet and Markant Sheet, giving options suitable for areas sensitive to static electricity such as computer and server rooms.

NEEDLEFELT COLLECTION AT A GLANCE

akzent

The introduction needlefelt sheet quality, Akzent is available in a blend of 80% polyamide and 20% polypropylene fibres, and is designed as a practical, value solution for hard wearing commercial flooring.



markant

A high-quality, coarse-texture needlefelt flooring made of 100% polyamide fibres, equipped with all the characteristics required for hard-wearing performance in frequently used places.



markant graphic city

A modern print "box" design using Markant Sheet as the basis, Markant Graphic City provides an easy and affordable solution to adding design interest to commercial spaces.



forte tile

Combining the ease of handling, optimized installation and maintenance benefits of modular flooring, with all of the durability and economic benefits of a needlefelt floor, Forte Tile is available as standard in a select range of 12 colour options.



forte

Our premium needlefelt flooring range, offering the maximum feeling of comfort in our heaviest weights, comes in sheet and modular (Tile) options. The very dense texture, with more than 3 million needle punches per m², guarantees a combination of attractive looks and hard-wearing performance for use in highly-frequented areas. Forte Sheet is available in all 25 colours, a palette of commercial neutral colours and trend led highlights.



akzent



The introduction needlefelt sheet quality, Akzent is available in a blend of 80% polyamide and 20% polypropylene fibres, and is designed as a practical, value solution for hard wearing commercial flooring.



Roll width	200 cm
Roll length	± 30 meter
Total thickness	5.0mm
Total weight	1000 gsm
Pile composition	100% polyamide
Pile weight	500gsm
Collection size	13
Application	EN 1307 Class 33
Impact sound reduction	ISO 10140-3 $\Delta L_w = 20$ dB
Recycled content	50%
CE	EN 14041:2004
Reaction to fire	EN 13501-1 B ₁ -s1, G, NCS

Needlefelt Akzent 10710 | quartz



markant



A high-quality, coarse-texture needlefelt flooring made of 100% polyamide fibres, equipped with all the characteristics required for hard-wearing performance in frequently used places.



Roll width	200 cm
Roll length	± 30 meter
Total thickness	5.5mm
Total weight	1200 gsm
Pile composition	100% polyamide
Pile weight	600gsm
Collection size	16
Application	EN 1307 Class 33
Impact sound reduction	ISO 10140-3 $\Delta L_w = 21$ dB
Recycled content	50%
CE	EN 14041:2004
Reaction to fire	EN 13501-1 B ₁ -s1, G, NCS

Needlefelt Markant 11113 | taupe, 11119 | jet



markant graphic city




A modern print "box" design using Markant Sheet as the basis, Markant Graphic City provides an easy and affordable solution to adding design interest to commercial spaces.



Markant Graphic City 11603 | Central Park

Roll width	200 cm	
Roll length	± 30 meter	
Total thickness	5.5mm	
Total weight	1200 gsm	
Pile composition	100% polyamide	
Pile weight	500gsm	
Collection size	4	
Application	EN 1307	Class 33
Impact sound reduction	ISO 10140-3	$\Delta L_w = 21$ dB
Recycled content	50%	
CE	EN 14041:2004	
Reaction to fire	EN 13501-1	B ₁ -s1, G, NCS



11619 | 5th Avenue LRV 2 11609 | Broadway LRV 4 11603 | Central Park LRV 3 11607 | Times Square LRV 4

forte tile



Combining the ease of handling, optimized installation and maintenance benefits of modular flooring, with all of the durability and economic benefits of a needlefelt floor, Forte Tile is available as standard in a select range of 12 colour options.



Needlefelt Forte Tile 96000T | smoke, 96017T | marine, 96047T | Pacific

Dimensions	50cm x 50cm	
Packaging 1 box	16pcs, 4sqm	
Total thickness	6.2mm	
Total weight	1350gsm	
Pile weight	400gsm	
Dye method	100% polyamide	
Collection size	12	
Application	EN 1307	Class 33
Impact sound reduction	ISO 10140-3	$\Delta L_w = 22$ dB
Recycled content	60%	
CE	EN 14041	
Reaction to fire	EN 13501-1	B ₁ -s1, G, NCS



96000T | smoke LRV 16 96010T | quartz LRV 21 96027T | storm LRV 8 96008T | field LRV 16
 96009T | charcoal LRV 7 96002T | granite LRV 14 96017T | marine LRV 8 96057T | lagoon LRV 4
 96019T | jet LRV 3 96012T | nickel LRV 9 96047T | Pacific LRV 4 96036T | rouge LRV 6



Our premium needlefelt flooring range, offering the maximum feeling of comfort in our heaviest weights, comes in sheet and modular (Tile) options. The very dense texture, with more than 3 million needle punches per m², guarantees a combination of attractive looks and hard-wearing performance for use in highly-frequented areas. Forte Sheet is available in all 25 colours, a palette of commercial neutral colours and trend led highlights.



	sheet	tile
Roll width	200 cm	-
Roll length	± 30 meter	-
Dimensions	-	50cm x 50cm
Packaging 1 box	-	16pcs, 4sqm
Total thickness	6.5mm	6.2mm
Total weight	1600 gsm	1350gsm
Pile composition	100% polyamide	100% polyamide
Pile weight	750gsm	400gsm
Collection size	25	12
Application	EN 1307	Class 33
Impact sound reduction	ISO 10140-3	ΔL _w = 22 dB
Recycled content	50%	60%
CE	EN 14041:2004	
Reaction to fire	EN 13501-1	B _{f1} -s1, G, NCS


Needlefelt Forte 96057 | lagoon, 96037 | Atlantic, 96001 | silver



* Also available in tiles
236 Carpet Tiles




Needlefelt Forte 96008 | field, 96018 | forest



* Also available in tiles
Carpet Tiles 237

The Showtime collection has been tailored to meet the demanding needs of the hotel and leisure sector. The specially developed needlefelt construction combines performance, comfort, ease of maintenance and improved acoustic performance, whilst the colour palette with co-ordinating print options complement today's hospitality interiors. All 17 colours and 20 co-ordinating graphic options in 5 designs are readily available for immediate installation, and all are made with over 50% recycled content for reduced environmental impact.



Made using polyamide fibres, 17 options in neutrals and tonal accents make up the unique Showtime colour palette; designed to harmonise with today's hospitality interior schemes.



Roll width	200 cm	
Roll length	± 40 meter	
Total thickness	4.9mm	
Total weight	1150 gsm	
Pile composition	100% polyamide	
Pile weight	280gsm	
Collection size	17	
Application	EN 1307	Class 32
Impact sound reduction	ISO 10140-3	$\Delta L_w = 20$ dB
Recycled content	50%	
CE	EN 14041:2004	
Reaction to fire	EN 13501-1	C _s -s1, G, NCS




900268 | celadon LRV 16



900261 | platinum LRV 22



900263 | sable LRV 21



900266 | rose LRV 16



900288 | jade LRV 6



900262 | slate LRV 11




900273 | sandstone LRV 13




900265 | sunshine LRV 25



900278 | pastoral LRV 5



900272 | steel LRV 5



900274 | espresso LRV 7




900276 | terracotta LRV 8



900267 | nautical LRV 4



900269 | carbon LRV 3



900279 | noir LRV 2



900286 | ruby LRV 5



900277 | indigo LRV 2



5 tonal graphics, designed to complement hospitality styles, make up Showtime Graphic, and each are readily available in a selection of Showtime base colours, making 20 graphic options available for immediate installation.




Showtime graphic ecosystem 07 936288 | jade, 936268 | celadon



ecosystem 07 - 936273 | sandstone

LRV 8




loft - 946261 | platinum

LRV 15



ecosystem 07 - 936261 | platinum

LRV 12



loft - 946262 | slate

LRV 7




ecosystem 07 - 936268 | celadon

LRV 10



loft - 946272 | steel

LRV 3



ecosystem 07 - 936288 | jade

LRV 4



loft - 946267 | nautical

LRV 3



loft - 946273 | sandstone

LRV 5



loft - 946286 | ruby

LRV 4

Roll width	200 cm
Roll length	± 40 meter
Total thickness	4.9mm
Total weight	1150 gsm
Pile composition	100% polyamide
Pile weight	280gsm
Collection size	20
Application	EN 1307 Class 32
Impact sound reduction	ISO 10140-3 $\Delta L_w = 20$ dB
Recycled content	50%
CE	EN 14041:2004
Reaction to fire	EN 13501-1 C _{fl} -s1, G, NCS



wonderlab 07 - 944261 | platinum

LRV 12



wonderlab 07 - 944268 | celadon

LRV 6



wonderlab 06 - 943272 | steel

LRV 4



wonderlab 06 - 943288 | jade

LRV 5



wonderlab 06 - 943267 | nautical

LRV 3




wonderlab 06 - 943268 | ruby

LRV 4



Showtime graphic wonderlab 06 943272 | steel



heritage 05 - 930262 | slate

LRV 8



heritage 05 - 930288 | jade

LRV 5



heritage 05 - 930267 | nautical

LRV 3



heritage 05 - 930286 | ruby

LRV 4

FLOCKED FLOORING IN SHEET, TILE AND PLANK

Flotex is a floor covering that looks and feels like a carpet without any of the drawbacks of a textile floor covering. It has a smooth, velour like surface that is comfortable to walk on and warm underfoot, with excellent slip resistant and acoustic properties.

flotex® colour

Choice is about possibilities, and choice in design starts with colour. Colour can communicate a message without words, it evokes emotions, creates associations and has the power to effect the whole mood and feel of an environment. Colour is personal and conveys our feelings and values, it is a fundamental part of our freedom to choose.



flotex® naturals

This special range of digitally printed Flotex delivers the appearance of a real wood floor but with improved acoustics and reduced maintenance costs.



flotex® stratus

The variety of installation methods available for Stratus opens up a huge number of flooring design options and, when used alongside colours from the contemporary Cirrus design, the creative options become almost infinite.



FLOTEX COLLECTION AT A GLANCE

flotex® cirrus

The Cirrus design is ideal for large scale installations and also offers a wide choice of fitting methods for additional flexibility. When used in combination with the Stratus design, colour coordinated solutions can easily be created.



flotex® cityscape

The embossed lines in the Flotex Cityscape collection create an intriguing design that changes in the light from whatever angle you observe the floor. Inspired by the lines and intersections of the urban landscape the collection captures the reflection and the rhythm of the windows of the city's skyscrapers or the pattern of the street beneath them.



flotex® planks

The performance attributes of Flotex along with the design versatility of the Plank collection, make these modular floor coverings ideal for use in workspaces as well as high traffic areas such as call centres, hotels and transport hubs.



Flotex, more than any of our products, fulfils our ambition to contribute to creating better indoor environments by committing to the health and well-being of all individuals living and working in indoor spaces. Flotex achieves this through excellent hygiene and sound absorbing qualities, phthalate-free products, the certification by Allergy UK for the positive effects it has on allergy sufferers, and a wide range of stimulating designs and sympathetic colours which can create inspiring interiors.



flotex® THE HIGH-TECH TEXTILE



UP TO 22 dB
IMPACT SOUND
REDUCTION AND 0.25 dB
IN ROOM SOUND RATING



EXCELLENT
SLIP RESISTANCE
WHEN WET



WASHABLE and
WATERPROOF



MECHANICAL
WET CLEANING
POSSIBLE



THE ONLY TEXTILE
FLOORING WITH
APPROVAL FROM THE
BRITISH ALLERGY
FOUNDATION

STRAIGHT NYLON 6.6 FIBRES (FLOCK)

capture fine dust and
allergens which are
easily released when
vacuumed


PHTHALATE
FREE

LOW ROLL RESISTANCE


Up to
80 million
fibres per m²
ensures high
durability

up to 52%
recycled
content

Flotex sheet




Flotex tile and plank



- 1 Nylon 6.6 pile
- 2 Flock adhesive
- 3 Nonwoven fibreglass
- 4 Closed cell PVC foam
- 5 Fibreglass net reinforcement
- 6 Closed cell PVC foam
- 7 Compact PVC layer
- 8 Compact PVC layer
- 9 Recycled PVC Backing

Safe and
ultra low
emissions

carpet flotex®
Vacuuming removes
almost **DOUBLE** the
ALLERGENS compared to
conventional carpet



HYGIENIC

**30% MORE SOIL
RELEASED THAN CARPET**


FLOTEX

Up to 80 million straight nylon fibres per m² are electrostatically flocked into the backing. The unique structure ensures dirt and allergens can be released when vacuumed.



CARPET

Loop and cut pile carpets have a structure that makes removing allergens and fine dust very difficult in comparison to the smooth, straight and almost upright fibres in Flotex flocked flooring.




flotex® colour

metro | penang | calgary | canyon

Four versatile and fresh designs make up the Flotex Colour collection: Metro, Calgary, Penang and Canyon. Together they offer a range of 90 unique colourways. All are available in sheet and tile, with 30 references available in plank.

The range is also complemented by 22 borders.



Flotex, more than any of our products, fulfils our ambition to contribute to creating better indoor environments by committing to the health and well-being of all individuals living and working in indoor spaces. Flotex achieves this through excellent hygiene and sound absorbing qualities, phthalate-free products, the certification by Allergy UK for the positive effects it has on allergy sufferers, and a wide range of stimulating designs and sympathetic colours which can create inspiring interiors.





metro

Metro is a versatile semi-plain floor design which covers a wide and modern colour bank. The understated pattern conveys texture without definite form, creating an authentic feel that is unique to Flotex flooring



penang

Flotex Penang offers a stunning look for any modern environment. It creates a subtle linear effect and comes in a range of rich modern shades





calgary

Flotex Calgary offers a wide colour choice in a soft, natural design that works well in larger areas. The pattern can be easily combined with complementary Flotex or resilient ranges and is the perfect choice for application areas that require a muted ambience.



canyon

Flotex Canyon is a heavily grained semi-plain inspired by natural earth and rock. It has a distinctive strong texture with a medium contrast.



Description	Flocked flooring
Dimensions	Sheet: Roll width 2m Roll length ≤ 30m Tile: 50cm x 50cm (3m ² per box)
Total thickness	ISO 1765 Sheet: 4.3mm Tile: 5.0mm
Slip resistance	Pendulum test Wet – low slip risk
Application	EN 1307 Class 33 heavy
Impact sound reduction	EN ISO 717-2 Sheet: ΔLw ≥ 20 dB Tile: ΔLw ≥ 19 dB
CE	EN 14041
Reaction to fire	EN 13501-1 B _f -s1
Slip resistance	EN 13893 DS: ≥0.30
Body voltage	EN ISO 10965 < 2 kV




Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.

Usage classification

- Superior appearance rating
- Good appearance rating
- Moderate appearance rating

s = Sheet
t = Tile
p = Planks


* Metro Grey t746006 is a stocked item
The AcousticPlus can be ordered for all tiles as a special order as of 700m² per colour.



Description	Flocked flooring
Dimensions	Sheet: Roll width 2m Roll length ≤ 30m Tile: 50cm x 50cm (3m ² per box)
Total thickness	ISO 1765 Sheet: 4.3mm Tile: 5.0mm
Slip resistance	Pendulum test Wet – low slip risk
Application	EN 1307 Class 33 heavy
Impact sound reduction	EN ISO 717-2 Sheet: ΔLw ≥ 20 dB Tile: ΔLw ≥ 19 dB
CE	EN 14041
Reaction to fire	EN 13501-1 B _{fl} -s1
Slip resistance	EN 13893 DS: ≥0.30
Body voltage	EN ISO 10965 < 2 kV



Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.




Usage classification

- Superior appearance rating
- Good appearance rating
- Moderate appearance rating


s = Sheet
t = Tile
p = Planks

flotex® colour

metro | penang | calgary | canyon




Description	Flocked flooring
Dimensions	Sheet: Roll width 2m Roll length ≤ 30m Tile: 50cm x 50cm (3m ² per box)
Total thickness	ISO 1765 Sheet: 4.3mm Tile: 5.0mm
Slip resistance	Pendulum test Wet – low slip risk
Application	EN 1307 Class 33 heavy
Impact sound reduction	EN ISO 717-2 Sheet: ΔLw ≥ 20 dB Tile: ΔLw ≥ 19 dB
CE	EN 14041
Reaction to fire	EN 13501-1 B ₁ -s1
Slip resistance	EN 13893 DS: ≥0.30
Body voltage	EN ISO 10965 < 2 kV



Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.

flotex® colour

metro | penang | calgary | canyon



Usage classification

- Superior appearance rating
- Good appearance rating
- Moderate appearance rating

s = Sheet
t = Tile
p = Planks

flotex® colour

embossing highlight



Would you like to have areas of your floor that stand out? Think about the option to use tiles with embossing. This way you can play with the floor design and have areas or individual tiles be different from the rest. The below 12 items can be chosen with either the organic or glass embossing. All embossed Flotex has the same performance characteristics as any other Flotex.





Emboss glass
Inspired by glass this pattern is a random geometric that can be used to add a striking accent to an installation.



Emboss organic
This is a versatile pattern that gives a subtle effect bringing direction to the tiles without being too formal.

Colour range




metro | pebble | t546011
metro | berry | t546017 | tg546517



Our renewed Flotex Vision Naturals range enables you to create the aesthetic of a real wood or ceramics floor, whilst maintaining the warmth, acoustics and comfort that a carpet offers.

Our state of the art digital printing technique achieves high quality, true to life visuals of wood and ceramic textures.



010076 | limed wood * 010078 | shaded oak * 010058 | titanium oak *




010073 | heritage plank * 010074 | shadow plank * 010077 | smoked walnut * 010075 | warm oak * 010039 | European white wood * 010036 | American oak *



010038 | white oak * 010034 | pear wood 010042 | steamed beech * 010041 | smoked beech * 010035 | distressed oak * 010002 | reclaimed pine



010056 | stained pine 010020 | dark elm 010003 | mixed wood antique




010012 | light elm 010057 | cedar 010013 | mixed wood rose



010040 | antique pine * 010033 | English oak 010037 | blackened oak *

Usage classification
 Superior appearance rating Good appearance rating Moderate appearance rating

Full technical specifications are available at www.forbo-flooring.com
 Please note: Digital representations may vary from the actual product.
 Please order a sample to see the full effect.



010079 | hungarian point grey *



010071 | summer chevron * 010080 | hungarian point *



010021 | reclaimed oak 010014 | teak 010031 | anthracite wood 010018 | linear walnut



010072 | autumn chevron * 010055 | chestnut * 010032 | oak herringbone 010017 | cork amber 010046 | China black



010051 | lava stone 010052 | welsh slate 010008 | dark slate 010023 | grey slate 010049 | charcoal glaze 010044 | quarry tile



010045 | farmhouse tile 010029 | limestone slate 010048 | Roman spa



010050 | salt glaze 010047 | limestone pavement 010043 | cornerstone

Description	Flocked flooring
Dimensions	Roll width 2m Roll length ≤ 30m
Total thickness	ISO 1765 4.3mm
Slip resistance	Pendulum test Wet – low slip risk
Collection size	48
Application	EN 1307 Class 33 heavy
Impact sound reduction	EN ISO 717-2 ΔLw = 20 dB
CE	EN 14041
Reaction to fire	EN 13501-1 B _{fl} -s1
Slip resistance	EN 13893 DS: ≥0.30
Body voltage	EN ISO 10965 < 2 kV



flotex® stratus

The variety of installation methods available for Stratus opens up a huge number of flooring design options and, when used alongside colours from the contemporary Cirrus design, the creative options become almost infinite.



flotex® cirrus

The Cirrus design is ideal for large scale installations and also offers a wide choice of fitting methods for additional flexibility. When used in combination with the Stratus design, colour coordinated solutions can easily be created.



flotex® cityscape

The embossed lines in the Flotex Cityscape collection create an intriguing design that changes in the light from whatever angle you observe the floor. Inspired by the lines and intersections of the urban landscape the collection captures the reflection and the rhythm of the windows of the city's sky scrapers or the pattern of the street beneath them.



Flotex, more than any of our products, fulfils our ambition to contribute to creating better indoor environments by committing to the health and well-being of all individuals living and working in indoor spaces. Flotex achieves this through excellent hygiene and sound absorbing qualities, phthalate-free products, the certification by Allergy UK for the positive effects it has on allergy sufferers, and a wide range of stimulating designs and sympathetic colours which can create inspiring interiors.



The Flotex Cirrus & Stratus collection is made up of two coordinating designs in a variety of colours to enable complete freedom of expression - create connections, highlights and transitions that will enhance any style of scheme. Used separately or in combination, this modular tile collection is well suited to office environments that have raised access floors. Flotex also has excellent acoustic properties of up to 22dB and is the only textile floor covering to receive the prestigious Allergy UK Seal of Approval™, helping to improve indoor air quality and creating better environments, in which to live, learn, work and play.



flotex® stratus


flotex® cirrus




t540005 | stratus sapphire LRV 21



t570005 | cirrus sapphire LRV 14



t540008 | stratus onyx LRV 10



t570008 | cirrus onyx LRV 11



t540014 | stratus eclipse LRV 10



t570014 | cirrus eclipse LRV 11



t540015 | stratus storm LRV 10



t570015 | cirrus storm LRV



Stratus t540008 | onyx
Cirrus t570008 | onyx


Description	Flocked flooring	
Dimensions	Tile: 50cm x 50cm	
Total thickness	ISO 1765	5.0 mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	16	
Application	EN 1307	Class 33 heavy
Impact sound reduction	EN ISO 717-2	$\Delta L_w \geq 19$ dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1, L, NCS
Slip resistance	EN 13893	$\mu \geq 0.30$
Body voltage	ISO 6365	< 2 kV
Installation	Tile	

Put Flotex in the spotlight and you'll discover its performance will never let you down. This unique flocked floor covering has been designed to handle high traffic and cleans up like new every time, without wearing or fading. It is well suited to areas where durability and cleanability are essential so there's no need to decide between functionality or style, why not have both with Flotex?



flotex® stratus


flotex® cirrus




t540003 | stratus sisal LRV 15



t570003 | cirrus sisal LRV 15



t540004 | stratus fossil LRV 13



t570004 | cirrus fossil LRV 14



t540006 | stratus ruby LRV 9



t570006 | cirrus ruby LRV 12



t540007 | stratus mint LRV 10



t570007 | cirrus mint LRV 10

Using European (EN) approved testing methodology we have graded every item in the collection on its ability to 'hide' dirt or staining that occurs during normal use depending on the application.

Usage classification

- Superior appearance rating
- Good appearance rating
- Moderate appearance rating



Cirrus t570003 | sisal

flotex® cityscape

The embossed lines in the Flotex Cityscape collection create an intriguing design that changes in the light from whatever angle you observe the floor. Inspired by the lines and intersections of the urban landscape the collection captures the reflection and the rhythm of the windows of the city's sky scrapers or the pattern of the street beneath them. The grid like patterns which are embossed in the Flotex nylon fibers create tactility as well as comfort and provide a third dimension to the floor. Discover and experience a whole new flooring concept with Flotex Cityscape.

flotex® integrity²

charcoal	t350003 50x50 cm t353003 50x25 cm t351003 embossed 50x50 cm t352003 embossed 50x25 cm	LRV 8%	grey	t350001 50x50 cm t353001 50x25 cm t351001 embossed 50x50 cm t352001 embossed 50x25 cm	LRV 8%	navy	t350004 50x50 cm t353004 50x25 cm t351004 embossed 50x50 cm t352004 embossed 50x25 cm	LRV 3%
steel	t350002 50x50 cm t353002 50x25 cm t351002 embossed 50x50 cm t352002 embossed 50x25 cm	LRV 4%	granite	t350012 50x50 cm t353012 50x25 cm t351012 embossed 50x50 cm t352012 embossed 50x25 cm	LRV 8%	marine	t350006 50x50 cm t353006 50x25 cm t351006 embossed 50x50 cm t352006 embossed 50x25 cm	LRV 7%

t350011 | integrity² leaf

Using European (EN) approved testing methodology we have graded every item in the collection on its ability to hide dirt or staining that occurs during normal use depending on the application.

- Usage classification**
- ☐ Superior appearance rating
 - ◐ Good appearance rating
 - Moderate appearance rating



flotex® complexity



Description	Flocked flooring	
Dimensions	Tile: 50cm x 50cm	
Total thickness	ISO 1765	5.0 mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	16	
Application	EN 1307	Class 33 heavy
Impact sound reduction	EN ISO 717-2	ΔLw = 19 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{f1} -s1, L, NCS
Slip resistance	EN 13893	μ ≥ 0.30
Body voltage	ISO 6365	< 2 kV
Installation	Tile	

charcoal	t550003 50x50 cm t553003 50x25 cm t551003 embossed 50x50 cm t552003 embossed 50x25 cm	LRV 10%	blue	t550007 50x50 cm t553007 50x25 cm t551007 embossed 50x50 cm t552007 embossed 50x25 cm	LRV 11%	grey	t550001 50x50 cm t553001 50x25 cm t551001 embossed 50x50 cm t552001 embossed 50x25 cm	LRV 9%
navy	t550004 50x50 cm t553004 50x25 cm t551004 embossed 50x50 cm t552004 embossed 50x25 cm	LRV 8%	marine	t550006 50x50 cm t553006 50x25 cm t551006 embossed 50x50 cm t552006 embossed 50x25 cm	LRV 7%	straw	t550010 50x50 cm t553010 50x25 cm t551010 embossed 50x50 cm t552010 embossed 50x25 cm	LRV 18%

flotex® planks

ombré

Strongly textile, subtly textured and shading from dark to light. The effect is one of deliberate contrasts, as the elements of the design mix with the format of plank. Ombré colours can easily be combined to make beautiful designs or used with their co-ordinating Montage colourways.



montage

The build-up of textures, with layer upon layer of blending and mixing structures, evolve into a complex pattern that gives Montage an elegant and contemporary feel. It can be used widely on its own or combined with Ombré to create inserts or zones.



frameweave

Inspired by rich woven fabric and combined with a graphical layout, the result creates both depth and movement as shapes form within the otherwise subtle design. The large choice of colours makes Frameweave a very versatile choice for designing stunning installations.



converge

Areas of pattern meet, joining at angles, creating different facets which contrast in shade or colour, forming abstract shapes and forms at random. Via their shared elements, all colours co-ordinate making this the perfect design for large areas requiring differentiation.



refract

A contrasting pattern made of textures formed by light, reflected and refracted across buildings. It has depth, movement and energy. It has been designed to ensure a perfectly random appearance, creating a stunning individual floor without the need for planning.



Flotex fulfils our ambition to contribute to creating better indoor environments by committing to the health and well-being of all individuals living and working in indoor spaces. Flotex achieves this through excellent hygiene and sound absorbing qualities, phthalate-free products, the certification by Allergy UK for the positive effects it has on allergy sufferers, and a wide range of stimulating designs and sympathetic colours which can create inspiring interiors.



FLOTEX PLANKS COLLECTION AT A GLANCE

triad

Based on the idea of a group of three lines, these geometric forms evolve becoming abstract and random, always familiar but never the same. Highly graphic and sophisticated in its design, the colourways can be combined or used individually, with or without co-ordinating accents.



box-cross

Subtly changing from a box to a cross, the motif seems to fade in and out creating light and shade that bring contrast and interest. The effect is both stylish and sophisticated, forming a unique visual look that works in both large and small areas.



seagrass

Organic but linear, naturally inspired and beautifully textured. A classic pattern with colours that can easily be mixed together in a variety of installation methods. Seagrass is versatile and understated, making it suitable for any environment.



concrete

Highlights of colour bring new life to this classic, offering a refreshing change to the normal by mixing fun with tradition. Use them on their own, together or with the classic Concrete colourways to design stunning individual floors.



marble

Classic and chic with an element of fun. To be mixed together or used individually to bring character or just challenge the senses. Marble brings something new, visually familiar yet texturally different, it aims to challenge perceptions and push boundaries.



wood

Inspired by natural wood, this familiar aesthetic takes on a new versatile guise offering a traditional look in an untraditional format. These wood patterns are beautifully detailed, look good individually and can be combined to create stunning flooring designs.



flotex® planks

ombré

Strongly textile, subtly textured and shading from dark to light. The effect is one of deliberate contrasts, as the elements of the design mix with the format of plank. Ombré colours can easily be combined to make beautiful designs or used with their co-ordinating Montage colourways.


Plank size
100 x 25 cm




Ombre 149004 | moraine



149007 | arctic LRV 11 149004 | moraine LRV 14




149006 | glacier LRV 11 149003 | tropic LRV 11




149008 | tundra LRV 13



149001 | boreal LRV 15




149002 | horizon LRV 10



149005 | estuary LRV 13

Description	Flocked flooring
Dimensions	100cm x 25cm (2.5m ² per box)
Total thickness	ISO 1765 5.0mm
Slip resistance	Pendulum test Wet – low slip risk
Collection size	94
Application	EN 1307 Class 33
Impact sound reduction	EN ISO 717-2 ΔLw = 19 dB
CE	EN 14041
Reaction to fire	EN 13501-1 B ₁ -s1, L, NCS
Slip resistance	EN 13893 DS: ≥0.30
Body voltage	EN ISO 10965 < 2 kV



flotex® planks

montage

The build-up of textures, with layer upon layer of blending and mixing structures, evolve into a complex pattern that gives Montage an elegant and contemporary feel. It can be used widely on its own or combined with Ombré to create inserts or zones.

Plank size
100 x 25 cm



Montage 147008 | tudra + Ombre 149008 | tundra



147007 | arctic LRV 8 147004 | moraine LRV 8



147006 | glacier LRV 7 147003 | tropic LRV 7

Description	Flocked flooring
Dimensions	100cm x 25cm (2.5m ² per box)
Total thickness	ISO 1765 5.0mm
Slip resistance	Pendulum test Wet – low slip risk
Collection size	94
Application	EN 1307 Class 33
Impact sound reduction	EN ISO 717-2 ΔLw = 19 dB
CE	EN 14041
Reaction to fire	EN 13501-1 B ₁ -s1, L, NCS
Slip resistance	EN 13893 DS: ≥0.30
Body voltage	EN ISO 10965 < 2 kV




147008 | tudra LRV 8




147001 | boreal LRV 9



147002 | horizon LRV 6



147005 | estuary LRV 8



Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.

flotex® planks frameweave

Inspired by rich woven fabric and combined with a graphical layout, the result creates both depth and movement as shapes form within the otherwise subtle design. The large choice of colours makes Frameweave a very versatile choice for designing stunning installations.



Frameweave 142004 | citrine + 142001 | pave + 142008 | pesto + 142006 | capri

Half-drop installation 1

Half-drop installation 2

Herringbone installation 1

Herringbone installation 2

Weave installation 1

Weave installation 2

Plank size
100 x 25 cm

Description	Flocked flooring	
Dimensions	100cm x 25cm (2.5m ² per box)	
Total thickness	ISO 1765	5.0mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	94	
Application	EN 1307	Class 33
Impact sound reduction	EN ISO 717-2	ΔLw = 19 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1, L, NCS
Slip resistance	EN 13893	DS: ≥0.30
Body voltage	EN ISO 10965	< 2 kV

Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.

Usage classification

- Superior appearance rating
- Good appearance rating
- Moderate appearance rating

flotex® planks converge

Areas of pattern meet, joining at angles, creating different facets which contrast in shade or colour, forming abstract shapes and forms at random. Via their shared elements, all colours co-ordinate making this the perfect design for large areas requiring differentiation.

Plank size
100 x 25 cm



Converge 141001 | prism + 141005 | radiant + 141006 | arc

Half-drop installation 1

Half-drop installation 2

Herringbone installation 1

Herringbone installation 2

Weave installation 1

Weave installation 2

Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.

Usage classification

- Superior appearance rating
- Good appearance rating
- Moderate appearance rating

flotex® planks

refract

A contrasting pattern made of textures formed by light, reflected and refracted across buildings. It has depth, movement and energy. It has been designed to ensure a perfectly random appearance, creating a stunning individual floor without the need for planning.



137004 | quartz LRV 5




137001 | obsidian LRV 6




137005 | topaz LRV 5



Description	Flocked flooring	
Dimensions	100cm x 25cm (2.5m ² per box)	
Total thickness	ISO 1765	5.0mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	94	
Application	EN 1307	Class 33
Impact sound reduction	EN ISO 717-2	ΔLw = 19 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1, L, NCS
Slip resistance	EN 13893	DS: ≥0.30
Body voltage	EN ISO 10965	< 2 kV



137002 | firoza LRV 6



137006 | malachite LRV 8



137003 | sapphire LRV 5

- Usage classification**
- Superior appearance rating
 - Good appearance rating
 - Moderate appearance rating

refract 137002 | firoza



Plank size
100 x 25 cm


flotex® planks

triad

Plank size
100 x 25 cm



Based on the idea of a group of three lines, these geometric forms evolve becoming abstract and random, always familiar but never the same. Highly graphic and sophisticated in its design, the colourways can be combined or used individually, with or without co-ordinating accents.



131005 | platinum LRV 9




131015 | stone LRV 18



131007 | steel LRV 9



131010 | taupe LRV 11




131008 | shadow LRV 6



131017 | anthracite LRV 5




121001 | embossed zinc LRV 8




131012 | blue line LRV 8




131006 | silver LRV 8



131013 | green line LRV 8



131014 | amber line LRV 8




131011 | red line LRV 9




131004 | amber LRV 12




131001 | red LRV 8



131002 | blue LRV 7



131003 | green LRV 10



Herringbone installation 2 Weave installation 1 Weave installation 2

Description	Flocked flooring	
Dimensions	100cm x 25cm (2.5m ² per box)	
Total thickness	ISO 1765	5.0mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	94	
Application	EN 1307	Class 33
Impact sound reduction	EN ISO 717-2	ΔLw = 19 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1, L, NCS
Slip resistance	EN 13893	DS: ≥0.30
Body voltage	EN ISO 10965	< 2 kV

flotex® planks


box-cross

Subtly changing from a box to a cross, the motif seems to fade in and out creating light and shade that bring contrast and interest. The effect is both stylish and sophisticated, forming a unique visual look that works in both large and small areas.




Plank size
100 x 25 cm

Description	Flocked flooring	
Dimensions	100cm x 25cm (2.5m ² per box)	
Total thickness	ISO 1765	5.0mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	94	
Application	EN 1307	Class 33
Impact sound reduction	EN ISO 717-2	ΔLw = 19 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B ₁ -s1, L, NCS
Slip resistance	EN 13893	DS: ≥0.30
Body voltage	EN ISO 10965	< 2 kV



Usage classification

- Superior appearance rating
- Good appearance rating
- Moderate appearance rating




flotex® planks

seagrass


Organic but linear, naturally inspired and beautifully textured. A classic pattern with colours that can easily be mixed together in a variety of installation methods. Seagrass is versatile and understated, making it suitable for any environment.



Plank size
100 x 25 cm



Description	Flocked flooring	
Dimensions	100cm x 25cm (2.5m ² per box)	
Total thickness	ISO 1765	5.0mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	94	
Application	EN 1307	Class 33
Impact sound reduction	EN ISO 717-2	ΔLw = 19 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B ₁ -s1, L, NCS
Slip resistance	EN 13893	DS: ≥0.30
Body voltage	EN ISO 10965	< 2 kV



Usage classification


- Superior appearance rating
- Good appearance rating
- Moderate appearance rating

Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.

flotex® planks

concrete

Highlights of colour bring new life to this classic, offering a refreshing change to the normal by mixing fun with tradition. Use them on their own, together or with the classic Concrete colourways to design stunning individual floors.





Concrete 139001 Cloud | 139003 + Smoke | 139002 Thunder



Plank size
100 x 25 cm

Description	Flocked flooring	
Dimensions	100cm x 25cm (2.5m ² per box)	
Total thickness	ISO 1765	5.0mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	94	
Application	EN 1307	Class 33
Impact sound reduction	EN ISO 717-2	ΔLw = 19 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1, L, NCS
Slip resistance	EN 13893	DS: ≥0.30
Body voltage	EN ISO 10965	< 2 kV



Full technical specifications are available at www.forbo-flooring.com

Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.

flotex® planks

marble


Classic and chic with an element of fun. To be mixed together or used individually to bring character or just challenge the senses. Marble brings something new, visually familiar yet texturally different, it aims to challenge perceptions and push boundaries.




Plank size
100 x 25 cm



marble 143004 | diano + 143003 | pietra



Description	Flocked flooring	
Dimensions	100cm x 25cm (2.5m ² per box)	
Total thickness	ISO 1765	5.0mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	94	
Application	EN 1307	Class 33
Impact sound reduction	EN ISO 717-2	ΔLw = 19 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1, L, NCS
Slip resistance	EN 13893	DS: ≥0.30
Body voltage	EN ISO 10965	< 2 kV



Full technical specifications are available at www.forbo-flooring.com

Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.

flotex® planks

wood

Inspired by natural wood, this familiar aesthetic takes on a new versatile guise offering a traditional look in an untraditional format. These wood patterns are beautifully detailed, look good individually and can be combined to create stunning flooring designs.



Plank size
100 x 25 cm

Description	Flocked flooring	
Dimensions	100cm x 25cm (2.5m ² per box)	
Total thickness	ISO 1765	5.0mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	94	
Application	EN 1307	Class 33
Impact sound reduction	EN ISO 717-2	ΔLw = 19 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1, L, NCS
Slip resistance	EN 13893	DS: ≥0.30
Body voltage	EN ISO 10965	< 2 kV



Wood 151001 | black wood + 151002 | grey wood + 151004 | american wood + 151006 | antique wood




151003 | silver wood LRV 31



151001 | black wood LRV 8



151002 | grey wood LRV 13



Half-drop installation 1




Half-drop installation 2



Herringbone installation 1



Herringbone installation 2



Double herringbone installation 1



Double herringbone installation 2



Weave installation 1



Weave installation 2



151004 | american wood LRV 15



151007 | english wood LRV 13



151006 | antique wood LRV 9



151008 | rustic wood LRV 9




151005 | red wood LRV 9

Usage classification

- Superior appearance rating
- Good appearance rating
- Moderate appearance rating

Full technical specifications are available at
www.forbo-flooring.com

Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.



Flotex Planks Wood 151007 | English wood

FLOORCOVERINGS CREATED BY

Forbo Flooring has been very privileged to team up with some amazing designers. Many have found inspiration from our advanced production methods which in many cases, allow high definition digital printing, enabling the designers to achieve an exact translation of their design vision.


flotex® BY STARCK®

Forbo Flooring Systems collaborated with visionary creator Philippe Starck in designing a highly innovative collection of floor covering systems: Flotex by Starck.



flotex® tibor

Forbo Flooring Systems has teamed up with Tibor Ltd. Tibor Reich, the creator of Tibor, was a man ahead of his time. Although these striking patterns date from the 1950's, they could have been designed yesterday.



flotex® sottsass

This exclusive design collaboration between Forbo and Sottsass Association was borne out of the desire to work with an innovative flooring technology and its precision HD printing brings to life the avant-garde designs that clearly carry the Sottsass signature.



mbstudio

Floorcoverings created by José Medina Galeote

José Medina Galeote is a Spanish artist who uses painting and other techniques to reflect on the creative process. By bringing his works of art right under our feet, José Médina Galeote explores new perspectives on various textures, such as textile and vinyl flooring.



Mac Stopa

by MAC STOPA

This collection is based on the idea of architectural modularity and the desire to organize the space around us in an architectural way. This is realised through the use of repetitive geometric forms, such as hexagons, trapezoids or braided structures which form the base of the collection.



flotex® BY STARCK®

Forbo Flooring Systems collaborated with visionary creator Philippe Starck in designing a highly innovative collection of floor covering systems: Flotex by Starck.

Philippe Starck created a collection of 3 systems, named **Vortex**, **Artist** and **Twilight**. Each of them comes in four separate parts that can be freely arranged to create patterns for your project that adapts to your needs and preferences.

Using a high definition digital printing technique with the dense fibre surface of Flotex flocked flooring, Starck's collection features unique patterns. By playing on scale and transition, each of the three systems challenges tradition and creates a new language in the perception of interior spaces and floor covering design.



Description	Flocked flooring
Dimensions	Roll width 2m Roll length ≤ 30m
Total thickness	ISO 1765 4.3mm
Slip resistance	Pendulum test Wet – low slip risk
Collection size	6
Application	EN 1307 Class 33
Impact sound reduction	EN ISO 717-2 ΔLw = 20 dB
CE	EN 14041
Reaction to fire	EN 13501-1 B ₁ -s1
Slip resistance	EN 13893 DS: ≥0.30
Body voltage	EN ISO 10965 < 2 kV



Our recommended adhesive for Flotex Tibor is 540 Eurosafe Special or 640 Eurostar Special. Full technical specifications are available at www.forbo-flooring.com



“Organised chaos of the wind on the field”

Philippe Starck



Vortex is a system of elements that are designed to transform the way we look at space. It provides a flexible solution to enable planning across large and small areas with patterns that freely mix and interchange allowing a contrast between large scale design and semi-plain texture. The Vortex design is available in 6 distinctive highlight colourways.



“Nothing replaces the painter’s hand”

Philippe Starck


Artist is a concept based on the transition of two textures that can be used either individually or together with one colour fading into another. The different parts provide a way of designing and planning space in a subtle but visually engaging way, creating a flow of colour that allows areas to be differentiated whilst maintaining a distinctive look and feel in a building.





“Eternal fight of night and day”
Philippe Starck

Twilight is a play on lights, shadows and colours. A design with two strong powerful and complementary sides ; one jewel like, bright and light and the other as a shadow of deep dark rich shades. They come together in a transition element that creates energy and impact making a bold statement that can both divide and link space simultaneously. The different parts allowing a mix and match flexibility across any size of installation.




TIBOR

ORIGINAL SINCE 1946

Tibor Reich, the creator of Tibor Ltd, received many important commissions, including textiles for the young Queen Elizabeth II and the Festival of Britain, and later for Concorde and the QEII. Renowned for his Deep Texture weaves, which were widely adopted by leading furniture manufacturers, such as G-Plan and Ercol, Tibor also excelled at printed fabrics, notably the highly-acclaimed Fotexur range.

A multi faceted artist, he also designed carpets, wallpapers, ceramics, tiles and vinyl flooring, all in his distinctive co-ordinated style.





Through focusing on texture and line, Tibor's detailed photograph of straw inspired this famous pattern from the Fotexur range. The photograph was taken in the spring sunshine to give the image greater definition and the design deliberately highlights the tonal contrast between light and dark. Co-ordinating broad stripes are available in two colourways.

TIBOR AND THE ART OF FOTEXUR

Hungarian émigré Tibor Reich (1916-1996) was one of the most prominent figures in the British post-war textile industry. A gifted artist and dynamic entrepreneur, he moved to the UK in 1937 to study at Leeds University. Tibor Ltd, the company he founded in 1946, was established at Clifford mill near Stratford-upon-Avon in Warwickshire, England. It was a leading brand throughout the 1950's and 60's.


Texture was the defining feature of Tibor's textiles. As well as his celebrated Deep Texture weaves, he produced arresting screen-printed curtain fabrics, known as texture Prints.

Most of the designs selected by Forbo are from Tibor's ground-breaking Fotexur collection, launched in 1957, winner of the Council of Industrial Design's inaugural Design Centre Award. The 'Fo' refers to photography, while 'texur' evokes texture, both key aspects of these designs.

Close-up photographs of organic materials, such as straw and bark, provided the starting point for Tibor's intriguing Fotexur patterns. A keen photographer, he drew inspiration from the natural world. His eye was attracted to relief patterns and tonal contrasts in unusual places, such as fissures in a dried up river bed. Tibor also photographed his own weaves and used these images in his designs.

The Fotexur process began by screen-printing the photograph on paper, before isolating a section of the image and cutting it into squares or strips. Patterns were created by rotating and re-arranging these repeated motifs in different formations to create energetic and rhythmic compositions. Tibor's bold choice of colour variations provided the final ingredient to these stimulating and eye-catching designs.

Printed on Forbo Flotex in vibrant colours, Tibor's innovative Fotexur designs have a timeless feel, despite dating back 70 years.



980211 | saffron



980203 | rust



980207 | marigold




980209 | autumn stripe



980206 | aqua




980202 | teal



980208 | marine




980210 | taupe



980204 | raspberry



980212 | grey stripe



980201 | lead



980205 | gunmetal

Description	Flocked flooring	
Dimensions	Roll width 2m Roll length ≤ 30m	
Total thickness	ISO 1765	4.3mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	12	
Application	EN 1307	Class 33
Impact sound reduction	EN ISO 717-2	ΔLw = 20 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B ₁ -s1
Slip resistance	EN 13893	DS: ≥0.30
Body voltage	EN ISO 10965	< 2 kV


All items in this range are made to order. Lead time on request.

flotex® tabor


mosaic




Tabor often incorporated richly-textured 'fancy yarns' into his weaves to create tactile effects. For this pattern Tabor photographed a sheer fabric made from slub yarn. The uniformity of the grid contrasts pleasingly with the randomness of the loops. Co-ordinating stripes available in two colourways.




Tabor Mosaic 980406 | aqua




980412 raspberry stripe




980403 | raspberry




980407 | tomato




980409 | citron




980402 | cornflower




980404 | lime




980406 | aqua




980411 | marine stripe




980405 | monochrome



980408 | stone



980410 | saffron



980401 | pewter



BREEAM ratings

Flotex Tabor – Flotex F200 HD sheet with PVC backing (EN1307)

	Commercial	Education	Health	Domestic	Retail (Durability)	Retail (Fashion)	Meets Ska criteria
Sheet	A	A	A	B	A	A+	✓

Description	Flocked flooring
Dimensions	Roll width 2m Roll length ≤ 30m
Total thickness	ISO 1765 4.3mm
Slip resistance	Pendulum test Wet – low slip risk
Collection size	12
Application	EN 1307 Class 33
Impact sound reduction	EN ISO 717-2 ΔLw = 20 dB
CE	EN 14041
Reaction to fire	EN 13501-1 B _{fl} -s1
Slip resistance	EN 13893 DS: ≥0.30
Body voltage	EN ISO 10965 < 2 kV

Our recommended adhesive for Flotex Tabor is 540 Eurosafe Special or 640 Eurostar Special. Full technical specifications are available at www.forbo-flooring.com.
Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.

All items in this range are made to order. Lead time on request.

flotex® tabor

quartz



The natural world provided a great source of inspiration for Tabor and he photographed it extensively. This pattern depicts the granular composition of rocks and pebbles.



Tabor Quartz 980101 | black

Description	Flocked flooring
Dimensions	Roll width 2m Roll length ≤ 30m
Total thickness	ISO 1765 4.3mm
Slip resistance	Pendulum test Wet – low slip risk
Collection size	6
Application	EN 1307 Class 33
Impact sound reduction	EN ISO 717-2 ΔLw = 20 dB
CE	EN 14041
Reaction to fire	EN 13501-1 B _{fl} -s1
Slip resistance	EN 13893 DS: ≥0.30
Body voltage	EN ISO 10965 < 2 kV

Our recommended adhesive for Flotex Tabor is 540 Eurosafe Special or 640 Eurostar Special. Full technical specifications are available at www.forbo-flooring.com




980106 | cornflower




980105 | orange




980103 | saffron



980102 | camel



980104 | white



980101 | black

All items in this range are made to order. Lead time on request.


flotex® tabor

tessello

This ingenious Tibor pattern has two distinct layers: a fine mesh in the background, overlaid with a fragmented larger scale-grid. Structured yet informal, its subtle textures create a highly effective low-key flooring design.



Tabor Tessello 980305 | ice




980308 | fuschia

980304 | tomato



980306 | marine




980302 | aqua

980303 | lime

Description	Flocked flooring	
Dimensions	Roll width 2m Roll length ≤ 30m	
Total thickness	ISO 1765	4.3mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	10	
Application	EN 1307	Class 33
Impact sound reduction	EN ISO 717-2	ΔLw = 20 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B ₁ -s1
Slip resistance	EN 13893	DS: ≥0.30
Body voltage	EN ISO 10965	< 2 kV

Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.



980301 | pewter

980305 | ice

980309 | stone

980310 | taupe



BREEAM ratings

Flotex Tibor – Flotex F200 HD sheet with PVC backing (EN1307)

	Commercial	Education	Health	Domestic	Retail (Durability)	Retail (Fashion)	Meets Ska criteria
Sheet	A	A	A	B	A	A+	✓

980307 | saffron

All items in this range are made to order. Lead time on request.

flotex® tabor


onyx

Although this pattern resembles marble, it was actually inspired by a photograph of cracked mud in the riverbed next to Tibor's Clifford Mill. One of his most famous Flotexur designs, it was originally used for a woven carpet called Padua, so it is particularly apt that it is now being used for decorative flooring once again. The majority of colourways work in pairs as positive and negative variations.



Tabor Onyx 980702 | pewter

Description	Flocked flooring	
Dimensions	Roll width 2m Roll length ≤ 30m	
Total thickness	ISO 1765	4.3mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	12	
Application	EN 1307	Class 33
Impact sound reduction	EN ISO 717-2	ΔLw = 20 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B ₁ -s1
Slip resistance	EN 13893	DS: ≥0.30
Body voltage	EN ISO 10965	< 2 kV




980702 | pewter

980703 | grey

980708 | smoke

980709 | stone



980701 | lime




980710 | moss



980712 | clay




980706 | honey



980704 | marine



980707 | mauve



980711 | taupe



980705 | heather

All items in this range are made to order. Lead time on request.

flotex® tiber

tweedy



Tiber was unusual as a textile designer in creating both printed and woven fabrics. This pattern was inspired by a photograph of one of his celebrated Deep Texture weaves, in which irregular slubby yarns were used to create tactile fabrics with textural variety and depth.



980509 | orange



980504 | flame




980513 | petrol



980514 | citron



980508 | lime



980511 | monochrome



980503 | aqua



980506 | stone



980502 | marine



980507 | grey



980510 | clay



980512 | raspberry



980501 | pewter



980505 | coffee



Tiber Tweedy 980504 | flame

Description	Flocked flooring
Dimensions	Roll width 2m Roll length ≤ 30m
Total thickness	ISO 1765 4.3mm
Slip resistance	Pendulum test Wet – low slip risk
Collection size	14
Application	EN 1307 Class 33
Impact sound reduction	EN ISO 717-2 ΔLw = 20 dB
CE	EN 14041
Reaction to fire	EN 13501-1 B _{fl} -s1
Slip resistance	EN 13893 DS: ≥0.30
Body voltage	EN ISO 10965 < 2 kV

Our recommended adhesive for Flotex Tiber is 540 Eurosafe Special or 640 Eurostar Special. Full technical specifications are available at www.forbo-flooring.com

Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.



BREEAM ratings

Flotex Tiber – Flotex F200 HD sheet with PVC backing (EN1307)

Sheet	Commercial	Education	Health	Domestic	Retail (Durability)	Retail (Fashion)	Meets Ska criteria
	A	A	A	B	A	A+	✓

All items in this range are made to order. Lead time on request.

flotex® tiber

arbor




Like all Tiber's Fotexur patterns, the starting point for this design was a crisp black and white photograph taken by the designer himself. The image, recording the rough striated bark of an oak tree, is ruggedly textural, providing the perfect foil for varied coloured overlays.



Tiber Arbor 980610 | cornflower


Description	Flocked flooring
Dimensions	Roll width 2m Roll length ≤ 30m
Total thickness	ISO 1765 4.3mm
Slip resistance	Pendulum test Wet – low slip risk
Collection size	12
Application	EN 1307 Class 33
Impact sound reduction	EN ISO 717-2 ΔLw = 20 dB
CE	EN 14041
Reaction to fire	EN 13501-1 B _{fl} -s1
Slip resistance	EN 13893 DS: ≥0.30
Body voltage	EN ISO 10965 < 2 kV



980606 aqua




980612 | saffron



980610 cornflower



980608 marigold



980602 marine



980603 moss




980601 | pewter



980605 | grey



980611 | taupe



980609 | stone



980607 | clay



980604 purple

All items in this range are made to order. Lead time on request.

flotex® tibor

atomic



This design, derived from a photograph of an atomic structure, symbolises the period known as the Atomic Age. Part of the Colatomic range, launched in 1960, it reflects Tibor's dual interests in colour and texture. It also reflects the impact of Abstract Expressionism, which was very popular in the art world at the time.



Tibor Atomic 980803 | monochrome



980803 | monochrome



980801 | raspberry



980804 | aqua



980802 | saffron

Description	Flocked flooring
Dimensions	Roll width 2m Roll length ≤ 30m
Total thickness	ISO 1765 4.3mm
Slip resistance	Pendulum test Wet – low slip risk
Collection size	4
Application	EN 1307 Class 33
Impact sound reduction	EN ISO 717-2 ΔLw = 20 dB
CE	EN 14041
Reaction to fire	EN 13501-1 B _{fl} -s1
Slip resistance	EN 13893 DS: ≥0.30
Body voltage	EN ISO 10965 < 2 kV



BREEAM ratings
Flotex Tibor – Flotex F200 HD sheet with PVC backing (EN1307)

Sheet	Commercial	Education	Health	Domestic	Retail (Durability)	Retail (Fashion)	Meets Ska criteria
	A	A	A	B	A	A+	✓

All items in this range are made to order. Lead time on request.

flotex® sottsass

At the crossroads of art, design and architecture, the work of Ettore Sottsass represents the birth of non-conformist Italian design, somewhere between the industrial and the experimental. A prominent figure in Italian design since the 1950's, this ingenious free thinker sought to explore every creative avenue with a non-conformist attitude that was both assuming and audacious.

Whether designer, architect, sculptor, artist or photographer, Ettore Sottsass has left his mark and his commitment in his global view of the environment and space, through his sculptures, jewellery, artwork, furniture, and industrial objects. Today, many designers and architects emulate his spiritual heritage, radical in its stance against functionalism.

The exclusive design collaboration with Flotex was borne out of the desire to work with an innovative flooring technology and its precision HD printing brings to life the avant guard designs that clearly carry the Sottsass signature.



Sottsass 990701 | terrazzo


flotex® sottsass

bacteria



Bacteria is a development of one of Ettore Sottsass' signature designs, created in the late 1970's, a forerunner of the current modern age of nano technology and genetic engineering. Optically challenging, the design is open to wide interpretation, close up amoebic forms sway and shift yet from afar it appears as a constellation of distant stars. Bacteria is available in 20 colourways.


Pattern repeat 200cm x 150cm.



Description	Flocked flooring	
Dimensions	Roll width 2m Roll length ≤ 30m	
Total thickness	ISO 1765	4.3mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	20	
Application	EN 1307	Class 33
Impact sound reduction	EN ISO 717-2	ΔLw = 20 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1
Slip resistance	EN 13893	DS: ≥0.30
Body voltage	EN ISO 10965	< 2 kV

Our recommended adhesive for Flotex Sottsass is 540 Eurosafe Special or 640 Eurostar Special. Full technical specifications are available at www.forbo-flooring.com

Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.



BREEAM ratings Flotex Sottsass – Flotex F200 HD sheet with PVC backing (EN1307)							
	Commercial	Education	Health	Domestic	Retail (Durability)	Retail (Fashion)	Meets Ska criteria
Sheet	A	A	A	B	A	A+	✓

Usage classification
 Superior appearance rating Good appearance rating Moderate appearance rating

All items in this range are made to order. Lead time on request.


flotex® sottsass

wool



The Wool design was conceived by Ettore Sottsass when he laid filaments of wool yarns, collected from various countries, onto a flat, coloured surface. It plays on the textures of the individual strands of the natural fibres to give a sense of depth and warmth to the floor along with a defined linear pattern that can dramatically shift the perspective of interior spaces. Wool is available in 12 colourways.

Pattern repeat 200cm x 150cm.



Description	Flocked flooring	
Dimensions	Roll width 2m Roll length ≤ 30m	
Total thickness	ISO 1765	4.3mm
Slip resistance	Pendulum test	Wet – low slip risk
Collection size	12	
Application	EN 1307	Class 33
Impact sound reduction	EN ISO 717-2	ΔLw = 20 dB
CE	EN 14041	
Reaction to fire	EN 13501-1	B _{fl} -s1
Slip resistance	EN 13893	DS: ≥0.30
Body voltage	EN ISO 10965	< 2 kV



BREEAM ratings Flotex Sottsass – Flotex F200 HD sheet with PVC backing (EN1307)						
	Commercial	Education	Health	Domestic	Retail (Durability)	Retail (Fashion)
Sheet	A	A	A	B	A	A+

Usage classification
 Superior appearance rating Good appearance rating Moderate appearance rating

Our recommended adhesive for Flotex Sottsass is 540 Eurosafe Special or 640 Eurostar Special. Full technical specifications are available at www.forbo-flooring.com
 Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.

All items in this range are made to order. Lead time on request.





flotex® sottsass

terrazzo



Terrazzo by Sottsass is a witty “twist” on the concept of Italian Terrazzo (a traditional flooring created several hundred years ago when Venetian workers found a use for discarded marble remnants). Sottsass Association has developed this idea to give the impression of a beautifully laid Mediterranean terrazzo floor. However, on closer inspection, the “chips” in Terrazzo are revealed as pieces of torn paper – each holding its own story – a shredded love letter or a business document? It’s left to the individual to decide and to create their own narrative. Terrazzo is available in 13 colourways.

Pattern repeat 200cm x 150cm.



Description	Flocked flooring
Dimensions	Roll width 2m Roll length ≤ 30m
Total thickness	ISO 1765 4.3mm
Slip resistance	Pendulum test Wet – low slip risk
Collection size	13
Application	EN 1307 Class 33
Impact sound reduction	EN ISO 717-2 ΔLw = 20 dB
CE	EN 14041
Reaction to fire	EN 13501-1 B _{fl} -s1
Slip resistance	EN 13893 DS: ≥0.30
Body voltage	EN ISO 10965 < 2 kV

All items in this range are made to order. Lead time on request.



Flotex Sottsass Terrazzo 990701



© Forbo / José Medina Galeote

José Medina Galeote is an artist who uses painting and other techniques to reflect on the creative process. In his work he first establishes themes sometimes stimulating, sometimes provoking, in which the roles of artist and spectator are interchangeable. In his deep reflection on art in general and on painting in particular, José Medina Galeote undertakes an optical experimentation building a particular aesthetic which distinguishes it, both stylistically and in terms of the ideas it carries. Within his work there are clear references to the minimal and conceptual art of the sixties as he raises the question of the very concept of representation reality.

In 2011 The Contemporary Art Centre of Málaga organized an exhibition of his work and has also exhibited in many renowned exhibitions, notably at the Centre Pompidou in Málaga. The collaboration of José Médina Galeote and the design teams of Forbo Flooring Systems gave birth to an unique collection of flooring in which the artist's creations are given a new dimension through the medium of flooring. By bringing his works of art right under our feet, José Médina Galeote explores new perspectives on various textures, such as textile and vinyl flooring. Thanks to high definition printing techniques, Forbo Flooring Systems can bring the creations of José Médina Galeote to life on any floor.

The choice of which type of flooring is up to you :

- The warmth and comfort of Flotex flocced textile
- The extreme resistance of Eternal compact heterogeneous vinyl
- The acoustic comfort of Sarlon 15 dB and 19 dB
- The ease and speed of installation of Modul'up 19 dB

CHOOSE THE TYPE OF FLOORING THAT SUITS YOUR PROJECT.

You can find all technical information about these product constructions on our website under

www.forbo-flooring.com/josemedinagaleote

flotex®



340000 | stripy man 70 x 94 cm



340001 | tiza blanco




340002 | tiza oscuro



340001F | tizia blanco 340002F | tizia oscuro 340000F | stripy man



340003 | dibujar



340006 | pizarra



340007 | lienzo



340004 | pastel



340005 | carboncillo

sarlon® | modul'up® | eternal®




340001 | tiza blanco



340003 | dibujar




340034 | labradonita



340002 | tiza oscuro



340033 | dibujar diapositivos



340006 | pizarra



340004 | pastel

Looking at the ground has never been so fun and intuitive.

José Medina Galeote



340005 | carboncillo

Albayzin


Scribble

Chalkboard

Patchwork

Bring art into the home, onto the floor, and let it interact fully with the furniture and decoration that adorn our homes.


José Medina Galeote



340012 | glifo



340024 | tinta



340013 | arpillera



340008 | origen



340019 | sepia



340014 | osier



340011 | vestigio



340020 | emaki




340015 | raffia



340009 | firma



340023 | brochazo




340016 | tejido



340010 | fuente




340022 | lapicera



340017 | fibras



340021 | lavis



340018 | malla



isla 340031



340025 | nacre



340031 | isla




340029 | aqua



340030 | atol



340027 | anemone



340026 | ambar

Sign

Angles

Dimension

Coralline

Reef




340031 | isla



340047 | noche




340048 | lapules azules




340041 | estructura gris



340049 | esmeralda



340040 | estructura gris azulada



340039 | estructura verde



mostaza 340044, verde oliva 340043



340043 | verde oliva



340038 | dunas



340040 | estructura gris azulada



340044 | mostaza



340036 | terra



340045 | naranja



340033 | ondas



340042 | azul cielo



340035 | ondas



340046 | negro oliva



340037 | purdo

Reef

Coralline

Dimension

Angles

Sign

The potential of a line to be concrete by the brush.

José Medina Galeote

CREATED BY JOSÉ MEDINA GALEOTE HIGH DEFINITION DIGITAL PRINTING

With over 20 years of experience in high definition digital printing, Forbo Flooring Systems offers you a range of high quality floor coverings, tailored to your needs. Whatever the segment or field of application, José Médina Galeote's creations will come to life under your feet!

CHOOSE THE TYPE OF FLOORING THAT SUITS YOUR PROJECT.


You can find all technical information about these product constructions on our website under www.forbo-flooring.com/josemedinagaleote

JM Studio

José Medina Galeote

	TEXTILE	ORDER ON DEMAND please contact your local sales for detailed information
flotex®	Flotex Flocked Flooring is a unique textile flooring that combines the hard wearing & durable characteristics of a resilient floor with the quality, warmth and comfort of a carpet. Discover the toughness and durability of Flotex which comes as a result of the 80 million nylon 6.6. fibres per m ² , while experiencing the quietness and comfort normally only associated with a carpet as a result of the impervious cushioned backing.	To order your floor as a flotex floor use the colour code from the flotex designs and add an « F ». So with 340004F you order design patchwork in the colour pastel in Flotex $\frac{340004}{\text{colour number}} \quad \frac{F}{\text{product type}} = 340004F$ Minimum order quantity: as of 6m²
sarlon®	Sarlon 15dB acoustic vinyl, the hybrid solution without compromise. Sarlon 15 dB is a unique flooring solution for areas with high acoustic and high load requirements. The Sarlon 19dB range is the perfect flooring solution for sound reduction. It offers the best possible acoustic properties along with a residual indentation that is best in class for acoustic flooring solutions.	To order your floor as a sarlon or modul'up floor use the colour code from the vinyl designs and add a suffix as indicated below: « T19 » for sarlon 19dB « T15 » for sarlon 15dB « UP19 » for modul'up 19dB « UPC » for modul'up compact So with 340004UP19 you order design patchwork in the colour pastel in Modul'up 19dB $\frac{340004}{\text{colour number}} \quad \frac{UP19}{\text{product type}} = 340004UP19$ Minimum order quantity: as of 30m²
modul'up®	Modul'up 19 dB loose lay vinyl is committed to the future. Modul'up is the best loose lay floor covering available for high traffic applications. It can be installed quickly without adhesives, and is even more time and cost efficient at time of replacement.	
eternal®	This vinyl sheet collection has been created to work across a wide variety of application areas. Create any desired atmosphere in every space. For every moment of the day Eternal offers the ideal solution: at work, school and in the gym.	To order your floor as eternal floor use the colour code from the vinyl designs and add an « E ». So with 340004E you order design patchwork in the colour pastel in Eternal $\frac{340004}{\text{colour number}} \quad \frac{E}{\text{product type}} = 340004E$ Minimum order quantity: as of 30m²





'As an architect, interior designer and designer of transmission forms, this collection is inspired by my experiences, observations and fascinations derived from a variety of design fields. These ideas have been visualised in partnership with Forbo Flooring through the medium of high resolution digital printing both on textile and vinyl substrates. Each one giving it's unique characteristics to my imagery.

I have based the collection on the idea of architectural modularity and the desire to organize the space around us in an architectural way. This is realised through the use of repetitive geometric forms, such as hexagons, trapezoids or braided structures which form the base of the collection.

My experience in Interior design has inspired me to combine those structures with the textures of classic interior materials such as wood, fabrics, metal and leather.

As a designer of industrial forms, I am fascinated by organic structures but also new technologies related to 3D printing. By combining these elements with the geometric shapes, the designs I have created achieve a quality of softness and three-dimensionality.

When designing, I like to experiment, I observe the beauty of nature and the physical phenomena that surround us. This often becomes the inspiration for new projects. A unique artistic interpretation.

Throughout the collection there is a recurrent theme based on the variable colours of adjacent modular forms. In nature this is associated with the refraction and absorption of light reflections. I have used it as a design tool, giving each pattern dimension and subtlety which, when combined with the traditional familiarity of modular patterning, creates an exciting fusion of classic form and 21st century technology.'

CHOOSE THE TYPE OF FLOORING THAT SUITS YOUR PROJECT. You can find all technical information about these product constructions on our website under www.forbo-flooring.com/macstopa




FLOWER



Geometric yet seemingly organic, Flower combines elements that both challenge and reassure us in a way that provokes thought and discussion blurring the space between nature and design.

360027E | knit

flotex®



360004 | grey jeans
360005 | stripes
360006 | linear beige
360007 | linear grey
360008 | woven
360009 | jute
360010 | flannel
360011 | indigo jeans

eternal®



360027 | knit
360029 | stripes XL
360010 | flannel
360028 | indigo jeans XL
360030 | light wood
360031 | honey wood

How to order the right product :
360010 F = 360010F
colour number product type*

The outcome of the colour differs per chosen product. The displayed design represents a space of 100 x 100 cm. *Find the right product code and product explanation on page 319.

TRAPEZOID

CREATED BY MAC STOPA



Mechanical and repetitive Trapezoid forms blend with recognisable material surfaces, each one playing with dimension and the perception of shape within the patterns context.

360018F | tweed

flotex®



eternal®



How to order the right product :
 360012 F = 360012F
 colour number product type*

The outcome of the colour differs per chosen product.
 The displayed design represents a space of 100 x 100 cm.
 *Find the right product code and product explanation on page 319.

WICKER

CREATED BY MAC STOPA



Based on the traditional structure of a woven form, Wicker transcends the ordinary by taking a range of textures that although familiar become exciting and unusual in the context of this juxtaposition.

360023F | jeans grey XS

360026E | jeans blue

flotex®



eternal®



How to order the right product :
 360020 F = 360020F
 colour number product type*

The outcome of the colour differs per chosen product.
 The displayed design represents a space of 100 x 100 cm.
 *Find the right product code and product explanation on page 319.




A seemingly bizarre synergy of conventional form with an unexpected twist, Hexagon is both curious and strangely compelling in a uniquely inspired way.

Flotex naturals
010078F | shaded oak
360001F | blue anemone

flotex®



360003 | fur cool



360001 | blue anemone




360002 | fur warm

eternal®



360003 | fur cool



360001 | blue anemone

CREATED BY MAC STOPA HIGH DEFINITION DIGITAL PRINTING

With over 20 years of experience in high definition digital printing, Forbo Flooring Systems offers you a range of high quality floor coverings, tailored to your needs. Whatever the segment or field of application, Mac Stopa's creations will bring the floor to life!

CHOOSE THE TYPE OF FLOORING THAT SUITS YOUR PROJECT.

You can find all technical information about these product constructions on our website under www.forbo-flooring.com/macstopa

	TEXTILE	ORDER ON DEMAND please contact your local sales for detailed information
flotex®	<p>Flotex Flocked Flooring is a unique textile flooring that combines the hard wearing & durable characteristics of a resilient floor with the quality, warmth and comfort of a carpet. Discover the toughness and durability of Flotex which comes as a result of the 80 million nylon 6.6. fibres per m2, while experiencing the quietness and comfort normally only associated with a carpet as a result of the impervious cushioned backing.</p>	<p>To order your floor as a flotex floor use the colour code from the flotex designs and add an « F ».</p> <p>So with 360010F you order design Flower in the colour flannel in Flotex</p> <div style="border: 1px solid black; padding: 5px; width: fit-content; margin: 10px auto;"> $\frac{360010}{\text{colour number}} \quad \frac{F}{\text{product type}} = 360010F$ </div> <p>Minimum order quantity: as of 6m²</p>

	VINYL	ORDER ON DEMAND please contact your local sales for detailed information
eternal®	<p>This vinyl sheet collection has been created to work across a wide variety of application areas. Create any desired atmosphere in every space. For every moment of the day Eternal offers the ideal solution in working, learning or relaxing environments. The balanced construction offers lowest residual indentation and the PUR Pearl finish brings the best protection against scuff and scratching.</p>	<p>To order your floor as eternal floor use the colour code from the vinyl designs and add an « E ».</p> <p>So with 360010E you order design Flower in the colour flannel in Eternal</p> <div style="border: 1px solid black; padding: 5px; width: fit-content; margin: 10px auto;"> $\frac{360010}{\text{colour number}} \quad \frac{E}{\text{product type}} = 360010E$ </div> <p>Minimum order quantity: as of 30m²</p>

How to order the right product :

$$\frac{360003}{\text{colour number}} \quad \frac{F}{\text{product type}^*} = 360003F$$

The outcome of the colour differs per chosen product.
 The displayed design represents a space of 100 x 100 cm.
 *Find the right product code and product explanation on page 319.



Flotex Vision | floral

Custom flooring

Can't find what you are looking for despite our wide product range? No worries, we have more. Within our Bespoke Design flooring you can design your own unique floor with our digital print techniques in Flotex, project vinyl and Coral entrance flooring and the refined Aquajet cutting technique for Marmoleum flooring.

Flotex vision

Forbo offers a unique Flotex collection of over 500 digitally printed designs in high level photographic resolutions. Flotex flocked flooring is a unique textile floor covering that combines the hard wearing and durable characteristics of a resilient floor with the comfort and warmth of a carpet.



Eternal bespoke

Our advanced digital printing technology enables striking floor visuals that cannot be achieved with conventional print techniques. It enables you to design your own unique floor in the high quality of our heterogeneous vinyl sheet flooring.



Designing with Marmoleum

Are you looking for something unique on your floor? That is also sustainable and durable? Our Designing with Marmoleum selection offers you just that. With our Aquajet technique we can create the most precise and detailed floor designs. From laser engraved Marmoleum tiles to exciting designs created by international designers. Explore your options below!



Coral logo entrance flooring

Great looks for a great welcome. Forbo offers a bespoke print and cut-out design service to create your own unique entrance mat. Forbo Coral Logo entrance flooring will retain its looks whilst keeping out dirt and moist for years to come



We have many options to customise your floor. This graph shows you the extensive possibilities, we invite you to visit our website and find out which solution fits you best or contact our local customer service department to help you out.

	Choose from a design library	Recolour option	Digital print custom design	Special shapes & cuts	Laser edging
Designing with textile	•	•	•	•	
Designing with vinyl	•	•	•	•	
Designing with marmoleum				•	•
Designing with the entrance systems			•	•	

Flotex vision & Eternal bespoke

The **digital** world of **Flotex** and **vinyl**

High definition digital print

With a smooth, velour like surface that looks and feels like a carpet, Flotex is the perfect textile substrate for vibrant designs and true to life visuals which can be produced in high level photographic resolution. All desired colour shades and hues can be achieved.



Fantastic effects

Digital print offers an infinite number of design options ranging from abstracts with intricate colour spectrums to realistic images of natural materials like sand, grass and water. Create 3D depth or a "trompe d'oeil" effect on your floor. Or bring nature into your room by choosing a floor covering with autumn leaves or flowers.

Endless design options

Digital printing is also well suited for those collections that require visual detail and effects that cannot easily be reached through conventional print. Our Flotex custom flooring collection contains more than 500 individual items.

Colour your own

Do you like the design, but you cannot find the colours you want?

A large number of designs can be recoloured to perfectly match the colour selection you prefer!

Bespoke design

You can also create something bespoke for a truly individual solution. Whether it be photography, commercial branding or specific Pantone references, we can work to match your requirements. We offer a bespoke design service on request, please contact your local sales representative for more information.


To view all our bespoke designs go to: www.forbo-flooring.com/customflooring



Floral



Linear



Textile | texture



Geometric | graphik



Organic




Natural world



Stone | ceramic



Statement



Designing with marmoleum



Are you looking for something unique on your floor? That is also sustainable and durable? Our Designing with Marmoleum selection offers you just that. With our Aquajet technique we can create the most precise and detailed floor designs. From laser engraved Marmoleum tiles to exciting designs created by international designers. Explore your options below!

To view all our bespoke designs go to: www.forbo-flooring.com/customflooring



Dare to Rug: 3257 | edelweiss, 3268 | honey suckle, 3872 | volcanic ash



Marmoleum Imagine

Did you know you can make the most refined floor designs with Marmoleum? For Marmoleum Imagine we asked 3 international designers to create a series of Marmoleum designs, made possible by our refined Aquajet cutting technique. The designs can be customized on request which allows for endless design possibilities. Get inspired by clicking through our digital magazine or read more below.



Marmoleum meets mendini

In close cooperation with the Italian architect and designer Alessandro Mendini we have created 3 unique Marmoleum designs that reflect his pointillist style: Proust, Harlekino and Plato. The 3 designs are available in a bright, contrasting variant and one of more subdued, greyish tones, both in the same geometric pattern. "The commission from Forbo Flooring gave me the opportunity to design a Proust floor in Marmoleum. The variations are keyed in such a way that they are easily recognisable and can be used one after the other."



Marmoleum Signature Tiles

Marmoleum Signature adds a unique feature to our Marmoleum tiles by adding light engraving themes to the linoleum. There are 4 engraving designs and for each design we've created a number of exciting floor plans. Watch the Marmoleum Signature video to see the design process of this unique laser engraved linoleum tile.



Marmoleum Tailor Made

With Marmoleum flooring you can make the most refined floor designs. Our very precise Aquajet cutting technique offers a sophisticated detailing in designs, perfect to create your own identity on your floor; a logo, a text, a piece of art. Or choose tailor made laser engraving, with which your own design can be lasered on the linoleum. Explore your possibilities below.



Coral logo entrance flooring



Great looks for a great welcome. Forbo offers a bespoke print and cut-out design service to create your own unique entrance mat. Forbo Coral Logo entrance flooring will retain its looks whilst keeping out dirt and moist for years to come

Your entrance flooring system can be enhanced by using Forbo's Coral Logo to express your company logo or identity. For this we offer:

- Highest functional performance on the market
- Unlimited possibilities
- Hassle free order process
- A Coral entrance system is an investment not a cost as it reduces the time spent cleaning the interior floor coverings by up to 65%
- Available in standard and custom dimensions

Where other logo mats tend to fade and get dirty very quickly, a Coral logo mat will retain its looks and continue to impress for many years because it has all the qualities and performance characteristics of our standard Forbo Coral products. The secret of its success is in the construction. Unlike many other bespoke mats, Coral logo is produced with high quality matt yarns which prevent tracking and soiling.

To view all our bespoke designs go to: www.forbo-flooring.com/customflooring



Choose your product

Depending on the colours and designs required to suit your corporate identity, you can make a choice between a printed or an inset logo mat. Please contact your local customer service department to find out how easy it is to personalise your entrance or promotion area or email info.bespokedesign@forbo.com.

Our recommended adhesive for Coral Logo is 540 Eurosafe Special. Full technical specifications are available at www.forbo-flooring.com
Please note: Digital representations may vary from the actual product. Please order a sample to see the full effect.

Inset logo mat (image above)

- Ideal for extreme traffic conditions and maximum functional performance
- Choose from any colour from the standard Forbo Coral ranges for the base background and logo colours
- Excellent performance because of Coral quality entrance matting
- Easy to combine as inlay in larger Coral installations

For more information on how to order the Coral Logo mats please contact your local Customer Service department.


Description	Cut pile entrance system	
Mat dimensions	55 x 90cm / 105 x 155cm 105 x 300cm / 155 x 197cm 155 x 300cm / 197 x 197cm 197 x 300cm	
Special mats	Up to 200cm wide and 600cm long (excluding edges)	
Total thickness	ISO 1765	Approx 8.0mm
Backing	EVERFORT® vinyl	
Yarn	100% polyamide	
Collection size	42 colours	
Application	EN 1307	Class 33
CE	EN 14041	<i>Note: The requirements of EN14041 do not apply to loose laid mats and rugs</i>
Reaction to fire	EN 13501-1	B _{fl} -s1
Slip resistance	EN 13893	DS: ≥0.30
Personal charging	ISO 6356	<2 kV



Printed logo mat

- Excellent visual quality and bright, attractive colours
- Perfect for complicated designs featuring multiple colours
- Choose from any of the colours shown above plus Pantone and RAL colour matching
- Stays flat on the floor, causing less trips, due to heavy vinyl backing
- Long lasting and high resistance to sun light.
- Excellent performance in removing dirt from your shoes.

The printed logo mat is available in 7 standard mat sizes (sizes with edges): 55x90, 105x155, 105x300, 155x205, 155x300, 205x205 & 205x300 (cm), and also in special sizes up to 192 cm wide (without edges).



Ammonite Hotel Amstelveen




Forbo's London EC1 showroom

FURTHER INFORMATION

Online services

Access Forbo 24/7 to find inspiration and information by visiting www.forbo-flooring.com or by following us on social media. To find out more, see page 320.



Our magazines

Interested in architectural stories and want to see some stunning projects, please check out our Archidea website.



Sample service

Forbo offers a next day sample service on commercial sample requests as we know how important it can be to see the actual material you are thinking of using. See page 323 to find out more.



Downloads (134)



All our brochures, technical specifications and installation instructions can also be downloaded – just click www.forbo-flooring.com/downloads. We've also got a FAQ section for when you need the answer quickly.

Installation and cleaning videos




In our Installation & Floorcare section you'll also find links to an ever increasing series of YouTube video guides – we're producing these for most of the products in our range to help your customers keep their floor coverings looking as good as the day they were installed. www.forbo-flooring.com/installation

BIM



Forbo Flooring Systems offers BIM objects of all its collections. The Forbo BIM files can be accessed through www.forbo-flooring.com/BIM


Forbo Floorplanner



With our floorplanner you can play with all our available floors. There are set roomsets in various segments or you can upload your own image to see how your future floor will look.

For more information, please visit www.forbo-flooring.com/floorplanner

References



If you are looking for inspiration by seeing how our customers use our products, or are looking for a specific product in a certain segment, please visit the 'Inspiration and references' page on our website www.forbo-flooring.com/references

Social Media

-  [@forboflooringsystems](https://www.facebook.com/forboflooringsystems)
-  [@forboflooring](https://twitter.com/forboflooring)
-  [@forboflooringsystems](https://www.instagram.com/forboflooringsystems)
-  [/forboflooring](https://www.pinterest.com/forboflooring/)
-  [forboflooringsystems](https://www.youtube.com/forboflooringsystems)
-  [company/forbo/](https://www.linkedin.com/company/forbo/)

EVERYTHING YOU NEED IN A COUPLE OF CLICKS

www.forbo-flooring.com


Please visit your local Forbo-Flooring website for information on the latest collections, inspiration and references, downloads, segment information as well as our sample ordering services.

OTHER INFORMATION.

Want to keep in touch with all the latest product and design trends in your sector? Simply register to any of our magazines via www.archidea.com

ArchIdea

Our global architects' magazine



SAMPLE SERVICE



We realize how important it is to physically see a product sample before purchasing our floor coverings. There are many ways to order larger sample formats. This can be done via email, via a contact to our customer service department, via our sales accountants and via the Forbo Flooring systems websites. Your samples will be dispatched the same day your request is made. You can also check with your local sales rep whether you can pick the samples up from a showroom or dealer near you.



Forbo Flooring Systems is part of the Forbo Group, a global leader in flooring and movement systems, and offers a full range of flooring products for commercial and affordable housing and new build markets. High quality linoleum, vinyl, textile, flocked and entrance flooring products combine functionality, colour and design, offering total flooring solutions for any indoor environment.

Forbo Flooring B.V.
P.O. Box 13
1560 AA Krommenie
The Netherlands
question@forbo.com
www.forbo-flooring.com

238925/012022

Find us on



creating better environments



FLOORING SYSTEMS